

Dr. Dobb's Journal of **Software Tools**

FOR THE PROFESSIONAL PROGRAMMER

**THE
BANDWIDTH
BOTTLENECK:**
Compressing
Image Data

Squeezing Text Files

Optimizing Integer
Multiplications

Webster's vs. K&R

80386 Resources

Languages:

C Text Formatter
Object-Oriented LISP
BASIC Modules and Libraries
Assembly vs. High-Level Languages



0 38351 16562 8

03



BOB STANTON HAD A GREAT IDEA. AN HOUR LATER HE WAS TESTING IT.

Appointments. Everybody takes them — dentists, auto-body shops, dance instructors. And lots of computer applications need appointment screens.

Bob thought that a calendar made a terrific graphic metaphor for taking appointments. Simply use the arrow keys to pick an open date, then press the Enter key, and up pops an appointment window.

Lucky for Bob, he's a CLARION programmer, one of a fast growing cadre of super-productive application developers.

With CLARION's Screener utility, he painted a white calendar on a black background. Then he drew a white-on-blue track around the page and between the days. He typed in the days of the week — and *voila!* — a calendar!

CLARION knows that a PC monitor is refreshed from memory, so it treats a screen layout like a group of variables. Just move data to a screen variable, and it shows up on the monitor.

Bob set up dimensioned screen variables for the days of the month and a screen pointer for selecting a date, and he was done. Then Screener generated the code.

Then Bob drew the appointments window, built an appointment file, filled in the connecting code and tested it — **ONE HOUR AFTER HE STARTED!**

Testing was a breeze. Screener doesn't just write code, it compiles your source, displays a screen, gets the changes, then replaces the old code in your program.

So here are Bob's appointment screens. You can see the source listing to the right. We marked all the code Screener wrote for him.

| SUNDAY | MONDAY | TUESDAY | WEDNESDAY | THURSDAY | FRIDAY | SATURDAY |
|---------------------|-----------------|--|-------------------------------|---|-------------------------------|------------------|
| | | | 1 AM: Booked PM: Booked | 2 AM: Booked PM: Booked | 3 AM: Booked PM: Not In | 4 |
| 5 | 6 AM: Booked | 7 AM: Booked PM: Booked | 8 AM: Booked | 9 AM: Booked | 10 PM: Not In | 11 |
| 12 | 13 | 14 | 15 | 16 | 17 | 18 |
| 19 Easter Sunday | 20 | APPOINTMENTS FOR APR 9, 1987 THURSDAY | | | | 21 AM: Booked |
| 22 | 23 | 9:00 J. Cohen 9:30 -same- 10:00 -same- 10:30 G. Fredricks 11:00 K. Lundstrom 11:30 -same- 12:00 Lunch - Rotary 12:30 -same- | 24 | 1:00 -same- 1:30 P. Roth 2:00 L. Henson 2:30 3:00 3:30 4:00 C. Stanley 4:30 -same- | 25 | 26 |

| SUNDAY | MONDAY | TUESDAY | WEDNESDAY | THURSDAY | FRIDAY | SATURDAY |
|---------------------|-----------------|---------|-------------------------------|-------------------------------|-------------------------------|----------|
| | | | 1 AM: Booked PM: Booked | 2 AM: Booked PM: Not In | 3 AM: Booked PM: Not In | 4 |
| 5 | 6 AM: Booked | 7 | 8 | 9 AM: Booked | 10 PM: Not In | 11 |
| 12 | 13 | 14 | 15 | 16 Good Friday | 17 | 18 |
| 19 Easter Sunday | 20 | 21 | 22 | 23 | 24 PM: Not In | 25 |
| 26 | 27 | 28 | 29 | 30 | | |

WHY CLARION?

Why are application developers everywhere changing to CLARION?

Because CLARION gives you all the tools you need: a coupled compiler and editor; screen, report, and help generators; an import/export utility; a sort/backup/restore utility; a formatted file dump; a DOS shell — and much more.

Because with CLARION's comprehensive data management routines, records can be locked and files shared on Novell®, 3COM®,

IBM® PC Net & Token Ring, Multi Link®, and most other networks.

Because CLARION is *not* hardware locked or copy protected. Run-time systems are *free* and soon you will be able to translate CLARION into native machine code (.EXEs).

And best yet, the price of CLARION v1.1 is just \$395 plus shipping and handling.

You'll need an IBM PC or true compatible with 320KB of memory and a hard disk drive. CLARION v1.1 also comes with a 30-day money back guarantee.

So call now and order CLARION v1.1. or ask for our detailed 16-page color brochure and reprints of major reviews.

800/354-5444

CLARION®

from BARRINGTON SYSTEMS, INC.

150 EAST SAMPLE ROAD

POMPANO BEACH, FLORIDA 33064

305/785-4555

Copyright 1986 Barrington Systems, Inc. CLARION is a registered trademark of Barrington Systems, Inc. IBM is a registered trademark of International Business Machines Corporation. Novell is a registered trademark of Novell, Inc. 3COM is a registered trademark of 3COM Corporation. Multi Link is a registered trademark of Software Link, Inc. Dept. A9

Circle no. 115 on reader service card.

TRANSFORM YOUR PC INTO A LISP MACHINE.



Not long ago, a specialized LISP machine was your only choice for serious AI development and delivery.

But now you can get LISP machine performance out of that ordinary IBM PC* sitting on your desk. With the **Gold Hill 386 LISP System**.

You simply plug in the System's HummingBoard™—unique 386-based hardware designed specifically for the LISP environment. Then you add the System's Golden Common LISP 386 Developer software.

That's all you need to transform your PC into a LISP machine. You can develop and deliver AI applications on your PC. And create your own expert systems. You'll get the kind of LISP performance you thought was only possible in a system costing ten times as much.

And if you don't need the whole system, Gold Hill can still offer you AI solutions. You can get GCLISP 286 Developer software for your PC.* And GCLISP 386 Developer software will be available for leading manufacturers' 386-based PCs.

Tomorrow's AI development tools for PCs are available today from Gold Hill. We'll prove it to you—just call to get the latest Gabriel Performance Benchmarks. You'll be amazed to learn what your PC is capable of. Call toll-free:

Gold Hill. The expert in AI on PCs.

1-800-242-LISP

*The Gold Hill 386 LISP System requires an IBM PC XT, AT or compatible. GCLISP 286 Developer Software requires an IBM PC AT or compatible.
© 1986 Gold Hill Computers, Inc. Gold Hill, Gold Hill 386 LISP System, Golden Common LISP, GCLISP, and Developer are trademarks of Gold Hill Computers, Inc. IBM PC, XT and AT are registered trademarks of International Business Machines Corp. HummingBoard is a trademark of A.I. Architects, Inc.

Circle no. 291 on reader service card.



In Mass.: (617) 492-2071
Gold Hill Computers, Inc.
163 Harvard St.,
Cambridge, MA 02139



NEW! FROM BLAISE COMPUTING

Today's programmers need more than yesterday's tools. Requirements such as removable windows and "sidekickable" pop-up utilities are changing the face of program design. You need to filter interrupts so that other resident programs still work. You need the ability to switch between multiple display pages and monitors. Today's technical demands are almost endless, but **C TOOLS PLUS** gives you what you need.



SOLID LIBRARY SUPPORT

Blaise Computing offers you solid library support that can meet all your demands and more. **C TOOLS PLUS** embodies the full spectrum of general-purpose utility functions that are critical to today's applications.

Here's just part of the PLUS in C TOOLS PLUS:

- ◆ **C TOOLS** and **C TOOLS 2** compatibility — two packages that receive rave reviews for quality, organization, usability and documentation.
- ◆ **FULL SOURCE CODE**

C Tools PlusTM For The Programmer Whose Alphabet Begins & Ends With "C"



- ◆ **WINDOWS** that are stackable, removable, that support word wrap and that can accept user input.
- ◆ **INTERRUPT SERVICE ROUTINE** support for truly flexible, robust and polite resident applications.
- ◆ **MULTIPLE** monitor and display support, including EGA 43-line mode.
- ◆ **FAST DIRECT VIDEO ACCESS** for efficiency that will not constrain good program design.
- ◆ **DOCUMENTATION, TECHNICAL SUPPORT** and attention to detail that have distinguished Blaise Computing products over the years.

C TOOLS PLUS supports the Microsoft (and IBM) 3.00 and Lattice 3.00 C compilers and is just **\$175.00**.

Also Available Are:
C VIEW MANAGER — A kit for building data entry screens and menus. Begin by designing on-screen what the operator will see; call upon our library functions from your program to display the screens and retrieve the data. Just \$275, including all library source code.

C ASYNCH MANAGER — provides the crucial core of hardware interrupt support needed to build applications that communicate. It

also includes the "XMODEM" file-transfer protocol and support for Hayes-compatible modems. All source code is included for \$175. **C TOOLS & C TOOLS 2** — an indispensable combination still available at a low price of \$175, including all source code. See review in PC Tech Journal, 6/85.

BLAISE COMPUTING INC.

2560 Ninth Street, Suite 316 Berkeley, CA 94710 (415) 540-5441

ORDER TOLL-FREE 800-227-8087!

YES, send me the PLUS I need! Enclosed is \$_____ for
C TOOLS PLUS. (CA residents add 6½% Sales Tax. All domestic
orders add \$10.00 for Federal Express shipping.)
Name: _____ Phone: (____) _____
Shipping Address: _____ State: _____ Zip: _____
City: _____ Exp. Date: _____
VISA or MC #: _____

ARTICLES

Compressing graphic data ➤**BANDWIDTH: Compressing Image Data with Quadtrees** 16*by Ronald G. White*

Ronald describes how a quadtree, a tree data structure that can have four child nodes for each node, can be used in a recursive scheme for compressing image data.

Squeezing text ➤**BANDWIDTH: ARC Wars: MS-DOS Archiving Utilities** 26*by Russell Nelson*

Archiving (compressing) text files saves disk space and, when transferring files between systems, saves time. Russell compares and contrasts several ARC programs that are available in the MS-DOS world.

Fast multiplication ➤**BANDWIDTH: Optimizing Integer Multiplications by Constant Multipliers** 34*by Robert D. Grappel*

A simple and nearly optimal algorithm to speed up that time-consuming operation—integer multiplication.

COLUMNS

What's wrong with K & R ➤**C CHEST** 96*by Allen Holub*

Allen continues the description of his nroff-like text editor, nr. In the Flotsam and Jetsam section, he takes Kernighan and Ritchie to task for their eccentric definitions of some common words.

80386, assembly, and more ➤**16-BIT SOFTWARE TOOLBOX** 110*by Ray Duncan*

It's the usual eclectic collection of fun and useful facts from Ray and his readers this month, including sources of information on the 80386 and assembly languages, a hint about writing adapting I/O routines, and a letter from a reader countering Ray's attacks on high-level languages.

STRUCTURED PROGRAMMING 120*by Namir Clemment Shammis*

Namir compares three flavors of BASIC: True BASIC, BASICA, and QuickBASIC.

Object-oriented programming ➤**ARTIFICIAL INTELLIGENCE** 126*by Ernest R. Tello*

Ernie gives us an overview of object-oriented LISP and talks with some LISP mavens about the future of the language.

FORUM

Channel capacity ➤**EDITORIAL** 6*by Michael Swaine***RUNNING LIGHT** 8*by Nick Turner***ARCHIVES** 8**LETTERS** 10*by you***DDJ ON LINE** 136**SWAINE'S FLAMES** 152*by Michael Swaine*

PROGRAMMER'S SERVICES

THE STATE OF BASIC: 138

A look at how the "new wave" BASICs support user-defined libraries.

OF INTEREST: 142

New products out there

ADVERTISER INDEX: 151

Where to find those ads

**About the Cover**

It's easy to reduce the size of a file so you can transmit it more quickly. The trick is to do it in such a way that you can recreate the original file on the other end.

This Issue

Given a fixed-capacity channel and a quantity of information to transfer, how do you move more information down the channel per unit of time than the channel will support? That apparently impossible challenge is the bandwidth problem, a topic that we intend to address in various ways throughout 1987. The expanded, extended, or otherwise enlarged memory space of today's microcomputers, in conjunction with the processing power of CPUs such as the 80386 and 68020, only makes the information bottlenecks in computer systems all the more apparent. Two solutions to the bandwidth dilemma lead off this issue.

Next Issue

In the area of artificial intelligence, expert systems are now old hat. The next area of growth in AI must be in techniques that allow the program to acquire new information—to learn. Our annual AI issue will include an implementation of a classic expert system, but it will also look forward with an example of software that mirrors the structure of the brain and learns by experience, much as clusters of neurons may learn.

➤ bandwidth topic

➤ entry point

IS GETTING THE ANSWER TO SOFTWARE PROBLEMS A BIGGER PROBLEM THAN THE PROBLEM?

Don't stay on hold when there's help online from CompuServe® Software Forums.

prompt, written answers to your specific problems. You can even talk with the actual software developers.

frequently publish software reviews. And you can find help for many other software products in our other computer-related forums for IBM®, Tandy®, Atari®, Apple®, Commodore®, TI® and others.

The last thing you need when you've got a software problem is a bigger problem getting answers. So, from now on, get prompt, informed answers on CompuServe Software Forums.

To buy your CompuServe Subscription Kit, see your nearest computer dealer. Suggested retail price is \$39.95.

To order direct or for more information, call 800-848-8199 (in Ohio, 614-457-0802).

If you're already a CompuServe subscriber, just type **GO SOFTWARE** at any ! prompt.

Adobe Systems®, Aldus®, Ashton-Tate®, Autodesk®, Borland International®, Creative Solutions®, Digital Research®, Living Videotext®, Lotus® Inc., Microsoft®, MicroPro®, Misosys Inc.® and Software Publishing® all have CompuServe Software Forums. And we keep adding more.

CompuServe's large subscriber base also puts you in touch with thousands of other, often more experienced, users of the same software. You'll find they can give you lots of creative ways to get the most out of your software.

And software forums are the best way to learn about product updates, new product announcements, new ways to expand the uses of your software, and offer free uploads of your own programs.

Our online electronic magazines

You've chucked the manual, because you've done exactly what it tells you to do six times already. So you call the software company.

Now you spend half a day beating your head against a brick wall of busy signals, ranting at recorded messages, hanging around on hold. And you still don't get the solution to your problem.

Meanwhile, progress is stopped and your profits are dribbling away. But wait. There's help...

Several prominent, progressive software publishers recognize this problem, and working with CompuServe, have developed a solution—CompuServe Software Forums.

Now you can go online with experts from the companies that produced your software and get

The new upgraded version of your software locks up. And every time you reboot, you get stuck in the same place in the program.

CompuServe®

Information Services, P.O. Box 20212
5000 Arlington Centre Blvd., Columbus, OH 43220

An H&R Block Company

Circle no. 237 on reader service card.

Btrieve®

The Programmer's Choice.

When you're serious about application development, there's just one choice for file management: Btrieve. With what *Computer Language* calls "near mainframe functionality", Btrieve sets the file management standard for PC applications. With Btrieve loaded in your PC, your programs can use simple subroutine calls to retrieve, store and update records.

B-tree based for high performance. Performance is all-important, especially as your database grows. That's why Btrieve implements the b-tree file structure—the fastest, most efficient method of accessing data.

Interfaces to C, BASIC, Pascal, COBOL. Don't waste time programming in awkward fourth generation languages! With Btrieve, simply use the languages you know best—and write applications the right way. Over 15 language interfaces available.

Help is just a phone call away. Need technical support? You've got it! Btrieve users receive 30 days of unlimited phone support at no charge. This "Direct Connect" policy is renewable for a full year at low cost. And try SoftCraft's free bulletin board for technical tips, seven days a week.

Fault tolerant. Btrieve insures against database disasters. Two levels of fault tolerance guarantee data integrity during accidents or power failures—even if lightning strikes. No extra programming required.

Multi-user versions for LANs and Xenix. When your applications need to network, count on Btrieve. A single version runs on all DOS 3 LANs, including IBM PC Network and Novell Advanced Netware. Btrieve is also available for Xenix and multitasking operating systems such as MultiLink Advanced, Microsoft Windows and IBM Topview.

Built-in security features. Lock up sensitive data with Btrieve's password protection and unique data encryption scheme—especially useful in local area networks.

Thorough documentation, easy implementation. Getting started with Btrieve is easy: the manual is packed with examples of every Btrieve function in BASIC, Pascal, COBOL and C.

Database queries, report writing. Add Xtrieve™ to your Btrieve applications for a fully-relational DBMS. Xtrieve's menu-driven interface gives your users the on-line query capabilities they need—without programming. Add our report writer option to produce custom reports and forms.

No royalties. Need we say more?




SoftCraft

P.O. Box 9802 #917 Austin, Texas 78766 (512) 346-8380 Telex 358 200


Suggested retail prices: Btrieve, \$245; multi-user Btrieve, \$595; Xtrieve, \$245; multi-user Xtrieve, \$595 (for report generation, add \$145 for single-user and \$345 for multi-user). Available from SoftCraft and selected distributors. Requires PC-DOS or MS-DOS 2.X, 3.X, Xenix. Btrieve is a registered trademark and Xtrieve is a trademark of SoftCraft Inc. ¹From Computer Language, November 1985.

Looking back, I can see that it was shortly after I started commuting from Santa Cruz into Silicon Valley that I began to see the importance of the bandwidth problem. Squeezing in with thousands of other commuters through the mountain pass to fight my way across Silicon Valley and up crowded Highway 101 got me thinking about channel capacity.

There are interesting similarities and relationships between transportation bottlenecks and the information-transmission bottlenecks that I believe represent the greatest challenge for programmers in the next decade. Just as data can be organized into packets, commuters can be packed up in trains or car pools to increase their transmission rate and decrease the frequency of collisions. The vehicular capacity of a highway really is a form of channel bandwidth. And anyone who has fallen into a web of one-way streets such as Berkeley's has something to say about network topology.

Relationships between transportation and communication are important when you consider trading one off against the other. At *DDJ* we have been, in a limited way, exploring the benefits of telecommuting. (I'm referring to the exchange of the costly movement of bodies for the lower-cost transmission of bits—not driving with a telephone at your ear, which so many of my fellow commuters are doing and which could also be called telecommuting.) I'm skeptical about how closely people can work together at physical long distance, but I'm willing to experiment because the cost of transportation, particularly the cost in time, is so great.

That cost will not go down, the world's transportation bottlenecks are only going to get worse, and there



is little to indicate that anyone is thinking very hard about what technological fixes there may be.

It would seem that we are closer to solutions to communications bottlenecks: we have seen the development of communications satellites, computer networks, and sophisticated routing software for voice and data. The picture phones of science fiction exist today. (See Swaine's *Flames*, page 152.)

In contrast, science fiction's visions of future transportation are further from realization. I did recently drive a car equipped with an impressive computerized navigation system from Etak Inc., of Menlo Park, but innovation like this in the area of consumer transportation is rare. Cars are still cars, highways are still highways, and traffic is still a battleground of a thousand conflicting desires. Maybe society can no longer afford the luxury of our current driving habits in constricted channels like Highway 101, and cars and highways should be modified to permit centralized control and routing. It's not such a radically ambitious notion, given the context of *Star Wars*, and it's a lot more down-to-earth.

This little peninsula with its runaway population growth and its wealth of technical expertise seems like the ideal place for the experiment to begin.

Staccato signals of constant information. . .

These are the days of miracle and wonder

This is the long distance call

—Paul Simon

Michael Swaine

Michael Swaine
editor-in-chief

Dr. Dobb's Journal of Software Tools

FOR THE PROFESSIONAL PROGRAMMER

Editorial

Editor-in-Chief Michael Swaine
Editor Nick Turner
Managing Editor Vince Leone
Assistant Editors Sara Noah Ruddy
Levi Thomas

Technical Editor Allen Holub
Contributing Editors Ray Duncan
Michael Ham
Bela Lubkin
Nimir Shammias
Ernest B. Tello
Rhoda Simmons

Copy Editor Production

Production Manager Bob Wynne
Art Director Michael Hollister
Assoc. Art Director Joe Sikoryak
Typesetter Jean Aring
Cover Photographer Michael Carr
Circulation
Circulation Director Maureen Kaminski
Newsstand Sales Mgr. Stephanie Barber
Book Marketing Mgr. Jane Sharninghouse
Circulation Coordinator Kathleen Shay

Administration

Finance Director Kate Wheat
Business Manager Betty Trickett
Accounts Payable Supv. Mayda Lopez-Quintana
Accts. Receivable Supv. Laura Di Lazzaro

Advertising Director

Robert Horton (415) 366-3600
Account Managers
Lisa Boudreau (415) 366-3600
Gary George (404) 897-1923
Michele Perkins (317) 875-8093
Michael Wiener (415) 366-3600
Cynthia Zuck (718) 499-9333
Promotions/Srvcs. Mgr. Anna Kittleson
Advertising Coordinator Charles Shively

M&T Publishing Inc.

Chairman of the Board Otmar Weber
Director C.F. von Quadt
President and Publisher Laird Foshay
Associate Publisher Michael Swaine

Dr. Dobb's Journal of Software Tools (USPS 307690) is published monthly by M&T Publishing Inc., 501 Galveston Dr., Redwood City, CA 94063; (415) 366-3600. Second-class postage paid at Redwood City and at additional entry points.

Article Submissions: Send manuscripts and disk (with article and listings) to the Editor.

DDJ on CompuServe: Type GO DDJ

Address Correction Requested: Postmaster: Send Form 3579 to *Dr. Dobb's Journal*, P.O. Box 27809, San Diego, CA 92128. **ISSN 0888-3076**

Customer Service: For subscription problems call: outside CA (800) 321-3333; in CA (619) 485-9623 or 566-6947. For book/software order problems call (415) 366-3600.

Subscriptions: \$29.97 per 1 year; \$56.97 for 2 years. Canada and Mexico add \$27 per year airmail or \$10 per year surface. All other countries add \$27 per year airmail. Foreign subscriptions must be prepaid in U.S. funds drawn on a U.S. bank. For foreign subscriptions, TELEX: 752-351.

Foreign Newsstand Distributor: Worldwide Media Service Inc., 386 Park Ave. South, New York, NY 10016; (212) 686-1520 TELEX: 620430 (WUD).

Entire contents copyright © 1987 by M&T Publishing, Inc., unless otherwise noted on specific articles. All rights reserved.

People's Computer Company

Dr. Dobb's Journal of Software Tools is published by M&T Publishing Inc. under license from People's Computer Company, 2682 Bishop Dr., Suite 107, San Ramon, CA 94583, a nonprofit corporation.



E=M C AZTEC

Our thanks to NASA for supplying this computer enhanced ultraviolet photo taken by Skylab IV of a solar prominence reaching out 350,000 miles above the sun's surface

Genius Begins With A Great Idea ...

But The Idea Is Just The Beginning

What follows is the time consuming task of giving form and function to the idea.

That's why we concentrate on building into our software development systems functions and features that help you develop your software ideas in less time and with less effort.

We've started 1987 by releasing new versions of our MS-DOS, Macintosh, Amiga, ROM, and Apple II C development systems. Each system is packed with new features, impressive performance, and a little bit more genius.

Aztec C86 4.1

New PC/MS-DOS • CP/M-86 • ROM

Superior performance, a powerful new array of features and utilities, and pricing that is unmatched make the new Aztec C86 the first choice of serious software developers.

Aztec C86-p Professional System . . . \$199

• optimized C with near, far, huge, small, and large memory + Inline assembler + Inline 8087/80287 + ANSI support + Fast Float (32 bit) + optimization options • Manx Aztec 8086/80x86 macro assembler • Aztec overlay linker (large/small model) • source level debugger • object librarian • 3.x file sharing & locking • comprehensive libraries of UNIX, DOS, Screen, Graphics, and special run time routines.

Aztec C86-d Developer System . . . \$299

• includes all of Aztec C86-p • Unix utilities make, diff, grep • vi editor • 6+ memory models • Profiler.

Aztec C86-c Commercial System . . . \$499

• includes all of Aztec C86-d • Source for library routines • ROM Support • CP/M-86 support • One year of updates.

Aztec C86 Third Party Software

A large array of support software is available for Aztec C86. Call or write for information. The following is a list of the most requested products: Essential Graphics • C Essentials • C Utility Library • Greenleaf Com. • Greenleaf General • Halo • Panel • PC-lint • PforCe • Pre-C • Windows for C • Windows for Data C terp • db Vista • Phact • Plink86Plus • C-tree.

CP/M • TRS-80 • 8080/Z80 ROM

C compiler, 8080/Z80 assembler, linker, librarian, UNIX libraries, and specialized utilities.

Aztec C II-c (CP/M-80 & ROM). \$349

Aztec CII-d (CP/M-80) \$199

Aztec C80 (TRS-80 3&4) \$199

Aztec C68k/Am 3.4

New Amiga Release

Amiga user groups across the USA voted Aztec C68k/Am release 3.3 the best Software Development System for the Amiga. Release 3.4 is more impressive.

Aztec C68k/Am-p Professional \$199

A price/feature/performance miracle. System includes: optimized C • 68000/680x0 assembler • 68881 support • overlay linker • UNIX and Amiga libraries • examples.

Aztec C68k/Am-d Developer \$299

The best of Manx, Amiga, and UNIX. System includes: all of Aztec C68k/Am-p • the Unix utilities make, diff, grep and vi.

Aztec C68k/Am-c Commercial \$499

Aztec C68k/Am-d plus source for the libraries and one year of updates.

Aztec C68k/Mac 3.4

New Macintosh Release

For code quality, reliability, and solid professional features, Aztec C for the Macintosh is unbeatable. This new release includes features and functions not found in any other Macintosh C development system.

Aztec C68k/Mac-p Professional \$199

• optimized C • 68000/680x0 assembler • 68881 support • overlay linker • UNIX and Macintosh libraries • examples.

Aztec C68k/Mac-d Developer \$299

The best of Manx, Macintosh, and UNIX. System includes: all of Aztec C68k/Am-p • the Unix utilities make, diff, grep • vi editor.

Aztec C68k/Mac-c Commercial \$499

Aztec C68k/Am-d plus source for the libraries and one year of updates.

Aztec C65

New ProDOS Release

Aztec C65 is the only commercial quality C compiler for the Apple II. Aztec C65 includes C compiler, 6502/65C02 assembler, linker, library utility, UNIX libraries, special purpose libraries, shell development environment, and more. An impressive system.

Aztec C65-c Commercial \$299

• runs under ProDOS • code for ProDOS or DOS 3.3

Aztec C65-d Developer \$199

• runs under DOS 3.3 • code for DOS 3.3

Aztec ROM Systems

6502/65C02 • 8080/Z80 • 8086/80x86 • 680x0

An IBM or Macintosh is not only a less expensive way to develop ROM code, it's better. Targets include the 6502/65C02, 8080/Z80, 8086/80x86, and 680x0.

Aztec C has an excellent reputation for producing compact high performance code. Our systems for under \$1,000 outperform systems priced at over \$10,000.

Initial Host Plus Target \$750

Additional Targets \$500

ROM Support Package \$500

Vax, Sun, PDP-11 ROM HOSTS

Call for information on Vax, PDP-11, Sun and other host environments.

C' Prime

PC/MS-DOS • Macintosh

Apple II • TRS-80 • CP/M

These C development systems are unbeatable for the price. They are earlier versions of Aztec C that originally sold for as much as \$500. Each system includes C compiler, assembler, linker, librarian, UNIX routines, and more. Special discounts are available for use as course material.

C' Prime \$75

Aztec Cross Development Systems

Most Aztec C systems are available as cross development systems. Hosts include: PC/MS-DOS, Macintosh, CP/M, Vax, PDP-11, Sun, and others. Call for information and pricing.

How To Become An Aztec C User

To become a user call 800-221-0440. From NJ or international locations call 201-542-2121. Telex: 4995812 or FAX: 201-542-8386. C.O.D., VISA, MasterCard, American Express, wire (domestic and international), and terms are available. One and two day delivery available for all domestic and most international destinations.

Aztec C is available directly from Manx and from technically oriented computer and software stores. Aztec Systems bought directly from Manx have a 30 day satisfaction guarantee.

Most systems are upgradable by paying the difference in price plus \$10. Site licenses, OEM, educational, and multiple copy discounts are available.

To order or for more information call today.

1-800-221-0440

In NJ or international call (201) 542-2121 • TELEX: 4995812

MANX

Manx Software Systems


Circle 108 on reader service card. 1 Industrial Way, Eatontown, NJ 07724

MS is a registered TM of Microsoft, Inc. CP/M TM DRI, HALO TM Media Cybernetics, PANEL TM Roundhill Computer Systems, Ltd. PHACT TM PHACT Assoc. PRE-C, Plink-86, Plink-86+, P-Force TM Phoenix, db Vista TM Raina Corp. C-tree, PC-lint, TM Gimpe Software, C-tree TM Faircom, Inc. Windows for C, Windows for DATA TM Creative Solutions, Apple II, Macintosh TM Apple, Inc., TRS-80 TM Radio Shack, Amiga TM Commodore Int'l., Unix TM AT&T, Vax TM DEC, Aztec TM Manx Software Systems.

RUNNING LIGHT

Several companies are feverishly (and secretly) working on new chips called "neural networks." These chips are designed to emulate various functions of the human brain. They contain thousands of standard microcircuit elements organized in a distinctly nonstandard way—hundreds of simulated neurons, each one of which is an always-active component capable of making simple decisions. Each "neuron" is connected by "synapses" to up to several hundred other neurons and can change its own activation potentials in response to signals it receives.

This could be the most important new invention in cybernetics since the Turing machine. Why? Because neural networks function in much the same way as your own brain (and mine, I think). Once they surpass a certain threshold of complexity, neural networks (whether they are actually implemented in hardware or simulated on traditional machines) begin to exhibit some interesting properties. Depending on their precise organization, they can act as spectacularly efficient pattern recognizers, solvers of multiple simultaneous equations (and other complex mathematical problems), learning machines that actually reach their own conclusions about the knowledge presented, and sophisticated device controllers—in short, all the functions that are currently performed by neural networks in your own body. A properly designed hardware neural network, for example, could easily provide a good solution to a 30-city traveling salesman problem in just a few (very few) microseconds. It's not guaranteed to be the best solution, but it will be extremely good. And the solution would be reached before a tradition-



al computer had even initialized its variables. Watch these pages for more about this exciting new field.

This issue marks the introduction of a new theme for *DDJ*. As the speed and storage of computers increase more and more rapidly, it becomes increasingly important to be able to move large quantities of information from one computer to another. We have advanced fiber-optic cables and satellite microwave links, but we also have an exponential growth in the amount of information being sent. The problem is one of bandwidth—the capacity of the communication channels is not growing as rapidly as the need to communicate.

We'll be looking at the bandwidth problem from several different perspectives. In this issue Ronald White describes graphical quadrees, a way to compress image data, sometimes dramatically. We also have a comparative review of four public-domain archiving programs. Archived files are files that have been compressed through the elimination of redundant data. Such files can be transmitted faster over modem lines; and because of this, archive programs have become popular on computer bulletin-board systems.

Do you have a project that excites you? Would you like to write about it for *DDJ*? Your first step is to give us a call at (415) 366-3600 and ask for a copy of the writers' guidelines. This wondrous document contains carefully refined advice that is intended to help you get published.

Nick Turner

Nick Turner
editor

ARCHIVES

Call for Innovation


"Think Big, dream bigger. Guest essays, dream pieces, signposts and other nefarious schemes for advancing this micro technology are welcome here, in addition to your hard software contributions to the community."—*Marlin Ouverson, DDJ, January 1982.*

WCCF

"The 6th West Coast Computer Faire is over (sigh of relief and aching feet). Director Jim Warren's roller skates have been hung up for another year, or at least until his rumoured mini-faires get under way. This year's was even bigger than expected...."

"Perhaps the biggest surprise to commercial concerns was the profile of the 'average' attendee. All the sales people had been coached well in advance on how to spill forth a technical-sounding pitch; none seemed able to answer basic questions like, 'Why should I have a computer?' 'What can I use it for?' 'I don't know anything about computers—where do I start?' Would-be consumers wandered from booth to booth in search of someone who could still remember how to speak their lingo and give a down-to-earth reply."—*Marlin Ouverson, DDJ, June 1981.*

Ten Years Ago in DDJ



"FAIRE CONSUMES EDITOR—DDJ LATE

"What more can we say? *DDJ*'s enterprising editor involved himself as chairperson of the First West Coast Computer Faire and discovered it to be an infinite sink of time. And he was spread much too thin before he started. Xeroxing editors failed."

"From time to time, over the past twenty years or so, there have been predictions that we will soon have inexpensive mass storage devices capable of holding the entire Library of Congress in a \$19 desk-top unit. These chimerical devices are usually based on some far-out technology involving proton resonance, magnetic bubbles, or holograms. Well, I'm still waiting patiently for such a device to materialize but I'm not holding my breath."—*Jim Day, DDJ, March 1977.*

DR. DOBB'S JOURNAL of
COMPUTER
Calisthenics & Orthodontia
Running Light Without Overbite

A Challenge to Microsoft® C...

We challenge Microsoft C (Ver 4.0) to a C compiler duel to the finish, measuring compile, link, and execution times. If they win, we will stop advertising for two months.

by Roy Sherrill

If Microsoft C (Ver 4.0) can beat Optimum-C then we will stop advertising in all magazines for two full months and, win or lose, we will publish the results in its entirety. Even the Microsoft ads say "The Fastest C you've ever seen," so let the challenge begin.

Walter says Optimum-C is better

It all started when Walter Bright, the developer of Optimum-C, was explaining his new global optimizing C compiler and how it's code would be faster than Microsoft C (Ver. 4.0). Walter and I were frustrated because here we had a C compiler that would beat Microsoft C on 7 out of 10 benchmarks and also compile and link faster; yet our marketing consultant, Mark Astengo, told us that Microsoft C had a lock on the C compiler market and by 1990 they would probably have an 80% market share. Then Mark said, "Roy, if your C compiler is as fast as you say it is, why not challenge Microsoft C to a duel? If Microsoft wins, Datalight should stop advertising for two months and print the results of the test, win or lose." Well, I've always been one for a challenge. So here it is...

We only ask the following...

The benchmark suite will consist of the set of programs that Microsoft supplied to *Computer Language* for their February 1987 C compiler review issue. Microsoft will make available the programs to Datalight at least two weeks prior to the benchmarking. The benchmarking will be between Microsoft C 4.0 and Optimum-C. It will occur at a mutually agreed upon time and place. Interested individuals will be allowed to attend. The benchmarks will be compiled and run on a standard IBM PC-AT.

There will be two separate tests for each program: compile and link speed, and execution speed. For each test, a representative from each company will set up the compiler so that it performs at its best.

The benchmarks will be adjusted so that they take sufficiently long to run, that the tolerance involved in timing them is insignificant. The winner is determined by the compiler with the faster execution times for the majority of the benchmarks. We'd like an answer from Microsoft no later than April 1, 1987.

So what's a global optimizer?

A global optimizer looks at an entire function at once, analyzing and optimizing the whole function. A technique called data flow analysis is used by Optimum-C to gather information about each function. This enables your compute-bound programs to execute as much as 30% faster after global optimization. But, there is one catch...because the global optimizer ruthlessly searches for

ways to speed-up execution speed and minimize memory usage, it has relatively slow compile times. No need to worry, though, because you can merely turn the global optimizer off. In fact, you can select all, none, or partial of the following optimizations: constant propagation, copy propagation, dead assignment elimination, dead variable elimination, dead code elimination, do register optimizations, global common subexpression elimination, loop invariant removal, loop induction variables, optimize for space, optimize for time, very busy expressions.

Choose from five memory models

Speed your programs by selecting the memory model that best suits your application.

Memory Models

| Model | Code | Data |
|---------|-----------------------|------|
| Compact | 64k total code & data | |
| Small | 64k | 64k |
| Program | 1M | 64k |
| Data | 64k | 1M |
| Large | 1M | 1M |

Compiling, one step...

Now with the one step DLC program you can create .OBJ, .EXE and .COM files. Also, DLC can handle multiple files and run MASM on your assembly files.

Try Optimum-C risk free

Try Optimum-C for 30 days and if you are not 100% satisfied return it for a full refund. Also, for a limited time we are including a *free C tutorial which is a combination workbook and floppy disk to help lead you through the C language with tutorials, quizzes, and program exercises.

O.K. Microsoft, it's up to you. We've put two months of advertising on the line that says you can't beat Optimum-C to a real test. Your answer, please?

PRICES

Developer's Kit still only \$99
Optimum-C \$139
(includes library source code)

Add \$5 for shipping in US/\$15 outside US
COD (add \$2.50)

Not Copy Protected



ORDER TOLL-FREE TODAY!

1-800-221-6630

Microsoft and MS-DOS are registered trademarks of the Microsoft Corporation.

Circle no. 203 on reader service card.

Magazine Reviewers Shocked by DATALIGHT's Performance...

"Reviewing this compiler was quite a surprise for us. For such a low price, we were expecting a "lightweight" compiler. What we got was a package that is as good as or better than most of the "heavyweights." Datalight C implements a complete C language. It also compiles quickly, doesn't take up much disk space, and looks impressive in the benchmarks."

DR. DOBBS, August 1986

"This is a sharp compiler!... what is impressive is that Datalight not only stole the compile time show completely, but had the fastest Fibonacci executable time and had excellent object file sizes to boot!"

COMPUTER LANGUAGE, February 1986

Optimum-C Version 3.0

- Full UNIX System 5 C language plus ANSI extensions
- Fast/tight code via powerful optimizations including common sub-expression elimination
- DLC one-step compile/link program
- Multiple memory model support
- UNIX compatible library with PC functions
- Compatible with DOS linker and assembler
- Third-party library support
- Automatic generation of .COM files
- Supports DOS pathnames, wild cards, and Input/Output redirection
- Compatible with Lattice C version 2.x
- Interrupt handling in C
- Debugger support
- ROMable code support/start-up source

MS-DOS® Support Features

- Mouse support
- Sound support
- Fast screen I/O
- Interrupt handler

MAKE Maintenance Utility

- Macro definition support
- MS-DOS internal commands
- Inference rule support
- TOUCH date manager

Tools in Source Code

- cat—UNIX style "type"
- diff—Text file differences
- fgrep—fast text search
- pr—Page printer
- pwd—Print working directory
- wc—Word count

Datalight

Box 82441
Kenmore, Washington 98028
(206) 367-1803

*Limited offer available exclusively to readers who purchase directly from Datalight.

LETTERS

**Programming Ethics**

Dear DDJ,

I've just read Allen Holub's December Viewpoint and was pleased to see him make his position known to the world. It's not an easy thing to do. I'm sure he'll receive letters criticizing his position.

On that note, allow me to introduce PeaceNet, an international computer network dedicated to improving communication between people worldwide on the issues of peace. PeaceNet is in need of programmer support, and anything readers can do, either directly or indirectly, would be helpful. PeaceNet is running on a Unix system (a Plexus P-60 [68000-based] to be exact) and is accessible through Telenet and via direct dial (Palo Alto, California).

In December, PeaceNet had more than 700 users and was gaining more than 100 per month. We have conferences on many important issues as well as "action alerts" and activity calendars. Readers interested in finding out more should call (415) 486-0624.

Corwin Nichols
223 Forest Ave.
Palo Alto, CA 94301

Dear DDJ,

I am responding to Allen Holub's Viewpoint in DDJ, December 1986. First, let me say, "bravo, Allen"; then let me say, "I disagree."

I say bravo because Allen states that he has examined the issues of working on defense contracts and that he feels he cannot live with his

conscience if he performs this kind of work. He also states that "there are people who have thought about these issues and have come to the opposite conclusion." I am one of these people, hence I disagree. He feels these people are wrong but that they are acting according to their beliefs in working on defense projects. He says he has his problem with people who refuse to look at the issues and work on defense projects anyway. I agree.

I am one of the people who has examined the issues and feels that defense work is a necessary activity in this world today. Although I wish that we were living in that time when "they shall beat their swords into plowshares, and their spears into pruning hooks: nation shall not lift up sword against nation, neither shall they learn war anymore" (Isaiah 2:4), we have Armageddon to face between here and there. I agree that defense work is a grave-digging activity: the enemy's grave. Not to engage in defense is a grave-digging lack of activity: our own grave. I cannot think of abstinence from defense work as other than suicide.

Robert J. Brown, III
Elijah Laboratories International

5150 W. Copans Rd., #1135
Margate, FL 33063

Dear DDJ,

After reading Mr. Holub's article in the December issue of DDJ, I felt I could not remain silent. I must disagree with Mr. Holub's opinions about nuclear weapons and whether or not an engineer could change this.

Assume just for the moment that all engineers agreed with him. Then what? Do we want a nonengineer cobbling together our weapons? Would that make us feel safer?

He said that if we didn't design them, they wouldn't exist. If all the ethical engineers in this country were to walk out on their defense contracts, do you know who would fill in for them? The unethical engineers.

I agree that we shouldn't sit around and wait for the bombs to be dropped. All of us, independent of our profession, should be much more politically aware—aware of the issues, who we vote for, and what we can do. That is the tack we need to follow as humans, not as engineers, to make the world a better, safer place to live.

I had a course in engineering ethics as well as an advanced philosophy course on ethics. I agree that these courses should be required of all engineering majors. The "tools" that you gain from these courses are just as important as everything else an engineer must learn.


Dave Podolske
University of Wisconsin

Dear DDJ,

Thanks to Allen Holub for writing his article about his personal decision not to work on weapons. I am gladdened whenever someone of his technical prowess speaks up on this issue.

He was brave to write it, and you were brave to print it.

You might tell your readers that there is an organization, Computer Professionals for



Feel the power of VAX/VMS® for a lot less ...

PCVMS.™



If you've written applications software on a VAX computer system, you already know about the power and flexibility of DEC's VMS operating system. Now, PCVMS puts the features of VAX/VMS on the IBM PC.

Designed specifically for applications programmers, PCVMS is a true multitasking, multiuser operating system that supports the most popular programming languages with resources you won't find in any other system for the same price. As powerful as it is easy to use, PCVMS offers a rich set of commands with easy-to-remember names like ALLOCATE, ASSIGN, COPY and DELETE. Like VAX/VMS it has a HELP command, which provides on-line documentation about commands, services and other topics. It also has built-in command prompting, so if you don't give all the information required for a command, the system will prompt you for the information you left out.

In addition to its powerful command set, PCVMS has over 80 system services, including enhanced system services that can be called from high level languages like BASIC, Fortran, Pascal, and C, as well as from assembly language. Using these enhanced services, you can create multiuser database, spreadsheet, and word processing programs that take full advantage of VAX/VMS system services. At the same time, PCVMS gives you multilevel protection that prevents services called by one process from inadvertently affecting or destroying other processes.

What it finally comes down to is this: if a VAX computer is out of your reach, now you can reach out and grab the power of a VAX for your PC with PCVMS.

PCVMS. From Wendin. Only \$99.

**Ask about our other products
for the IBM PC and true
compatibles.**

PCNX™

True multitasking, multiuser operating system similar to AT&T's popular UNIX® operating system.

OPERATING SYSTEM TOOLBOX™

Complete software construction set that lets you build your own multitasking, multiuser operating systems.

XTC®

The ultimate programmer's editor. Multitasking macro language plus multiple linkable windows and buffers.

**All products priced at \$99
with source code included.**

DEALER INQUIRIES WELCOME

Foreign orders inquire about shipping. Domestic orders add \$5.00/1st item, \$1.00 each additional item for shipping, handling, and insurance. We accept Visa/MC, American Express, COD, and Bank Drafts drawn on U.S. Banks. Washington residents add 7.8% sales tax.

MS is a trademark of Microsoft, PC-DOS is a trademark of IBM. UNIX is a trademark of AT&T. VAX/VMS is a registered trademark of Digital Equipment Corporation.

Wendin and XTC are registered trademarks of Wendin, Inc. PCNX, PCVMS, Operating System Toolbox, and Personal Operating System are trademarks of Wendin, Inc.

WENDIN®
327 E. PACIFIC
SPOKANE, WA 99202

© Copyright 1987 Wendin, Inc.

The people who make quality
software tools affordable.

ORDER HOTLINE
(509) 624-8088
(MON.-FRI., 8-5 PACIFIC TIME)



Circle no. 112 on reader service card.

LETTERS

(continued from page 10)

Social Responsibility, that deals with these issues. Its address is Box 717, Palo Alto, CA 94301. Also, the ACM SIGSOFT and SIGAS publish related information.

Kerry Tatlow
1706 Charles
Rockford, IL 61108

Dear DDJ,

Thank you and congratulations for running Allen Holub's Viewpoint on programming ethics. It says a lot for DDJ's position on the forefront of software technology in particular and thought in general, regardless of where one stands on the guns and butter debate.

Michael Gardner
Wordtech Systems, Inc.
P.O. Box 1747
Orinda, CA 94563

Dear DDJ,

I enjoyed reading Allen Holub's December article concerning the choices that engineers and programmers make in determining the effect of the work that they do upon society. It appears that we are primarily concerned with the intellectual challenge and financial rewards of our technical careers and that we seldom think about the effect of our work on society as a whole.

However, I think that the following is evidence that people are also concerned with the moral aspects of their work: There is a tendency for technical people working in the defense industry to be paid more than people doing nondefense-related work. A large part of the reason for the pay discrepancy is that many people just don't want to work on weapons. In order to make defense-industry work attractive enough to fill the positions, employers are forced to pay more than the market rate to overcome people's natural distaste.

Eric D. Andresen
529 Stone Dr.
Novato, CA 94947

In Search of a Sine

A number of people who responded to Richard Campbell's article "In Search of a Sine," published in the December 1986 issue, pointed out additional references for transcendental algo-

rithms. Following is a list taken from the letters.—eds.

Abramowitz, M. I. A. Stegun ed., *Handbook of Mathematical Functions and Formulas, Graphs and Mathematical Tables*. National Bureau of Standards Applied Math Series, 55, Washington, D.C.: U.S. Govt. Printing Office, 1964.

Acton, Foreman S. *Numerical Methods That Work*. New York: Harper & Row, 1970.

Cody, W., and Waite, W. *Software Manual for the Elementary Functions*, Englewood Cliffs, N.J.: Prentice-Hall, 1980.

Hart, J., et al. *Computer Approximations*. New York: Wiley, 1968.

Hastings, Cecil, Jr. *Approximations for Digital Computers*. Princeton, N.J.: Princeton Univ. Press, 1955.

Knuth, D. E. *Art of Computer Programming, Volume 2: Seminumerical Analysis*. Reading, Mass.: Addison-Wesley, 1969.

Dear DDJ,

Regarding the article "In Search of a Sine," I would like to point out that the Taylor's series expansion, although of inestimable value in doing analytical, theoretical work, is in general of little value in computing numerical approximations of a function and is hardly ever used. There is a good reason for this. When expanding a function into its Taylor's series expansion, you choose a reference point upon which to anchor the expansion and then use the series to approximate the function in the vicinity of this point. If, for example, you are interested in approximating $\sin(x)$ (as Mr. Campbell was), you might choose the anchor point $x=0$ and come up with the result:

$$\sin(x) = x - \frac{x^3}{3!} + \frac{x^5}{5!} \dots$$

or, in expanded form:

$$\sin(x) = x - 0.166667x^3 + 0.00833333x^5 + \dots$$

It is evident that this approximation produces an exact result at the reference point, $x=0$.

If, however, you choose the refer-

ence point $x=\pi/4$ radians (45°), the resultant series becomes:

$$\sin(x) = -0.00924739 + 1.04438x - 0.0758732x^2 - 0.117851x^3 + \dots$$

This approximation isn't worth beans for $x=0$ but is exact at the reference point—well, exact to within the accuracy of the coefficients, as represented, anyway.

The point is this. The Taylor's series approximation of a function—any function—is exact at the reference point about which it is expanded but gets worse the farther you get from this point. Furthermore, it often gets worse fast! To achieve good overall accuracy, you would have to use many series, each anchored at an appropriate point.

A better way was invented by a clever mathematician named Chebyshev (sometimes spelled Tchebyshev or variant thereof). Instead of approximating a function with a series of powers of x , he whipped up some nifty polynomials in x (called Chebyshev polynomials, what else?) and approximated the function with a series of these polynomials. Of course, all the powers of x in these polynomials eventually combine to produce something looking very much like a Taylor's series, except that the coefficients are slightly different and they have the absolutely lovely property of distributing and bounding the approximation error over the range of the approximation. Not only that, the Chebyshev scheme produces approximations of comparable error to Taylor's but with fewer terms. The process is oft-times called Chebyshev economization. Without going into the details of why this happens or how to do it (which would require a lengthy article in itself), suffice it to say that if you expand $\sin((\pi/2)x)$ in terms of Chebyshev polynomials and then simplify it, the result is:

$$\sin((\pi/2)x) = 1.5706268x - 0.6432292x^3 + 0.0727102x^5$$

I have used the notation $\text{Sin}()$ to mean an approximation of $\sin()$. This function has a maximum error of about 0.0001 over the range $-1 < x$



You'd Be Surprised Who Uses Essential Graphics Functions

And some of our well-known customers would be just as surprised if they saw themselves in this ad. We don't splash their names all over the place as a matter of professional courtesy.

Let's face it. Just because someone else uses a product is not reason enough to buy it. The clincher is that our programs run a *documented 40% faster* than the closest competitor. To complete the picture, our code is up to *75% smaller* due to efficient coding and the granularity of functions.

However, should curiosity get the best of you, call us at 201-762-6965 and we'll drop a few highly impressive names on you.



Behind every great program is a great library.

Draw Your Own Conclusions

When you're responsible for a project that includes advanced graphics, "graphics windowing," or character font manipulation, Essential Graphics is the clear choice. We've taken the grind out of graphics programming and replaced it with speed and versatility.

No Royalties, 30 Day Guarantee

We believe that selling you a programming tool does not make us your co-authors. So we don't charge any royalties or run time fees. If within 30 days you don't find our library satisfactory, dump the whole thing and receive a complete refund.

Functions At A Glance

Features:

- Fastest functions available
- Dots, Lines, Circles, Arcs, Pies, Bars
- Manipulate character fonts
- Move blocks, do animation
- User definable patterns
- Seed filling in a boundary
- Clipping on screen coordinates

Devices Supported:

- IBM, Epson, Oki printers
- HP Plotters, HP Laser Jet
- Microsoft, Logitech Mice

Graphics Adapters:

- IBM Color Graphics
- IBM Enhanced Graphics
- Hercules Graphics
- AT&T, Olivetti Graphics
- Tecmar Graphics Master
- Others (Call)


Compiler Compatibility:

- Microsoft, C, Fortran, Pascal
- Lattice C, Aztec C
- Computer Innovations C86, DeSmet C
- Wizard C, Mark Williams

\$250.00

Do Your Homework

The library you buy can influence the rest of your programming life. We encourage you to do some checking before making a decision. When you've done your homework, you'll choose Essential. Call our support staff of experienced C programmers and find out before you buy how things will be after your check clears.



**To order or for support
call: 201-762-6965**

For foreign orders contact:

England: Gray Matter Tel. (0364) 53499
Japan: Lifeboat Inc. of Japan Tel: 293 4711
West Germany: Omnitex Tel. 07623-61820

Essential Software, Inc.

P.O. Box 1003, Maplewood, New Jersey 07040

LETTERS

(continued from page 12)

< 1, which covers the entire first and fourth quadrants. If you require greater accuracy, you can use the approximation:

$$\begin{aligned} \sin((\pi/2)x) = & 1.57079631847x \\ & - 0.64596371106x^3 \\ & + 0.07968967928x^5 \\ & - 0.00467376557x^7 \\ & + 0.00015148419x^9 \end{aligned}$$

This approximation is valid over the same range and has a maximum error, which occurs at several places within the range, of about 0.000000005.

Another mathematician named Padé generated a slick way to do the job using the ratio of two polynomials. I'll say nothing more about this technique, except that it works sublimely with certain types of functions.

I would add one last thing in passing. You should never evaluate the polynomial (for example):

$$a + bx + cx^2 + dx^3$$

as it stands. You should always arrange it into the nested form:

$$((dx + c)x + b)x + a$$

This form requires fewer multiply instructions, thereby executing faster and producing smaller numerical errors.

Charlie Rose
Ball Aerospace Systems
P.O. Box 1062
Boulder, CO 80306

Dear DDJ,

The sine routine given by Richard Campbell in your December issue could be improved. One improvement would be to compute $aa = a^2$ and then compute the sine approximation as:

$$s = (((C4 * aa + C3) * aa + C2) * aa + C1 * a$$

using the same coefficients as before. This nested form of the polynomial accumulates the small terms first and thus reduces the errors due to floating-point rounding. By initially squaring a , you end up doing three

additions and five multiplications.

Another improvement would be to use a ninth-order polynomial instead of a seventh-order one. The sine would then be computed as:

$$s = (((C5 * aa + C4) * aa + C3) * aa + C2) * aa + C1 * aa$$

where the coefficients are:

$$\begin{aligned} C1 &= 1.5707963 \\ C2 &= -0.64596371 \\ C3 &= 0.079689679 \\ C4 &= -0.0046737666 \\ C5 &= 0.00015148513 \end{aligned}$$

The coefficients published in the December DDJ can be found on page 203, item SIN 3340, in *Computer Approximations* (J. Hart et al.), but are given to more precision. The coefficients for the ninth-order polynomial listed above can be found on page 204, item SIN 3341, of the same reference.

A third way to improve the routine would be to use the methods outlined in the two references and develop a program whose accuracy is limited only by the precision of the floating-point representation of the final result.

Harry J. Smith
Litton Computer Services
1300 Villa St.
Mountain View, CA 94039

Dear DDJ,

Here is some feedback on "In Search of a Sine." Some readers may notice that the coefficients C1 through C4 are somewhat different from the theoretical coefficients for the Maclaurin's series for the sine function. After truncating a series to a specific number of terms, it is advantageous to cook the coefficients using least-squares curve fitting. Presumably the values given for C1 through C4 were derived in this manner. Rearranging the sine formula before doing the actual computation would result in fewer operations. The BASIC rendition would be:

$$\begin{aligned} A2 &= A^2 \\ \text{SIN} &= (((C4 * A2 + C3) * A2 + C2) * A2 + C1) * A \end{aligned}$$

and the 32K assembly-language ren-

dition would be:

DoSin

```
MOV F3,F1
MUL F1,F1
MOV F -0.004362469,F5
MUL F1,F5
ADDF 0.07948765,F5
MUL F1,F5
ADDF -0.645921,F5
MUL F1,F5
ADDF 1.570795,F5
MUL F5,F3
RET 0
```

Because the coefficients can be used only by the *DoSin* routine, there is no reason to keep them in a table. Making them immediate operands is more compact, faster, and more readable. When coding for the 32K, you often find that in-line coding is more compact than the looping method. When using the 32K, you must remain alert for opportunities to be liberated from your old habits.

For higher precision, you could further divide the range of A . That is, if A is more than 0.5, you take the cosine of $(1.0 - A)$ using the Maclaurin's series for the cosine:

$$\begin{aligned} A2 &= A^2 \\ \text{COS} &= (((D4 * A2 + D3) * A2 + D2) * A2 + D1) * A2 + 1.0 \end{aligned}$$

In order to realize the higher precision, you would need to recook the coefficients based upon the shorter range.

Another thing to keep in mind when doing math routines for the 32K is that the FPU is very fast; it does a double-precision multiply faster than the operands can be moved in and out of memory. Therefore, the old rule of thumb about the floating-point operation dominating the time is no longer true.

The bugs in the 32K alluded to by Mr. Campbell are almost certainly a thing of the past; if you have a reasonably mature version of the 32K, you should refrain from using any and all addressing modes with floating-point operands.

Neil R. Koozer
Kellogg Star Route Box 125
Oakland, OR 97462

DDJ



Some Very Impressive People Keep Our Asynch C Tools Under Their Hats

This is the only way we can get some of our customers to take their hats off to us in public. We understand. Most people like to keep a good thing to themselves.

Once you see how powerful and simple our functions are, you'll want to treat our Communications Library Plus as a well guarded trade secret too.

Essential provides the best alternative to Assembly language for communicating via an RS-232.

However, should curiosity get the best of you, call us at 201-762-6965 and we'll let you in on the identity of some of our secret admirers.



Behind every great program is a great library

What Good Are Library Functions If You Can't Get Them To Work?

Providing functions is not enough. Essential Communications Library Plus includes BreakOut, a slick on-line data monitor. BreakOut saves hours of frustration. We know, we used it to debug the XMODEM and other functions in Essential Communications.

No Royalties, 30-Day Guarantee

If within 30 days you don't find our library or BreakOut totally satisfactory, hang the whole thing up and receive a complete refund.

Functions At A Glance

- Interrupt driven to 9600 baud
- Hayes compatible support
- 150 page manual—tutorial
- XMODEM, XON/XOFF support
- Timer/Keyboard functions
- Input buffers to 500K
- Source included
- Demo terminal program
- Demo BBS system
- All major compilers supported
- Ctrl-Break status

Comm Library Plus/BreakOut \$250 Comm Library \$185

BreakOut On-line Monitor/Debugger

- Monitor RS232 ports up to 9600 baud
- Control comm variables and line signals
- Send/receive data using the scratch-pad editor
- Edit scratch-pad in Hex or ASCII
- Save data to file or re-transmit it
- User configurable keyboard macros
- Use symbols for control chars (<ACK>) for Hex 06

BreakOut \$125

Do Your Homework

The library you buy will influence the rest of your programming life. When you've done your homework, you'll choose Essential. Call our support staff of C programmers and find out now how things will be after your check clears.



**To order or for support
call: 201-762-6965**

For foreign orders contact:

England: Gray Matter Tel. (0364) 53499
Japan: Lifeboat Inc. of Japan Tel: 293 4711
West Germany: Omnitex Tel. 07623-61820

Essential Software, Inc.
P.O. Box 1003, Maplewood, New Jersey 07040

Compressing Image Data With Quadtrees

by Ronald G. White

A quadtree is a tree data structure in which each node can have four child nodes under it (compared to a binary tree in which each node can have two children). Quadtrees can be used as an efficient representation of

graphical information and offer some interesting features. For a graphical quadtree, each node represents a square area of the graphical image and each of its four children represents one quadrant, or one fourth, of its area. These subareas are defined by dividing the original area in two equal halves, left and right, and dividing each of these halves in half, top and bottom. Thus the subareas, or quadrants, are of equal size and are also squares. The root node, called the top node, represents the entire image and has under it four children each representing one fourth of the entire image. This process of division is repeated until each child represents only a single pixel of the original image. If the original image is not a square with the number of pixels on each side being a power of 2, the image has to be filled out to that size with a background color. The bottom nodes, each representing one pixel, are leaf nodes of the tree. (Data structure trees are upside down from actual trees because the root node is said to be on the top and the leaf nodes on the bottom.) All the nodes in the tree at the same distance from the root—that is, having the same number of nodes between them and the root—are said to be on the same level. For graphical quadtrees, the levels are numbered starting from the

When a graphical image is represented by an efficient quadtree, the amount of data can be less than with other representations.

bottom nodes—the leaves—which are at level 0. If the image is $N \times N$ pixels, where $N = 2^k$, then the root, or top, node is at level k and the number of levels is $k + 1$.

To represent a graphical image, the leaves of the quadtree need to have information about the corresponding pixel associated with

them. If the image is a color image, then the bottom nodes will have a color value. This value can be an index into a color map, a set of RGB values, or some other color information. The information associated with nodes that are not at the bottom level has a less obvious meaning. If all four children of a nonleaf node are leaf nodes and they all have the same color, the parent node can adopt that color. In fact, the child nodes then become redundant and can be removed from the quadtree. With all four children removed, this node now becomes a leaf node even though it is not a level 0 node. Removal of unnecessary nodes is called pruning and can be repeated for successively higher levels, moving from the leaves toward the root.

If fewer than four child nodes have the same color, the parent can still adopt the predominant color of the children. If the children with the same color are leaf nodes, they can be removed from the tree. The parent node does not become a leaf node in this case because there are still child nodes under it, but you have reduced the size of the tree by removing at least some of the child nodes. It would be possible, even if all four child nodes were different colors, for the parent node to adopt one of the child nodes' colors and to remove that child node. As you will see later, in the section about locational codes, in the end this removal does not gain anything. You can get rid of one child node, but you then have to keep the parent

Ronald G. White, 161 S. 35th St., Boulder, CO 80303. Ronald has an M.S. in computer science from the University of Colorado. He is currently involved in porting software to new graphics terminals and workstations.



node. In my code I prefer to have the parent node adopt a color only if at least two of the child nodes have that color.

When a graphical image is represented by an efficient form of a quadtree (locational codes, presented in the next section, are one way), the amount of data can be less than with some other common representations such as simple pixel dumps or run-length encodings. This depends on the image, of course—a very fine mesh checkerboard pattern would not be represented efficiently by a quadtree. Images in which large areas are the same color can be represented by small quadtrees because higher-level nodes in the quadtree can represent large sections of the image with no need for lower-level nodes below them.

Another advantage of quadtrees is that if they are transmitted or displayed starting from the top level, then each successive level represents a closer approximation to the final image. This is particularly useful on some newer graphics displays that support a fast polygon fill command so that the area represented by a node can be filled quickly by a single command. Although I don't define the color of intermediate nodes in this way, each nonleaf node's color could be the average color of the area it represents. Each lower level would then provide a more accurate description of the image as it was transmitted or displayed. The method I use defines colors for intermediate nodes only if at least half of the final area represented by that node will be that color. In this case, each lower level provides additional information about some areas of the image that are not yet accurately defined. In an interactive situation where transmission of data is slow or costly, the user could be allowed to stop the transmission or display as soon as the image was accurate enough to be recognized as wrong or of no interest. With normal scan-line display of images, much of the image, and thus a lot of data, must be displayed before the contents of the picture can be guessed.

Quadtrees also have advantages for certain types of analysis and manipulation of images, but a discussion of these is beyond the scope of this article. For those of you who want to pursue this topic further, I've provided a list of references at the end of this article.

Locational Codes

The quadtree representation is efficient for certain types of processing, but it is not very efficient in terms of storage. Locational codes are a way of indicating the position of a node in the quadtree without actually storing the pointers from the root node to the given node. Instead, the path from the root node to the given node is coded as a single number. This is generally done by equating each direction—NW, NE, SW, or SE—from the parent to the relevant child as a single digit (for example, 0, 1, 2, and 3) and combining the digits representing the path into a single number. For example, the path NE-SE-SE-NW could be expressed as 1330, where the 1 represents the NE child of the root node, the first 3 represents the SE child of that node, the second 3 represents the SE child of the 13 node, and the 0 represents the NW child of the 133 node. Each node, then, has a unique representation. Using a base 10 representation, however, wastes storage space. In my code, I pack each direction value into two bits—that is, I use a base 4 representation. Other authors recommend using a base 5 representation so that the directions are the values 1, 2, 3, and 4 and 0 is reserved as a beginning marker. This is useful because, depending on the level of the node, the number of direction values—that is, digits—will vary. In base 5, the preceding example would be 02441, where the 0 indicates the beginning of the code. In base 4, there is no unique bit pattern to use as a beginning marker because all four possible two-bit patterns are used as direction values.

The disadvantage of the base 5 scheme is that it requires multiplying and dividing by five in order to manipulate



COMPRESSING IMAGE DATA (continued from page 17)

the encoding. I originally used a base 5 encoding but found the conversion from a quadtree path to a locational code (and back) too slow. To speed up this process, I switched to a base 4 encoding and replaced the multiplies and divides by shifts and bit operations, which are faster. This representation also needs fewer bits to store it. To solve the problem of a beginning marker, I chose to mark the beginning with a 01 bit pattern. Because I always put a 01 in front of the actual direction values, I can search the bits in the locational code from left to right, two at a time, and know that the first nonzero pair is not a valid direction value but that the next pair is. Without this marker, it would be impossible to determine where the direction values start.

Because pointers are not needed with locational-coded quadtrees, nodes that only supply redundant information—that is, serve only as placeholders in the tree—can be removed, or pruned, from this form of the quadtree for more efficient storage or transmission. This pruning can result in significant space savings. Consider, for example, an image consisting of a single red pixel against a black background. In the pointer form of the quadtree, the root node would have a color of black because this is the predominant color of the area it represents (though not the only color). Three of its child nodes, representing the three quadrants not containing the red pixel, are not necessary because the information they would hold—the color black—is already held by their parent and all nodes under them would also have the same information. The fourth node, on the other hand, is necessary because somewhere at the bottom of its subtree is a node representing a single pixel and its information is different—that is, it has a color of red. This pattern—three nodes are unnecessary but the fourth is needed—is repeated down through the levels of the quadtree until you reach the node representing the red pixel. The nodes in the tree

between the root node and the bottom node do not contain useful color information, but they are necessary to save the path from the root node to the bottom node. With the locational code form of the quadtree, each node is represented by a pair of numbers—the locational code itself and a color. For the image of a single red pixel, you need to have only two nodes—the root node and the single bottom node—all the intermediate nodes can be thrown away.

Another advantage of some locational codes is that when the codes are sorted into numerical order, the higher-level nodes come before lower-level nodes. This is true for the three coding schemes already mentioned (base 10, base 5, and my base 4 with special marker) because each lower-level code requires an additional digit to represent the next direction value. Sorted in normal numeric order, the higher-level nodes, having fewer digits, will always precede the lower-level nodes. The base 4 scheme I use preserves this feature because the 1 in front of the actual direction values is shifted two bits left at each lower level. My code, however, makes sorting unnecessary because it outputs the nodes from the root node one level at a time.

Listing One

Listing One, page 40, is a set of routines for converting a graphical image from pixels to a quadtree and outputting the quadtree in locational code form. I have not provided a main routine because initialization is likely to be application specific and possibly system dependent. The main routine should do whatever is necessary to make available a graphical image. Necessary tasks might involve reading the image into an array from a file, getting information interactively about what image or what part of the image the user wants, or initializing the display with the image if the image is to be taken directly from the display. The main routine also needs to perform initialization for the output of the quadtree. This could be opening a disk file and writing some header information to it, or it might involve opening a communications channel of some sort. After all this is done, the main routine calls *px2quad()*.

The only externally accessible routine is *px2quad()*, which must be passed the size of the image. If the actual size of the image is not a square with each side equal to a power of 2, the size passed to *px2quad()* is the smallest such square that the image will fit inside. These routines assume the availability of two routines, *getpix()* and *putlcc()*, that they can call. Besides the main routine, you must also supply these routines. *Getpix()* returns the color value of a pixel at a given x,y position, and *putlcc()* is called to output the locational code and color for each node.

The primary data structure used by the routines in Listing One, defined at the beginning of the listing, is used for each node in the quadtree. The first field, *child*, is an array for the four pointers to child nodes. The direction value serves as a subscript into this array, with the following correspondences: 0, 1, 2, and 3 correspond to the directions NW, NE, SW, and SE, respectively. The second field in the node data structure, *next*, is a pointer to the next node on the linked list used during output. This linked list is explained later as part of the explanation of



**“Microport is
the *fastest* path
between
real UNIX[®]
System V
and you.”**

Dimitri Rotow runs a company on the go. He has little time for hardware or software that doesn't do the ultimate job for his company's customers.

Two months ago he assessed three readily-available UNIX (and UNIX-like) operating systems. After evaluating pricing, packaging, documentation, quality, service, manufacturer's support, compatibility, third-party support, features, conformity and performance, he and his VP of engineering came to one conclusion: “To praise Microport is to praise the AT&T/Intel joint venture, because Microport's version of UNIX System V is virtually *identical*. However, more *value* is received since more middlemen are removed—that's much closer to buying direct and selling direct.”

Bell Technologies' customers appreciate real value plus real System V. If you're an OEM, a reseller, an end-user or simply curious about our product—call us today and see what all the endorsements are about.

Microport Systems, Inc.
10 Victor Square
Scotts Valley, CA 95066

408/438-UNIX (438-8649, local)
800/822-UNIX (Inside California)
800/722-UNIX (Outside California)
FAX: 408/438-2511
Telex: 249554



Team Use for The AT.

**Dimitri Rotow, President
BELL TECHNOLOGIES**

UNIX is a registered trademark of AT&T

Circle no. 154 on reader service card.

the routines *outtree()* and *outnode()*. The next field, *color*, is the color associated with the node. I store this as a single value because I am using the index value into a color table. More extensive information could be substituted for the single value although this would complicate the code somewhat. The *ntype* field is a flag that indicates what type of node this one is. The three node types are defined in the next section of code. The *ntype* field is not absolutely necessary (as is explained later), but I find it useful. The final field in the node structure, *locode*, is the locational code for this node, which is calculated as each node is added to the quadtree.

The next section of code defines the three node types—*LEAF*, *BLEND*, and *WASH*. *LEAF* type nodes are nodes that have no further nodes under them. The color value of a leaf node represents the color of all the pixels in the area defined by that node even if it is not a bottom-level node. If, during the initial pruning of the quadtree, a node has two or three children that are leaf nodes and that share the same color, the parent node adopts the color of these child nodes and these nodes are removed from the tree. This parent node is marked as a *BLEND* type node to indicate that its color value is the color of pixels in areas represented by missing child nodes and that the node has child nodes that were not removed. All nodes that are neither *LEAF* type nodes nor *BLEND* type nodes are marked as *WASH* nodes, indicating that their only purpose is as placeholders for the pointers to child nodes and that their own color is not relevant.

The routine *px2quad()* is the control routine for all the processing necessary to build and output the quadtree. The first thing it does is create the root node with a call to *crtnode()*. It then calculates the level number of the root node from the parameter *size*, which the calling routine passed to it. What this code does is find *k*, where $size = 2^k$. (There may be a more direct way to do this.) After setting the locational code for the root to 0 (remember that the 1 is not actually part of the locational code but a beginning marker), *px2quad()* calls *addnode()* to add the root node to the currently empty quadtree. *Addnode()* calls *crtnode()* and itself recursively to create the rest of the quadtree. When *addnode()* finally returns, the quadtree has been built and the initial pruning done. *Px2quad()* then calls *outtree()* to control the final pruning and the output of the quadtree as locational codes and colors.

The function *crtnode()* creates a new node, initializes it with default values, and returns a pointer to it. I use a call to the system routine *malloc()* to get enough space for one node. This step could be a problem for several reasons. The first is the overhead associated with making this call perhaps hundreds of thousands of times during the creation of the quadtree. This overhead could be reduced by getting larger chunks of memory (or even statically allocating a very large array) and having *crtnode()* and *relnode()* maintain a list of free nodes. This approach complicates the code, of course, but it might be worthwhile for improved performance. The second potential problem is the amount of memory required for a quadtree that represents a reasonable-size image. I'll discuss this in

more detail at the end of the article. *Malloc()* returns a *NULL* pointer if no more memory is available or something else goes wrong; *crtnode()* checks for this condition. The last part of the code initializes the newly created node. The node type is set to *LEAF*, indicating that this node does not have child nodes after it. If *addnode()*, the next routine, creates new nodes under this one, it will also call *condense()*, which, among other things, resets the node type.

Addnode() adds a newly created node to the quadtree. If this node is not at the bottom level, it creates four new child nodes under the current one with calls to *crtnode()* and calculates locational codes for these new nodes. This calculation is simple. The locational code for the current node is available in the node data. The locational code for a child node needs only one direction value added onto the end of the parent's code. Because the direction value is the same as the subscript into the array of pointers to the four child nodes, all the code has to do is shift the parent's locational code left two bits and add in the direction value for the child. *Addnode()* then calls itself recursively for each of the new child nodes. After these four new nodes have been added, *addnode()* calls the routine *condense()*, which examines the four nodes under the current node to see if any of them can be removed. If, on the other hand, the current node is at the bottom level—that is, this node represents a single pixel of the image—*getcolor()* is called to get the color of the pixel.

Condense() is the routine that does the initial pruning of the quadtree and is probably the most complex routine presented here. It first loops through the four children of the current node (*addnode()* does not call *condense()* for leaf nodes, so the current node will always have four children), collecting information about their colors. What the code is looking for is a predominant color—that is, a color shared by two or more child nodes. Nodes that are marked as type *WASH* are ignored because their color is meaningless (as is explained later). *Condense()* sets the current node's color to the predominant color. If no two children have the same color, then the next section is skipped. Otherwise, the code again loops over the four children. If a child had a type of *WASH*, it can't be deleted, so it is ignored. If a child has the same color as the predominant color, it is either removed, if it is a leaf, or demoted to type *WASH* otherwise. The reason why it can be removed if it is a leaf is that the area it represents is included in the area represented by its parent and the parent now has the same color—the color of the child node is therefore redundant. If a child node is not a leaf, this means that it has at least one child node of a different color below it and so it cannot be deleted without losing the pointers to its children. Its color, however, is now redundant information, and this fact is noted by marking it as a *WASH* type. The final section of code in *condense()* resets the node type of the current node. If all four children have been released (because they were all the same color and now this node has that color), then this node becomes a leaf node and is marked *LEAF*. If this node has adopted a color because two or more of its children have been removed or marked as *WASH* type nodes, it is marked as a *BLEND* type node to indicate that it is not a leaf node but its color is relevant information. If the node is

WINDOWS FOR DATA™

The first choice of professional C programmers

"Windows for Data is the best
programming tool I've ever used.
It's the most flexible I've seen.
Whenever I've wanted to do something,
I've been able to find a way."

Steven Weiss,
Stratford Systems

Professionals choose our tools because they are designed, crafted, and supported for professionals. Here at Vermont Creative Software, we understand that performance and pleasure in programming derive from more than a long list of functions. **Windows for Data** provides:

PROFESSIONAL FLEXIBILITY:

Our customers repeatedly tell us how they've used WFD in ways we never imagined - but which we anticipated by designing WFD for unprecedented adaptability. Virtually every capability and feature can be modified to meet special needs. You will be amazed at what you can do with WFD.

PROFESSIONAL PERFORMANCE:

Screen output is crisp and fast. Windows, menus, and data-entry forms snap up and down from the screen. WFD is built upon and includes **Windows for C, the windowing system rated #1 in speed and overall quality** in PC Tech Journal (William Hunt, July 1985).

PROFESSIONAL RELIABILITY:

An unreliable tool is worse than no tool at all. VCS products are known in the industry for their exceptional reliability. Ask anyone who owns one.

PROFESSIONAL DOCUMENTATION:

Over 600 pages of documentation provide step-by-step explanations for each major application, a reference page for each function, listings of functions alphabetically and by usage, and a fully cross-referenced

index. Extensive tutorials and demonstration programs assist learning.

PROFESSIONAL TECHNICAL SUPPORT:

The same expert programmers that develop our products provide prompt, knowledgeable technical support.

PROFESSIONAL PORTABILITY:

High-performance versions of VCS products are available for XENIX, UNIX, and VMS, as well as DOS. No royalties.

OUR CHALLENGE AND GUARANTEE

If you have an application where no other tool can do the job, try **Windows for Data**. If it doesn't help you solve your problem, RETURN FOR A FULL REFUND. YOU MUST BE SATISFIED.

Ask for **FREE DEMO DISKETTE**



**Vermont
Creative
Software** 21 Elm Ave.
Richford, VT 05476
802-848-7738,
Telex: 510-601-4160 VCSOFT

Prices: PCDOS* \$295; XENIX, VMS, UNIX Call.
No royalties. Shipping \$3.50.
*PCDOS specify C compiler.

Circle no. 157 on reader service card.

WINDOWS FOR DATA

for DOS, UNIX, VMS ...

The complete windowing data entry, menu, and help system that does the hard job others can't - we **guarantee** it!

Pop-up data entry windows; field types for all C data types, plus decimals, dates, and times; auto conversion to and from strings for all field types; system and user supplied validation functions; range checking; required, must-fill, and protected fields; free-form movement; multiple-choice field entry; scrollable sub-forms. Branch and nest windows, forms, and menus.

Complete context-sensitive help system with pop-up windows and scrollable text.

Pop-up, pull-down, scrollable, and Lotus-style menus.

NEW FOR DEBUGGING: Exclusive **VCS Error Traceback System** automatically identifies the location and cause of program errors. Eliminates the need to code error checks on all function calls! **VCS Memory Integrity Checking** helps catch those hard-to-detect, memory-corruption errors.

NEW FOR ERROR HANDLING: Install your own error handler to be called whenever a function detects an error.

NEW FORM LAYOUT UTILITY simplifies form design.

How a magical Genie saved this programmer from going crazy

File format changes were driving me nuts. Then, I got stuck with a 12 year old word processing file that had to be converted to WordStar® ASAP. I must have passed out momentarily, because the next thing I remember is a guy in a turban, jamming a diskette into my PC. He pressed a few keys and "Presto," he created a new utility for my program. The file conversion underway, I passed out again and when I woke up, he was gone—but the amazing utility software he had used remained.

File Genie, that's the name on the diskette. An amazing tool. Since then, I discovered that it will convert word processing and data files from most any format to any other. And, as if that isn't enough, it also: diagnoses and fixes errors in broken database files, instantly searches and replaces on seven and eight bit data (on ambiguous file names, with the most complete set of regular expressions I've ever seen), has a script language with IF, ELSE, WHILE, FULL SCREEN CONTROL, and the ability to run DOS commands or programs, comes with on-line context sensitive help, et cetera, et cetera. Allows printing of files without my printer reacting to control codes too.

With **File Genie** I write my own utility programs quickly and easily. As you can imagine, I guarded this little gem with my life, keeping it totally secret. Until everybody kept asking me how I was doing all these incredible things. I have to admit, I am sold. Which gets me to the really fabulous news. **File Genie** is available by calling 1-800-822-0852 for an introductory price of only \$69.95. You'll save that much in aggravation the first time you use it. So if those files are driving you crazy, too, call and order your **File Genie** today.


WordStar® is a registered trademark of MicroPro




A software product of Team Austin Inc.

6809 Convoy Court
San Diego, CA 92111
619-278-5353 (CA)
800-822-0852 (USA)

Circle no. 204 on reader service card.



Turbo Programmers:



Find the culprit fast with T-DebugPLUS.™

You're programming, getting all your ducks in a row, but there's a culprit in there, a bug. T-DebugPLUS, the new symbolic run-time debugger, helps you find that bug and fix it faster than ever before.

IN COMMAND. IN CONTROL.

See what happens as your Turbo Pascal programs run...examine variables...change values...be in control. The top half of your screen displays the source code, current line highlighted. You debug interactively on the lower half. All variable types are accessible, local and global. Set breakpoints at a procedure, function, or statement number.

INSTANT GRATIFICATION.

T-DebugPLUS integrates invisibly, automatically loading Turbo Pascal. Switch instantly between the debug and output screen. Jump instantly to the editor to fix that bug.

NEW...DEBUG IN OVERLAYS.

Debug in overlays with release 1.04. Examine areas of memory and CPU registers. A MAP generation utility even lets you use an external debugger on your program. T-DebugPLUS is only \$60.

"T-DebugPLUS: Don't program in Turbo Pascal without it!"

Neil Rubenking
PC Magazine

MORE POWER. MORE PRODUCTIVITY.

Turbo EXTENDER™ helps you break the 64K barrier for both code and data; use all 640K. A source

code conversion program, make facility, and run-time routines make writing and compiling large programs dramatically easier. Turbo EXTENDER is only \$85.

TurboPower Utilities™ supplies nine powerful programs. Four Pascal utilities, including the acclaimed Pascal Structure Analyzer and Execution Timer, help you write programs that are bug free, faster, and easier to document. Five PC-DOS utilities help you analyze, change, and find your program files. TurboPower Utilities is only \$55 for executable, \$95 with source.

"Impressive products...I recommend them."

Philippe Kahn, President
Borland International

Satisfaction guaranteed or your money back within 30 days.


Call toll free for credit card orders:

800-538-8157 x830


outside California or
800-672-3470 x830
in California

Shipping and taxes prepaid for U.S. and Canadian customers. Others please include \$6 per item for shipping.

TurboPower Software products require Turbo Pascal 3.0 (standard, 8087, or BCD) and require PC-DOS 2.X or 3.X, and run on the IBM PC/XT/AT and compatibles.



TurboPower Software, 3109 Scotts Valley Dr. #122
Scotts Valley, CA 95066
Call 408-438-8608 for more information (M-F 9AM-5PM PST).



neither a *LEAF* nor a *BLEND*, it is marked as a *WASH*. This happens when none of the four children share a common color either because they are really four different colors or some of them are *WASH* nodes and have no color information. The node type is used later when this node's parent node is passed to *condense()* and this node is then one of the child nodes. It is also used during output of the quadtree because *WASH* nodes are not output.

Relnode() is the complement of *crtnode()*—it releases an unneeded node. For efficiency, this routine could add the node to a linked list of free nodes from which *crtnode()* could get space for new nodes. It is implemented here as a call to the system routine *free()*.

Getcolor(), called by *addnode()* when it reaches a leaf node at the bottom level, is a function to return the color of the pixel represented by a bottom-level node. The majority of the code is concerned with converting the position of the node in the quadtree, given as its locational code, to a column and row (x and y) pixel position. The code does this by extracting the directions shifted into the locational code by *addnode()* in the process of building the locational code. Because this is a bottom-level node, the number of direction values is equal to the top-level number. *Getcolor()* shifts the direction value for each level, starting with the top level or root, to the bottom bits and masks them off. As the direction code is recovered for each level, the column and row values are shifted left one bit and the new bottom bit is set or not depending on the direction. This works because the direction values define two simultaneous binary searches through the pixel space. The first search, for column, successively splits the pixel space into left and right halves. The second search, for row, successively splits the pixel space into upper and lower halves. Thus each bit in the column or row value is a direction in the binary search. Whereas the locational code needs two bits to represent one of four directions, the column and row values need one bit to represent one of two directions.

Outtree() and *outnode()* are the control routines for the second phase of Listing One—outputting the quadtree as locational codes. In order to output the nodes in a breadth-first order—that is, all nodes at one level are output before any lower-level nodes—*outtree()* and *outnode()* construct a linked list of nodes yet to be dealt with. As the node at the front of the list is examined, and possibly output, its children are added to the end of the list. The linked list serves as a FIFO queue, which means that each level, starting from the top, is processed before the next level is started. *Outtree()* initializes the linked list by putting the root node on it and setting its next pointer to *NULL*. It then enters a loop calling *outnode()* with the next node on the list until the list is exhausted. *Outnode()* checks the node type of the current node and outputs the locational code and color if the node is not a *WASH*. During this final pruning of the quadtree, nodes whose only function in the quadtree was to point to lower-level nodes are dropped from the locational code form because the pointers are no longer needed. The routine *putlcc()* is not defined here because what it does could be system or

application dependent. The simplest thing for *putlcc()* to do is write the data to a file for later processing or display. *Putlcc()* could also transmit the data to a remote display. After *putlcc()* is called, the node's children, if any, are added to the end of the list.

Listing Two

Listing Two, page 44, presents a set of routines for displaying a quadtree from a locational code form. As with the first set of routines, no main routine is given and only a single routine needs to be called. The main routine will have to do whatever initialization is necessary, such as opening the file containing the quadtree and reading in a header section or opening a communications channel. It may also need to initialize a graphics system or at least clear the screen. *Qdisp()* is the entry point for the second set of routines. It needs to know the size of the original image, which could be read from a file header associated with the quadtree file or supplied by the user. These routines make calls to two externally defined routines that you must supply. These are *getnxcn()*, which returns the next quadtree node as a locational code and a color, and *filrec()*, which fills in a rectangle on the display with a given color.

Most of *qdisp()* is a loop that gets the next node as a locational code and color by a call to *getnxcn()*, converts the locational code to the corner and side of the square represented, and fills in the square with the color by a call to *filrec()*. *Getnxcn()* and *filrec()* are assumed to be supplied separately because they might be both system and application dependent. *Getnxcn()*, for instance, might be reading the quadtree data from a file or reading it from a serial port. *Filrec()* is given the upper-left corner and sides of a rectangle (node quadrants are, of course, always square, but *filrec()* is presumed to be more general) and a color, and it fills the defined rectangle on the display with the color. If you are lucky enough to be using a system with a graphics package that supplies such a call (or better yet, a display that has the function available in hardware), then the implementation of *filrec()* should be simple. If you are not so lucky, then *filrec()* may have to loop over all the pixels in the rectangle, setting each to the given color.

The routine *square()* converts a locational code to the corner and side of the square represented by the node. It is very similar to *getcolor()* in Listing One. Because the level of the node is not known, the code must search the locational code for the beginning marker. After finding this, the code loops, like *getcolor()*, over the direction values from the root to the current node. At each iteration, the length of the side, initialized to the original image size, is divided by two and the corner position is adjusted according to which quadrant is indicated.

Practical Considerations

Quadtrees in pointer form can use up a lot of memory. In the worst case, in which no nodes can be released during construction, an image of size $N (= 2^k)$ would require more than $N \times N$ nodes. For example, an image of 256×256 pixels could require more than 64K nodes. Using my data structure for a node, this takes up 2 megabytes of memory on a machine that uses 4 bytes for *ints* and pointers. A more efficient structure may be needed. Using

smaller fields and/or combining fields would be one way to reduce memory needs. The node type field could be removed with some additional processing—the type *LEAF* could be deduced from the fact that all child pointers are *NULL* and, because the color of a *WASH* node is meaningless, a special value in the color field could indicate that a node was a *WASH*.

Besides the memory problem, the time required to create the quadtree may also prove to be a problem. Despite some efforts to speed up the process, such as switching to a base 4 representation for the locational codes, creating the quadtree is still very slow. One improvement, as mentioned already, might be to change the way *crtnode()* and *relnode()* get and release nodes. Another might be to keep more information about the location of the current node so that *getcolor()* does not have to figure this out from the locational codes. I think, however, that major improvements will require somehow avoiding all the hundreds (or thousands) of calls to *addnode()* and *condense()* for sections of the image that are a single color and could be quickly defined as a few high-level nodes.

Much to my disappointment, the display of the quadtree is not very fast. Even on a display that supports rectangle fill, a scan-line display of an image is faster than the quadtree display, although the display of the quadtree is more interesting to watch. For any reasonably interesting image, a lot of individual pixels must ultimately be filled in to complete the image and this takes a lot of time.

Despite these problems, quadtrees can offer some advantages over other graphical image representations and, in some cases, may be the best choice.

Availability

All the source code for articles in this issue (except *C Chest*) is available on a single disk. To order, send \$14.95 to *Dr. Dobb's Journal*, 501 Galveston Dr., Redwood City, CA 94063 or call (415) 366-3600 ext. 216. Please specify the issue number and disk format (MS-DOS, Macintosh, Kaypro).

Bibliography

Gargantini, I. "An Effective Way to Represent Quadtrees." *Communications of the ACM*, vol. 25, no.12 (December 1982): 905-910.

Jones, L., and Iyengar, S. "Representation of Regions as a Forest of Quadtrees." *Proceedings of the IEEE Conference on Pattern Recognition* (1981): 57-59.

Samet, H. "An Algorithm for Converting Rasters to Quad-trees." *IEEE Transactions in Pattern Analysis and Machine Intelligence*, vol. 3, no. 1 (January 1981): 93-95.

Samet, H. "Data Structures for Quadtree Approximation and Compression." *Communications of the ACM*, vol. 28, no. 9 (September 1985): 973-993.

Scott, S., and Iyengar, S. "TID—A Translation Invariant Data Structure for Storing Images." *Communications of the ACM*, vol.29, no. 5 (May 1986): 418-429.

Witten, I. H., and Cleary, J. G. "Foretelling the Future by Adaptive Modeling." *ABACUS*, vol.3, no.3 (Spring 1986): 16-36, 73.



(Listings begin on page 40.)

Vote for your favorite feature/article.
Circle Reader Service No. 1.

IQCLISP

More Common Lisp features in less space
for less money than any other IBM-PC lisp.

- MSDOS portable
- Bignums, 8087 support
- Multidimensional arrays
- Full Common Lisp package system
- Full set of control primitives.
- Keyword parameters, macros
- Save/restore full environments for speed
- STEP, TRACE, BREAK, DEBUG, ADVISE, APROPOS
- Roll-out frees space for invoking MSDOS commands

IQCLISP PACKAGE \$300.

LISP

Integral Quality

P.O. Box 31970
Seattle, Washington 98103
(206) 527-2918

IDLISP

Now with a compiler.

- Compiler comes with source
- Compiler cuts execution time 50-75%,
program size 60-80%
- Multidimensional arrays
- Floating point, bignums, 8087 support
- Macros
- Color graphics
- Multiple display windows
- Assembly language interface
- Available for IBM PC or TI-PRO

IDLISP PACKAGE \$270.
INCLUDES COMPILER

- VISA and Mastercard accepted
- Generous update policy
- Attractive educational license

Circle no. 327 on reader service card.

ARC Wars: MS-DOS Archiving Utilities

by Russell Nelson

Since the dawn of computers, people have been trying to make their computers run faster. One speedup technique is data compression, which lets the computer operate on less data while still accomplishing the same amount of work.

Data compression relies on the fact that most data are not random. English language text, for example, has a known character distribution—the letter *E* occurs more often than *T*, *T* more often than *O*, and so on. A data compression algorithm relies on these quirks to use fewer bits to represent the same data. For users downloading from bulletin boards, this approach translates into lower phone bills.

The old standard for data compression was a combination of three programs—one to combine files into one library (LU, library utility), one to squeeze this library into fewer bits (SQ), and another to unsqueeze the library (USQ). The squeeze program would produce a Huffman encoding¹ of its input file.

Thom Henderson of System Enhancement Associates (SEA) created ARC to provide an alternative to LU. ARC can add files to an archive and automatically determine which of four different compression methods to use. An archive can never be much larger than the component files because one of the four "compression" methods consists simply of storing

Data compression relies on the fact that most data are not random.

the file unaltered.

In actual use, the savings are often considerable. After automatic compression was added, ARC performed better than the LU/SQ/USQ combination, and within seven months of its introduction, it became the new standard for BBS files. This could have happened just because it was more convenient, but more probably it was because it used an improved compression algorithm—the Lempel-Ziv² algorithm.

In fact, ARC became so popular that spin-offs using the same file format appeared. Spin-offs were easy to develop because SEA made the ARC source available. At present, four different ARC-compatible systems and one ARC-incompatible system are in use. This article reviews the performance of each of them on different sets of files.

The Programs

Table 1, below, lists the current (as of October 1986) program versions that comprise each of the five archiving systems. Note that two of the systems are distributed as separate programs—PKARC and PKXARC form one system; ARCA, ARCE, and ARCV form another. The other three systems are ARC, ARCH, and ZOO.

The Donation column in Table 1 gives the suggested donation if the software is shareware. Some of the software is copyrighted, but no donation is suggested. The Cost column gives the cost of the software including automatic updates, printed documentation, and so on. All these programs are freely copyable.

The box on page 28 gives the author's address for each system. In addition, all the files mentioned in this article are available from the Clarkson University Heath Users Group (CUHUG) Fido—(315) 268-6667, 300/1,200/2,400 baud, 24 hours—as well as from many other BBSS. ARC and PKXARC are distributed as self-extracting .COM files; the other programs are distributed in archive form. Look for ARC*. and PKX*. if the BBS has a wildcard list function.

| Program | Version | Size (bytes) | Donation | Cost |
|---------|---------|--------------|----------|------|
| ARC | 5.12 | 32429 | \$35 | \$50 |
| ARCA | 1.18 | 3796 | none | |
| ARCE | 2.06 | 5424 | none | |
| ARCV | 1.15 | 2063 | none | |
| ARCH | 5.38 | 32694 | none | |
| PKARC | 1.1 | 15972 | \$15 | \$35 |
| PKXARC | 3.2 | 9984 | \$15 | \$35 |
| ZOO | 1.20 | 29120 | none | |

Table 1: Program versions

Russell Nelson, 11 Grant St., Potsdam, NY 13676. Russell is the author of *Painter's Apprentice*. He holds an M.S.E.E. degree from Clarkson University in Potsdam, New York.

In addition to the archive programs discussed in this article, the CUEHUG Fido has the following related files: DARC.ARC, which deletes from the disk any files that may be found in the archive; XONE2.ARC, which extracts one file from an archive into a new archive containing just that file; LZ.ARC, which contains assembly-language source for a Lempel-Ziv compressor and decompressor; ARCX.ARC, which contains Turbo Pascal source for an archive extractor; and ARC44.ARC, which contains the source for Version 4.4 of ARC.

Comparison of Features

Table 2, below, lists the features that each program provides. Most of the titles are self-explanatory; those that aren't are:

- Add files to archive: Obviously all archive systems can add files to an archive but not all programs in an archive system can do so.
- Alphabetic file names: Because ARC uses a distributed directory (the file names are not kept in a central location), alphabetic adding means that the files in the archive must be reordered when a new file is added and a copy of the archive must be made. The advantage of not copying the archive is that an archive can fill a

whole floppy rather than being limited to just half. ZOO uses a version numbering scheme to avoid copying. ARCA simply ignores the issue and makes two copies of the file, only the first of which is accessible.

- Damaged headers: If an archive gets munged, a file header can be damaged. Some archivers can skip the damaged file; some just give up.
- Extract to explicit path: Sometimes you might want to extract a file to a subdirectory/drive other than the current one.
- Forced storing: Because data compression can take a fair bit of time, some archivers allow you to force the files to be added uncompressed for later compression of the entire archive.
- Freshen files already in archive: Only newer files already in the archive are archived.
- List file names only: This is useful if you want to pipe the list of file names to another program.
- Only packing and crunching: Some archivers don't bother to squeeze or store a file.
- Update adds only newer files: Older files in the archive are left alone.
- Wildcard archive file names: You can specify an ambiguous archive file name using wildcards in combination with some operations.

Benchmarks

I ran benchmarks using a 5-MHz Z100 with a V20 to run MS-DOS 2.18—all the programs run under generic MS-DOS. I stored the files and programs in a RAM disk so that physical disk access times were not significant. The verbose listings were redirected to a file, so console output time is not reflected in the run time.

I have tried to use test data that is easily obtainable. ARC44 is an archive of the source of ARC, Version 4.4, and I used it to test the ability of an archiver to cope with a file that cannot be compressed further. The MASM benchmark is the MASM, Version 4.0, distribution disk, and I included it to test the compression of nontext files. The TDebug benchmark is the source of TDebug Plus, available from Turbo Power Software; I included it to test the compression of text files.

I tested only the most common operations—add, add to existing, delete, list, and extract. Results of the benchmark tests are shown in Table 3, page 28. I assume less common operations, such as update, freshen, and move, will be roughly similar in speed. Example 1, page 30, shows the output of verbose listings for some of the archive systems. There is not much to say because all give the same information and have similar run times.

| | ARC | ARCA | ARCE | ARCV | ARCH | PKARC | PKXARC | ZOO |
|-----------------------------------|-----|------|------|------|------|-------|--------|-----|
| Add files to archive | y | y | - | - | y | y | - | y |
| Alphabetic file names | y | - | - | - | y | y | - | - |
| Archive file compatible | y | y | y | y | y | y | y | - |
| Comments attached to files | - | - | - | - | - | y | - | y |
| Copies while modifying | y | - | - | - | y | y | - | - |
| Damaged headers | y | y | - | - | y | - | - | n/a |
| Delete files after adding | y | y | - | - | y | y | - | y |
| Encryption | y | - | - | - | - | - | - | - |
| Extract files to console | y | - | - | - | y | - | y | y |
| Extract files to printer | - | - | - | - | - | - | y | - |
| Extract into archive | - | - | - | - | y | - | - | - |
| Extract to explicit path | - | - | y | - | - | - | y | - |
| Forced storing | y | - | - | - | y | - | - | y |
| Freshen files already in archive | y | - | - | - | y | y | - | y |
| List file names only | - | - | - | - | y | - | - | y |
| Make backup of the archive file | y | - | - | - | y | - | - | y |
| Only packing and crunching | - | y | - | - | - | - | - | - |
| Replace existing files on extract | y | - | y | - | y | - | y | y |
| Test archive integrity | y | - | - | - | y | - | y | y |
| Update adds only newer files | y | - | - | - | y | y | - | y |
| Verbose listing of archive | y | - | - | - | y | - | y | y |
| Wildcard archive file names | - | - | y | y | y | y | y | y |

Table 2: Comparison of features

ARC WARS

(continued from page 27)

Conclusions

As shown in Table 3, PKARC is the fastest archiver by a wide margin,

and PKXARC is the fastest extractor. PKARC also produced the smallest archives in all but one instance, in which ZOO was slightly smaller. ARCA/ARCE/ARCV, PKARC/PKXARC, and ZOO are written in assembly lan-

guage, whereas ARC and ARCH are written in C. If you don't mind the donation, PKARC/PKXARC is the system to use.

ZOO performed adequately. ZOO is the only explicitly public-domain ar-

Authors/Vendors

ARC

Thom Henderson
System Enhancement Associates
21 New St.
Wayne, NJ 07470

For \$50 you receive a program disk with printed documentation. If you obtain ARC by other means, then you cannot use it in a commercial environment or a government organization unless you pay a \$35 license fee. Site licenses and commercial distribution licenses are available, as is the full program source.

ARCA, ARCE, ARCV

Vernon D. Buerg
456 Lakeshire Dr.
Daly City, CA 94015
CompuServe: 70007,1212

Data/RBBS: (415) 994-2944

ARCH

Les Satenstein
PCOM RBBS Montreal
(514) 989-9450

Given the similarity in features, run time, and results, ARCH must be a modified copy of ARC. The ARC copyright permissions strictly prohibit distribution of modified copies of ARC. Nevertheless, ARCH has more features than ARC, and so I included it in this review.

PKARC, PKXARC

Phil Katz
7032 Ardara Ave.
Glendale, WI 53209
Send comments to:

Exec-PC multiuser IBM BBS
modem: (414) 964-5160

If you find PKARC and PKXARC fast, easy, and convenient to use, a contribution of \$15 would be appreciated. With each contribution of \$35 or more, you receive free upgrades of the next versions of PKARC and PKXARC when available, including documentation.

ZOO

Rahul Dhesi
Genie: DHESI
People/Link: OLS806
ARPAnet/CSnet: dhesi%bsu@csnet-relay.ARPA
UUCP: !seismo!csnet relay
.ARPA!bsu!dhesi
ZOO is in the public domain.

Archive add—ARC44—archive of source of ARC (57,728 bytes)

| | ARC | ARCA | ARCH | PKARC | ZOO |
|--------------------|--------|--------|--------|--------|--------|
| Run time (seconds) | 144.66 | 42.42 | 150.27 | 25.86 | 40.41 |
| Size (bytes) | 57,728 | 58,014 | 57,728 | 57,728 | 57,728 |
| Total size (bytes) | 57,759 | 65,564 | 57,759 | 57,759 | 60,625 |
| Stowage | stored | packed | stored | stored | stored |

Archive add—MASM 4.00 distribution disk (288,122 bytes total)

| | ARC | ARCA | ARCH | PKARC | ZOO |
|-----------------------|---------|---------|---------|---------|---------|
| Run time (seconds) | 648.77 | 122.41 | 653.73 | 92.11 | 124.91 |
| Total size (bytes) | 237,072 | 221,751 | 237,072 | 221,020 | 221,907 |
| Compression (percent) | 17 | 23 | 17 | 23 | 23 |

Archive add—TDebug Plus source (289,049 bytes total, all ASCII)

| | ARC | ARCA | ARCH | PKARC | ZOO |
|-----------------------|---------|---------|---------|---------|---------|
| Run time (seconds) | 373.44 | 86.56 | 364.17 | 65.36 | 82.25 |
| Total size (bytes) | 116,802 | 116,255 | 116,802 | 115,950 | 113,013 |
| Compression (percent) | 59 | 59 | 59 | 59 | 61 |

Archive extract—ARC44—archive of source of ARC (57,728 bytes)

| | ARC | ARCE | ARCH | PKXARC | ZOO |
|----------|--------|-------|--------|--------|-----|
| Run time | 136.87 | 51.27 | 139.75 | 50.98 | n/a |

Archive extract—MASM 4.00 distribution disk (288,122 bytes total, 13,595 bytes ASCII)

| | ARC | ARCE | ARCH | PKXARC | ZOO |
|----------|--------|-------|--------|--------|-------|
| Run time | 244.39 | 58.06 | 252.00 | 46.74 | 69.64 |

Archive extract—TDebug Plus source (289,049 bytes total, all ASCII)

| | ARC | ARCE | ARCH | PKXARC | ZOO |
|----------|--------|-------|--------|--------|-------|
| Run time | 182.60 | 42.73 | 188.30 | 33.43 | 54.86 |

Table 3: Benchmark results

Name _____
 Title _____
 Company _____ Phone _____
 Address _____
 City/State/Zip _____

March 1987 #125

Expiration Date: June 30, 1987

Please circle one letter in each category:

I. My work is performed:

- A. for in-house use only.
- B. for other companies.
- C. for end users/retailers.
- D. in none of the above areas.

II. My primary job function:

- A. Software Project Mgmt/Spvr
- B. Hardware Project Mgmt/Spvr
- C. Computer Consultant
- D. Corporate Consultant
- E. Other

III. My company department performs:

- A. software development.
- B. computer system integration.
- C. computer manufacturing.
- D. computer consulting.
- E. computer research
- F. none of the above.

IV. This inquiry is for:

- A. a purchase within 1 month.
- B. a purchase within 1 to 6 months.
- C. product information only.

V. Corporate Purchase Authority:

- A. Final Decision-maker
- B. Approve/Recommend
- C. No Influence

VI. Personal Computer Users at my Jobsite:

- A. 10,000 or more
- B. 500 to 9,999
- C. 100 to 499
- D. 10 to 99
- E. less than 10

VII. On average, I advise others about computers:

- A. more than once per day.
- B. once per day.
- C. once per week.
- D. less than once per week.

VIII. In my job function, I:

- A. design software and/or write code.
- B. design software.
- C. write code.
- D. don't design software or write code.

A Reader Service number appears on each advertisement. Circle the corresponding numbers at right for more info.

| | | | | | | | |
|-----|-----|-----|-----|-----|-----|-----|-----|
| 1 | 2 | 3 | 4 | 5 | 6 | 7 | 8 |
| 11 | 12 | 13 | 14 | 15 | 16 | 17 | 18 |
| 19 | 21 | 22 | 23 | 24 | 25 | 26 | 27 |
| 28 | 29 | 31 | 32 | 33 | 34 | 35 | 36 |
| 37 | 38 | 39 | 41 | 42 | 43 | 44 | 45 |
| 46 | 47 | 48 | 49 | 51 | 52 | 53 | 54 |
| 55 | 56 | 57 | 58 | 59 | 61 | 62 | 63 |
| 64 | 65 | 66 | 67 | 68 | 69 | 71 | 72 |
| 73 | 74 | 75 | 76 | 77 | 78 | 79 | 81 |
| 82 | 83 | 84 | 85 | 86 | 87 | 88 | 89 |
| 91 | 92 | 93 | 94 | 95 | 96 | 97 | 98 |
| 99 | 101 | 102 | 103 | 104 | 105 | 106 | 107 |
| 108 | 109 | 111 | 112 | 113 | 114 | 115 | 116 |
| 117 | 118 | 119 | 121 | 122 | 123 | 124 | 125 |
| 126 | 127 | 128 | 129 | 131 | 132 | 133 | 134 |
| 135 | 136 | 137 | 138 | 139 | 141 | 142 | 143 |
| 144 | 145 | 146 | 147 | 148 | 149 | 151 | 152 |
| 153 | 154 | 155 | 156 | 157 | 158 | 159 | 161 |
| 162 | 163 | 164 | 165 | 166 | 167 | 168 | 169 |
| 171 | 172 | 173 | 174 | 175 | 176 | 177 | 178 |
| 179 | 181 | 182 | 183 | 184 | 185 | 186 | 187 |
| 188 | 189 | 191 | 192 | 193 | 194 | 195 | 196 |
| 197 | 198 | 199 | 201 | 202 | 203 | 204 | 205 |
| 206 | 207 | 208 | 209 | 211 | 212 | 213 | 214 |
| 215 | 216 | 217 | 218 | 219 | 221 | 222 | 223 |
| 224 | 225 | 226 | 227 | 228 | 229 | 231 | 232 |
| 233 | 234 | 235 | 236 | 237 | 238 | 239 | 241 |
| 242 | 243 | 244 | 245 | 246 | 247 | 248 | 249 |
| 251 | 252 | 253 | 254 | 255 | 256 | 257 | 258 |
| 259 | 261 | 262 | 263 | 264 | 265 | 266 | 267 |
| 268 | 269 | 271 | 272 | 273 | 274 | 275 | 276 |
| 277 | 278 | 279 | 281 | 282 | 283 | 284 | 285 |
| 286 | 287 | 288 | 289 | 291 | 292 | 293 | 294 |
| 295 | 296 | 297 | 298 | 299 | 301 | 302 | 303 |
| 304 | 305 | 306 | 307 | 308 | 309 | 311 | 312 |
| 313 | 314 | 315 | 316 | 317 | 318 | 319 | 321 |
| 322 | 323 | 324 | 325 | 326 | 327 | 328 | 329 |
| 331 | 332 | 333 | 334 | 335 | 336 | 337 | 338 |
| 339 | 341 | 342 | 343 | 344 | 345 | 346 | 347 |
| 348 | 349 | 351 | 352 | 353 | 354 | 355 | 356 |
| 357 | 358 | 359 | 361 | 362 | 363 | 364 | 365 |
| 366 | 367 | 368 | 369 | 371 | 372 | 373 | 374 |
| 375 | 376 | 377 | 378 | 379 | 381 | 382 | 383 |
| 384 | 385 | 386 | 387 | 388 | 389 | 391 | 392 |
| 393 | 394 | 395 | 396 | 397 | 398 | 399 | |

Circle 999 to start a 12 month subscription at the price of \$29.97

**TAKE THIS CARD WITH YOU
 AS YOU READ THROUGH
 THIS ISSUE OF DR. DOBB'S.**



NO POSTAGE
 NECESSARY
 IF MAILED
 IN THE
 UNITED STATES


BUSINESS REPLY MAIL

FIRST CLASS PERMIT #217, CLINTON, IOWA

POSTAGE WILL BE PAID BY ADDRESSEE

**Dr. Dobb's Journal of
 Software Tools**
 FOR THE PROFESSIONAL PROGRAMMER

P.O. Box 2157
 Clinton, Iowa 52735-2157



**Technical Product
 Information.**

NO POSTAGE
NECESSARY
IF MAILED
IN THE
UNITED STATES

BUSINESS REPLY MAIL

FIRST CLASS PERMIT #217, CLINTON, IOWA

POSTAGE WILL BE PAID BY ADDRESSEE

**Dr. Dobb's Journal of
Software Tools**
FOR THE PROFESSIONAL PROGRAMMER

P.O. Box 2157
Clinton, Iowa 52735-2157

**TAKE THIS CARD WITH YOU
AS YOU READ THROUGH
THIS ISSUE OF DR. DOBB'S.**

**Technical Product
Information.**

Dr. Dobb's Journal of Software Tools

Name _____
Title _____
Company _____ Phone _____
Address _____
City/State/Zip _____

March 1987 #125 Expiration Date: June 30, 1987

Please circle one letter in each category:

I. My work is performed:

- A. for in-house use only.
- B. for other companies.
- C. for end users/retailers.
- D. in none of the above areas.

II. My primary job function:

- A. Software Project Mgmt/Spvr
- B. Hardware Project Mgmt/Spvr
- C. Computer Consultant
- D. Corporate Consultant
- E. Other

III. My company department performs:

- A. software development.
- B. computer system integration.
- C. computer manufacturing.
- D. computer consulting.
- E. computer research
- F. none of the above.

IV. This inquiry is for:

- A. a purchase within 1 month.
- B. a purchase within 1 to 6 months.
- C. product information only.

V. Corporate Purchase Authority:

- A. Final Decision-maker
- B. Approve/Recommend
- C. No Influence

VI. Personal Computer Users at my Jobsite:

- A. 10,000 or more
- B. 500 to 9,999
- C. 100 to 499
- D. 10 to 99
- E. less than 10

VII. On average, I advise others about computers:

- A. more than once per day.
- B. once per day.
- C. once per week.
- D. less than once per week.

VIII. In my job function, I:

- A. design software and/or write code.
- B. design software.
- C. write code.
- D. don't design software or write code.

A Reader Service number appears on each advertisement. Circle the corresponding numbers at left for more info.

1 2 3 4 5 6 7 8 9 10
11 12 13 14 15 16 17 18 19 20
21 22 23 24 25 26 27 28 29 30
31 32 33 34 35 36 37 38 39 40
41 42 43 44 45 46 47 48 49 50
51 52 53 54 55 56 57 58 59 60
61 62 63 64 65 66 67 68 69 70
71 72 73 74 75 76 77 78 79 80
81 82 83 84 85 86 87 88 89 90
91 92 93 94 95 96 97 98 99 100
101 102 103 104 105 106 107 108 109 110
111 112 113 114 115 116 117 118 119 120
121 122 123 124 125 126 127 128 129 130
131 132 133 134 135 136 137 138 139 140
141 142 143 144 145 146 147 148 149 150
151 152 153 154 155 156 157 158 159 160
161 162 163 164 165 166 167 168 169 170
171 172 173 174 175 176 177 178 179 180
181 182 183 184 185 186 187 188 189 190
191 192 193 194 195 196 197 198 199 200
201 202 203 204 205 206 207 208 209 210
211 212 213 214 215 216 217 218 219 220
221 222 223 224 225 226 227 228 229 230
231 232 233 234 235 236 237 238 239 240
241 242 243 244 245 246 247 248 249 250
251 252 253 254 255 256 257 258 259 260
261 262 263 264 265 266 267 268 269 270
271 272 273 274 275 276 277 278 279 280
281 282 283 284 285 286 287 288 289 290
291 292 293 294 295 296 297 298 299 300
301 302 303 304 305 306 307 308 309 310
311 312 313 314 315 316 317 318 319 320
321 322 323 324 325 326 327 328 329 330
331 332 333 334 335 336 337 338 339 340
341 342 343 344 345 346 347 348 349 350
351 352 353 354 355 356 357 358 359 360
361 362 363 364 365 366 367 368 369 370
371 372 373 374 375 376 377 378 379 380
381 382 383 384 385 386 387 388 389 390
391 392 393 394 395 396 397 398 399 400

Circle 999 to start a 12 month subscription
at the price of \$29.97

"How to protect your software by letting people copy it"

By Dick Erett, President of Software Security



Inventor and entrepreneur, Dick Erett, explains his company's view on the

protection of intellectual property.

"A crucial point that even sophisticated software development companies and the trade press seem to be missing or ignoring is this:


Software protection must be understood to be a distinctively different concept from that commonly referred to as copy protection.

Fundamentally, software protection involves devising a method that prevents unauthorized use of a program, without restricting a legitimate user from making any number of additional copies or preventing program operation via hard disk or LANs.

Logic dictates that magnetic media can no more protect itself from misuse than a padlock can lock itself. Software protection must reside outside the actual storage media. The technique can then be made as tamper proof as deemed necessary.

If one is clever enough, patent law can be brought to bear on the method.

Software protection is at a crossroads and the choices are clear. You can give product away to a segment



Soon all software installation procedures will be as straightforward as this. The only difference will be whether you include the option to steal your product or not.

of the market, or take a stand against the theft of your intellectual property.

"...giving your software away is fine..."

We strongly believe that giving your software away is fine, if you make the decision to do so. However, if the public's sense of ethics is determining company policy, then you are no longer in control.

We have patented a device that protects your software while allowing unlimited archival copies and uninhibited use of hard disks and LANs. The name of this product is The BLOCK™.

The BLOCK is the only patented method we know of to protect your investment. It answers all the complaints of reasonable people concerning software protection.

In reality, the only people who could object are those who would like the option of stealing your company's product.

"...eliminating the rationale for copy-busting..."

Since The BLOCK allows a user to make unlimited archival copies the rationale for copy-busting programs is eliminated.

The BLOCK is fully protected by federal patent law rather than the less effective copyright statutes. The law clearly prohibits the production of work-alike devices to replace The BLOCK.

The BLOCK attaches to any communications port of virtually any microcomputer. It comes with a unique customer product number programmed into the circuit.

The BLOCK is transparent to any device attached to the port. Once it is in place users are essentially unaware of its presence. The BLOCK may be daisy-chained to provide security for more than one software package.

Each software developer devises their own procedure for accessing The BLOCK to confirm a legitimate user. If it is not present, then the program can take appropriate action.

"...possibilities... limited only by your imagination..."

The elegance of The BLOCK lies in its simplicity. Once you understand the principle of The BLOCK, hundreds of possibilities will manifest themselves, limited only by your imagination.

Your efforts, investments and intellectual property belong to you, and you have an obligation to protect them. Let us help you safeguard what's rightfully yours. Call today for our brochure, or a demo unit."

Software Security inc.

870 High Ridge Road Stamford, Connecticut 06905
203 329 8870

QUIT DOING GRUNT WORK.

Let Greenleaf do it for you
and set you free.

C Program developers, stop slaving!

Greenleaf libraries have the functions you need — already perfected and in use by winning program developers in major corporations such as IBM, EDS and GM.

Between our Greenleaf Functions and Greenleaf Comm Library, we have over 340 functions on the shelf. Each one can save you time and effort. Money, too.

Many C programmers have told us that, even if they only use one or two functions, our products easily pay for themselves:

The Greenleaf Functions

The most complete and mature C language function library for the IBM PC, XT, AT and close compatibles. Our version 3.0 includes over 225 functions — DOS, disk, video, color text and graphics, string, time/date, keyboard, new disk status and Ctrl-Break control functions plus many more!

The Greenleaf Comm Library


Our 2.0 version is the hottest communications facility of its kind. Over 120 all new functions — ring buffered, interrupt-driven asynchronous communications.

Call Toll Free

1-800-523-9830

In Texas and Alaska, call

214-446-8641



GREENLEAF

Software

**Greenleaf Software, Inc.
1411 LeMay Drive Suite 101
Carrollton, TX 75007**

If you need more than 2 ports, only Greenleaf gives you the total solution — boards, software, and complete instructions that enable you to build a 16-port communication system.

And no matter how many ports you have, it's virtually impossible to lose information with multiple file transfers. XMODEM, XON/XOFF and Hayes modem controls are featured.

We support all popular C compilers for MS DOS: Lattice, Microsoft, Computer Innovations, Wizard, Aztec, DeSmet and Mark Williams.

Order today!

Order a Greenleaf C library now. See your dealer or call 1-800-523-9830. Specify compiler when ordering. Add \$8 for UPS second day air, or \$5 for ground. Texas residents, add sales tax. Mastercard, VISA, P.O., check, COD. In stock, shipped next day.

Greenleaf

| | |
|--------------------------|-------|
| Comm Library v2.0 | \$185 |
| Greenleaf Functions v3.0 | \$185 |
| Digiboard Comm/4-II | \$315 |
| Digiboard Comm/8-II | \$515 |

We also sell compilers, books and combination packages.

CODE BLUE



PANASONIC FX-800

80286 8MHz • 1.2 MB Floppy

30 MB Hard Disk • 512K RAM

Monitor and
Graphics Card

\$2199

Custom configurations available



PANASONIC FX-800

8086 7.14 MHz • One 360K Floppy

20 MB Hard Disk • 640K

Monitor and
Graphics Card

\$1375



TOSHIBA T1100 PLUS

2 720KB Drives
8 hr. Battery • 640K

CALL

Aldebaran Labs

| | |
|--|------|
| Source Print | 109 |
| Compact Source Print | CALL |
| Tree Diagrammer | CALL |
| Alpha Computer | |
| ACS Time Series | 399 |
| For-Winds | 75 |
| Forlib-Plus | 52 |
| Scientific Subroutine Pkg. | 254 |
| Strings & Things | 52 |
| <i>Please specify Fortran Compiler</i> | |

Ariety

| | |
|-----------------------------|-----|
| Expert System Dev. Pkg. | 269 |
| File Interchange Toolkit | 45 |
| Prolog Compiler/Interpreter | 729 |
| Prolog Interpreter | 319 |
| Screen Design Toolkit | 45 |
| SQL Development Package | 269 |

Blaise

| | |
|------------------------|-----|
| Asynch Manager-C | 131 |
| Asynch Manager-Pascal | 131 |
| C Tools | 98 |
| C Tools 2 | 78 |
| C Tools Plus | 134 |
| EXEC Program Chainer | 74 |
| Pascal Tools | 98 |
| Pascal Tools 2 | 78 |
| Pascal Tools & Tools 2 | 134 |
| Runoff Text Formatter | 44 |
| Turbo Asynch Plus | 78 |
| Turbo Power Tools Plus | 78 |
| View Manager-C | 195 |
| View Manager-Pascal | 195 |

Borland

| | |
|-------------------------------|-----|
| Reflex | 97 |
| Reflex Workshop | 47 |
| Reflex & Reflex Workshop | 141 |
| Turbo Database Toolbox | 47 |
| Turbo Editor Toolbox | 47 |
| Turbo Gameworks Toolbox | 47 |
| Turbo Graphix Toolbox | 47 |
| Word Wizard | 47 |
| Turbo Lightning | 65 |
| Turbo Pascal w/8087 & BCD | 65 |
| Turbo Prolog | 64 |
| Turbo Tutor for Pascal | 27 |
| Word Wizard & Turbo Lightning | 98 |
| Turbo Pascal-Macintosh | 71 |

Computer Innovations

| | |
|---------------|------|
| C-86 | 279 |
| Introducing C | 99 |
| C to dBase | 129 |
| CI-86 Plus | CALL |
| CI Probe | 189 |
| CI ROMPac | 139 |

Entelekon

| | |
|--------------------|-----|
| Combo | 165 |
| C Function Library | 105 |
| C Windows | 105 |
| Superfonts for C | 42 |

Essential Software

| | |
|--------------------|-----|
| C Essentials | 82 |
| C Utility Library | 135 |
| Essential Graphics | 189 |

GSS

| | |
|------------------------------|-----|
| Graphics Development Toolkit | 369 |
|------------------------------|-----|

Kernel System (DOS)

| | |
|------------------------|-----|
| Kernel System (IBM RT) | 639 |
| Metafile Interpreter | 229 |

Plotting System

| | |
|--------------------|-----|
| Solutions Chart | 235 |
| Solutions Plottalk | 235 |
| Solutions Terminal | 235 |

Intel

| | |
|--------------------------|------|
| 386 Board (Avail. April) | CALL |
|--------------------------|------|

Laboratory Micro

| | |
|-----------------------------|-----|
| PC/Forth | 114 |
| PC/Forth Plus | 204 |
| Adv. Color Graphics Support | 75 |

Enhanced Graphics Support

| | |
|-------------------------------|----|
| 8087 Support | 75 |
| Interactive Symbolic Debugger | 75 |

Native Code Optimizer

| | |
|-------------------------|-----|
| PCTERM | 154 |
| Software Floating Point | 75 |

Lattice

| | |
|---------------------------|-----|
| C Compiler | 289 |
| C Compiler w/Library S.C. | 544 |
| C XREF Generator | 38 |
| C XREF Generator w/S.C. | 147 |
| C-Sprite | 135 |
| Curses Screen Mgr. | 93 |
| Curses Screen Mgr. w/S.C. | 181 |
| dBC | 186 |
| dBC w/Source Code | 369 |
| LMK Make Facility | 144 |

RPGII Combo

| | |
|---------------------------|-----|
| RPGII Compiler-No Royalty | 899 |
|---------------------------|-----|

Secret Disk

| | |
|----------|----|
| SideTalk | 92 |
|----------|----|

Text Management Utilities

| | |
|--------------------|-----|
| TopView Toolbasket | 186 |
|--------------------|-----|

TopView Toolbasket w/S.C.

| | |
|-----------------------|-----|
| Z-80 C Cross Compiler | 375 |
|-----------------------|-----|

Z-80 C X-Compiler w/S.C.

| | |
|--|-----|
| | 744 |
|--|-----|

Logitech

| | |
|----------------------|----|
| Modula-2/86 Compiler | 63 |
|----------------------|----|

Modula 2/86 w/8087

| | |
|------------------|-----|
| Modula 2/86 PLUS | 144 |
|------------------|-----|

Modula 2 Library Sources

| | |
|-----------------------|----|
| Modula 2 Make Utility | 26 |
|-----------------------|----|

Modula 2 ROM Package

| | |
|------------------------|-----|
| Modula 2 RunTime Debug | 177 |
|------------------------|-----|

Turbo-Modula Translator

| | |
|--------------------------|----|
| Modula 2 Utilities Pack. | 43 |
|--------------------------|----|

Modula 2 Windows Pack.

| | |
|--|----|
| | 43 |
|--|----|

Mice listed on next page.

MetaGraphics

| | |
|-------------|-----|
| MetaWindows | 135 |
|-------------|-----|

MetaWindows Plus

| | |
|--------------|-----|
| TurboWindows | 195 |
|--------------|-----|

MicroFocus

All products available.

MicroHelp

| | |
|---------------|----|
| Peeks n Pokes | 38 |
|---------------|----|

Inside Track

| | |
|--------|----|
| MACH 2 | 52 |
|--------|----|

Stay-Res

| | |
|--|----|
| | 62 |
|--|----|

QuickSoft

| | |
|---------------------------|----|
| Basic Interpreter (XENIX) | 65 |
|---------------------------|----|

C Compiler

| | |
|----------------|-----|
| Cobol Compiler | 215 |
|----------------|-----|

Cobol Compiler (XENIX)

| | |
|-------------|-----|
| Cobol Tools | 282 |
|-------------|-----|

Cobol Tools (XENIX)

| | |
|------------------|-----|
| Fortran Compiler | 435 |
|------------------|-----|

Fortran Compiler (XENIX)

| | |
|------|-----|
| LISP | 619 |
|------|-----|

Macro Assembler

| | |
|-----------|-----|
| Bus Mouse | 299 |
|-----------|-----|

Serial Mouse

| | |
|------|-----|
| Sort | 129 |
|------|-----|

muMath & muSimp

| | |
|-----------------|-----|
| Pascal Compiler | 134 |
|-----------------|-----|

Pascal Compiler (XENIX)

| | |
|-------------------------|-----|
| Tech. Ref. Encyclopedia | 189 |
|-------------------------|-----|

Windows

| | |
|-------------------------|----|
| Windows Development Kit | 65 |
|-------------------------|----|

Phoenix

| | |
|------------------------|-----|
| Pasm86 Macro Assembler | 324 |
|------------------------|-----|

Pdisk Hard Disk Utility

| | |
|--------------|-----|
| Pfantasy Pac | 129 |
|--------------|-----|

Pfinish Performance Anal.

| | |
|-------------------------|------|
| Pfix-86+ Symbolic Debug | CALL |
|-------------------------|------|

PforCe C Library

| | |
|---------------------------|-----|
| Plink-86+ Enhanced Linker | 235 |
|---------------------------|-----|

Pmaker Make Utility

| | |
|-------------------------|-----|
| Pmate Macro Text Editor | 319 |
|-------------------------|-----|

Pre-C Lint Utility

| | |
|---------------------------|----|
| Ptel Binary File Transfer | 79 |
|---------------------------|----|

Polytron

| | |
|-----------|-----|
| PolyBoost | 119 |
|-----------|-----|

C Beautifier

| | |
|-------------|-----|
| C Library I | 159 |
|-------------|-----|

C Library II

| | |
|-------------|-----|
| Power Comm. | 115 |
|-------------|-----|

PolyLibrarian

| | |
|------------------|----|
| PolyLibrarian II | 74 |
|------------------|----|

PolyMake

| | |
|-------------|----|
| PolyOverlay | 74 |
|-------------|----|

PolyXREF-Complete

| | |
|-----------------------|-----|
| PolyXREF-One Language | 175 |
|-----------------------|-----|

PVCS Version Control Sys.

| | |
|------------------------|-----|
| PVMFM Virtual Mem Mgr. | 319 |
|------------------------|-----|

Raima

All products available.

RDS

All products available.

Relia

| | |
|-------|-----|
| Cobol | 829 |
|-------|-----|

Ryan-McFarland

| | |
|------------------|-----|
| RM/Cobol (XENIX) | 975 |
|------------------|-----|

RM/Fortran (XENIX)

| | |
|----------|-----|
| RM/Cobol | 589 |
|----------|-----|

RM/Cobol 8X ANSI 85

| | |
|------------|-----|
| RM/Fortran | 615 |
|------------|-----|

Santa Cruz Operation

| | |
|-----------------------|-----|
| Complete XENIX System | 875 |
|-----------------------|-----|

XENIX Development System

| | |
|--|-----|
| | 379 |
|--|-----|

XENIX Operating System

| | |
|-----------------------|-----|
| XENIX Test Processing | 519 |
|-----------------------|-----|

Package

| | |
|-------|-----|
| Lyrix | 149 |
|-------|-----|

Networks for XENIX

| | |
|------------------|-----|
| SCO Professional | 479 |
|------------------|-----|

Softcraft

| | |
|----------------------|-----|
| Btrieve ISAM Manager | 685 |
|----------------------|-----|

Xtrieve Query Utility

| | |
|--------------------------|-----|
| Rtrieve Report Generator | 162 |
|--------------------------|-----|

Btrieve/N Networks

| | |
|--------------------|-----|
| Xtrieve/N Networks | 119 |
|--------------------|-----|

Rtrieve/N Networks

| | |
|--|------|
| | CALL |
|--|------|

Flash-Up Windows

| | |
|------------|----|
| Flash Code | 75 |
|------------|----|

Screen Sculptor

| | |
|--------------|-----|
| Speed Screen | 119 |
|--------------|-----|

STSC

| | |
|-------------|----|
| APL PLUS/PC | 94 |
|-------------|----|

APL PLUS/PC Spreadsheet

| | |
|--------------------------|----|
| APL PLUS/PC Tools Vol. 1 | 28 |
|--------------------------|----|

APL PLUS/PC Tools Vol. 2

| | |
|-----------------------|-----|
| APL PLUS/UNIX (XENIX) | 439 |
|-----------------------|-----|

Financial/Stat. Library

| | |
|------------|-----|
| Pocket APL | 149 |
|------------|-----|

StatGraphics

| | |
|-------------|-----|
| BetterBasic | 229 |
|-------------|-----|

BetterBasic 8087 Support

| | |
|-------------------------------|----|
| BetterBasic Btrieve Interface | 59 |
|-------------------------------|----|

BetterBasic C Interface

| | |
|----------------------------|-----|
| BetterBasic RunTime Module | 695 |
|----------------------------|-----|

3.5" Drive Kit

| | |
|------------------------|-----|
| True Basic w/Converter | 194 |
|------------------------|-----|

True Basic w/Converter/

| | |
|---------|----|
| RunTime | 75 |
|---------|----|

Advanced String Library

| | |
|----------------------|-----|
| Asynch Communication | 589 |
|----------------------|-----|

Support

| | |
|------------------|----|
| BasicA Converter | 42 |
|------------------|----|

Btrieve Interface

| | |
|---------------------|----|
| Developer's Toolkit | 42 |
|---------------------|----|

Formlib

| | |
|---------------------------|----|
| Hercules Graphics Support | 42 |
|---------------------------|----|

Sorting & Searching

| | |
|----------------|----|
| RunTime Module | 42 |
|----------------|----|

TurboPower Software

| | |
|---------|----|
| T-Debug | 99 |
|---------|----|

Turbo Extender

| | |
|--------------------------------|----|
| Turbo Power Utilities w/source | 52 |
|--------------------------------|----|

Turbo Power Utilities no source

| | |
|--|----|
| | 65 |
|--|----|

Wendin

| | |
|--------------------------|----|
| Operating System Toolbox | 79 |
|--------------------------|----|

PCNX Operating System

| | |
|-------|----|
| PCVMS | 77 |
|-------|----|

XTC Text Editor with Source

| | |
|--|----|
| | 77 |
|--|----|

FREE BLUE LABEL SHIPPING*


20-Day Money Back Guarantee! Call for Details



TOSHIBA 3100

80286 • Gas Plasma Screen
10MB H.D. • 640K
720KB Drive

CALL



MICROSOFT®

MACH 10™

Performance Enhancement Board
with Windows
and Mouse.

\$375

Orders only:

(800) 232-6442

In California:

(800) 843-2842

Customer service:

(415) 322-0686

Send mail orders to:

Code Blue

508 Waverly Avenue

Palo Alto, CA 94301

Terms & Policies

1. At least 20-day money back guarantee on most products. We back all products with full manufacturer's warranty. Returned merchandise must be in resalable condition. Call for details.

2. Shipping charges: On orders over \$100, we ship free UPS 2nd day air. On orders under \$100, shipping is \$4 for UPS Ground, \$8 for 2nd day air. Call for shipping charges on hardware products. Overseas shipping available at additional charge.

3. This ad is prepared well in advance of publication. Please call for latest prices. Prices subject to change without notice.

4. Delivery subject to product availability. We carry only the latest versions.

5. P.O.'s accepted from qualified U.S. institutions. Call for credit applications.

6. Products not covered by the money back guarantee and those for which the money back guarantee has expired can only be returned for repair or replacement.

7. VISA and MasterCard accepted. COD available at additional cost. Personal checks take 10 days to clear.



* On all orders over \$100 to destinations east of the Rocky Mountains.

C COMPILERS

| | |
|------------------------------------|------|
| Datalight C Developer's Kit | 77 |
| Eco-C Development Sys. by Ecosoft | 85 |
| MWC-86 by Mark Williams | 285 |
| CI-86 Plus by Computer Innovations | CALL |
| Microsoft C | 269 |
| Lattice C | 289 |
| Lattice w/Source | CALL |
| Wizard C | 351 |
| Wizard C Combo | 585 |

TURBO PASCAL UTILITIES

| | |
|--|------|
| See Metagraphics, Software Bottling, and Turbo Power | |
| Alice by Software Channels | 67 |
| FirstTime for Turbo by Spruce Tech | CALL |
| Report Builder by Royal American | 89 |
| System Builder by Royal American | 54 |
| Turbo Professional by Sunny Hill | 45 |
| TurboHALO by IMSI | 86 |
| On Line Help by Opt Tech | 107 |

MORE LANGUAGES!

| | |
|-------------------------------|------|
| SNOBOL4+ by Catspaw | 81 |
| Methods by Digitalk | 67 |
| SmallTalk/V by Digitalk | 85 |
| SmallTalk/Comm by Digitalk | 42 |
| Personal REXX by Mansfield | 104 |
| CCS MUMPS by MGlobal | CALL |
| Janus/ADA C Pack by R&R | 85 |
| Janus/ADA D Pack by R&R | 789 |
| TransLisp by Solution Systems | CALL |

OTHER PRODUCTS

| | |
|----------------------------------|-----|
| Norton Utilities | 58 |
| Norton Commander | 52 |
| Mace Utilities by Paul Mace | 65 |
| Super PC-Kwik by Multisoft | 65 |
| PrintQ by Software Directions | 79 |
| TaskView by Sunny Hill | 60 |
| Dan Bricklin's Demo Program | 59 |
| Instant Replay by Nostrodamus | 75 |
| Fastback by FGS | 139 |
| Visible 8088 by Software Masters | 63 |
| Clipper by Nantucket | 389 |
| Quicksilver by Wordtech | 379 |

C UTILITIES

| | |
|---|------|
| See also Aldebaran Labs, Blaise, Computer Innovations, Entelekon, Essential Software, GSS, MetaGraphics, Polytron, and Raima. | |
| Greenleaf Functions | 132 |
| Greenleaf Data Windows | 179 |
| Greenleaf Data Windows with Source | 369 |
| Greenleaf Comm Library | 132 |
| Vitamin C by Creative Programming | CALL |
| VC Screen by Creative Programming | 83 |
| dBx dBase-C Translator by Al | 319 |
| dBx with Source Code | 494 |
| Basic C Library by C Source | 128 |
| c-tree by FairCom | 325 |
| r-tree by FairCom | 245 |
| GraphiC Mono by Scientific Endeavors | 207 |
| GraphiC Color by Scientific Endeavors | 285 |
| PC-Lint by Gimpel | 103 |
| Scientific Sub. Library by Peerless | 135 |
| Z View by Data Mgmt. Cons. | 187 |
| On Line Help by Opt Tech | 107 |
| Halo by Media Cybernetics | 212 |
| Panel by Roundhill Computers | 223 |
| HELP/Control by MDS | 105 |
| ROM Dev. Package by Wizard | 294 |
| PforCe Library by Phoenix | 235 |
| C Food Smorgasbord by Lattice | 97 |
| C Food Smorgasbord with Source | 187 |
| The Hammer by OES | 172 |
| On Line Help by Opt Tech | 115 |
| Many of these products are compiler specific. Call for details | |

EDITORS

| | |
|-----------------------------------|------|
| SPF/PC by Command Tech. | 141 |
| Vedit by CompuView | 107 |
| Vedit Plus by CompuView | 144 |
| PC/Vi by Custome Software Systems | 127 |
| Brief by Solution Systems | CALL |
| dBrief by Solution Systems | CALL |
| Epsilon by Lugaru | 157 |
| KEDIT by Mansfield | 104 |
| XTC by Wendin | 81 |

C INTERPRETERS

| | |
|---------------------------------------|-----|
| Run C by Lifeboat | 98 |
| Run C Professional by Lifeboat | 174 |
| Let's C by Mark Williams | 57 |
| Let's C with Source Debugger | 115 |
| Introducing C by Computer Innovations | 99 |

FORTRAN COMPILERS AND UTILITIES

| | |
|--|-----|
| See also Alpha Computer | |
| 50 More: Fortran by Peerless | 96 |
| Scientific Sub. Library by Peerless | 135 |
| Fortran Addenda by Impulse Engineering | 144 |
| Fortran Addendum | 86 |
| Microsoft Fortran | 207 |
| Ryan-McFarland Fortran | 379 |

MICE

| | |
|---|-----|
| Microsoft Bus Mouse | 119 |
| Microsoft Serial Mouse | 129 |
| Logitech Logimouse C7 Plus | 99 |
| Logimouse C7 Plus w/Paint | 129 |
| Logimouse C7 Plus w/CADD | 149 |
| Logimouse C7 Plus w/Paint and CADD | 174 |
| Logimouse C7 Plus-Bus Version | 119 |
| Mouse Systems Optical Mouse | 139 |
| Mouse Systems Optical Mouse-Bus Version | 145 |
| Specify DB-9 or DB-25 Connector | |

DEBUGGERS & PROFILERS

| | |
|------------------------------|------|
| The Watcher by StonyBrook | 54 |
| Codesmith-86 by Visual Age | 105 |
| Advanced Trace 86 by Morgan | 130 |
| 386 Debug by Phar Lap | 147 |
| 386 ASM/LINK by Phar Lap | CALL |
| DSD87 by Soft Advances | 85 |
| DSD86 by Soft Advances | 62 |
| Periscope I by Periscope Co. | 240 |
| Periscope II w/NMI Switch | 107 |
| Periscope II-X | 87 |
| Codesifter by David Smith | 95 |
| The Profiler by DWB | 91 |
| Pasm 86 by Phoenix | 129 |
| Pfinish by Phoenix | 235 |
| Pfix 86+ by Phoenix | 235 |

Optimizing Integer Multiplications by Constant Multipliers

by Robert D. Grappel

Integer multiplication by a constant multiplier can occur frequently in high-level language programs. Besides the explicitly coded multiplications, the compiler must generate multiplication instructions as part of each array reference. To address an array element, the compiler forms code to multiply the array index by the size of an array element (a constant). If the array elements are simple data types (bytes, words, and so on) then the multiplication is often done as a shift left because the size of the element is a power of 2. Some of the more powerful processors (Intel 80386, Motorola 68020, National 32016, and so on) provide scaled-indexed addressing modes that incorporate the appropriate shift as part of the address calculation.

If the array element is not a simple type, however, the multiplication must be done explicitly. Multiply dimensioned arrays require a multiplication for each index (except, perhaps, for the last one, which can be done with a shift).

Multiplication is a time-consuming operation, even on those processors that have multiplication instructions. Table 1, right, shows the execution times, in clock cycles, for several types of instructions, including multiplication, on some modern microprocessors. The 68000, for example, requires about 70 clocks for a 16-bit

**Some
multiplications
can be sped up
by 'unrolling' the
calculation.**

register-to-register multiplication instruction, compared to about 8 clocks for a 32-bit register-to-register addition or subtraction. A 32-bit register shift requires about 6 clocks plus an additional 2 clocks per shift position. Clearly, the 68000 can do several adds, subtracts, and shifts in the time it takes to perform one multiplication.

Indexing an array (without artificially limiting the size to 64K) requires a 32-bit multiplication, which necessitates at least two 16-bit multiplications and an addition on the 68000 along with some logic. Because this 32-bit multiplication is likely to be done as a run-time subroutine, there is often an additional setup and calling overhead, too. (The 16-bit multiplication of the Intel 80286 is sufficient to address an entire memory segment.) Thus, there is room for a compiler to fabricate an optimized sequence of additions, subtractions, and shifts in place of a multiplication on any of these processors.

Unrolling the Loop

Computers multiply numbers using some variation of the following algorithm:

1. Clear work register *Rw*, which becomes the product.
2. If the low-order bit of the multiplier is a 1, add the multiplicand to *Rw*.
3. Shift the multiplier right one bit position.
4. If the multiplier is 0, stop (product in *Rw*).
5. Shift the multiplicand left one bit position.
6. Go to step 2.

It is apparent that the computer performs multiplication as a sequence of shifts and additions—step 2 is an addition; steps 3 and 5 are shifts. If the multiplier is a constant, the algorithm can be “unrolled” into a sequence that includes only adds and shifts. This sequence is called a “star-chain” sequence because the result of each step is used immediately in the next step—no intermediate stores are required. The sequence requires only two registers—the original multiplicand and the work register in which the product is formed. Consider the following examples, in which the notation *R1* indicates the multiplicand, $\ll n$ means shift left *n* bit positions, and $+=R1$ means add the

Robert D. Grappel, 28 Buckmaster Dr., Concord, MA 01742. Robert Grappel has a Ph.D. in solid-state physics from Ohio University. He is currently a consultant involved in the design of new air-traffic control systems.

| | 80286 | 68000 | 68020 |
|----------------|-------|--------|-------|
| ADD | 2 | 8 | 0-3 |
| SUB | 2 | 8 | 0-3 |
| SHIFT <i>n</i> | $5+n$ | $6+2n$ | 1-4 |
| MUL 16 | 21 | 70 | 21-28 |
| MUL 32 | ** | ** | 41-44 |

Table 1: Timing for several basic arithmetic instructions (clock cycles)

multiplicand:

R1 * 10:

```
1 Rw = R1
2 Rw <<= 1
3 Rw += R1
4 Rw <<= 2
5 Rw += R1
```

R1 * 7:

```
1 Rw = R1
2 Rw <<= 1
3 Rw += R1
4 Rw <<= 1
5 Rw += R1
6 Rw <<= 1
7 Rw += R1
```

Note that the shifts and additions always come in pairs. Note, also, that there are as many shift-add pairs as there are one bits in the multiplier. This implies that the worst-case sequence will have as many shift-adds as the bit width of the multiplier.

You can generate shorter sequences by using shift-subtract as well as shift-add pairs. If the notation $2^{\hat{n}}$ indicates 2 to the power n , you can write $((2^{\hat{n}}) - 1)$ to denote a binary integer with n 1s in a row (for example, $8 - 1 = 7$). Hence, the sequence shown above can be shortened to:

R1 * 7:

```
1 Rw = R1
2 Rw <<= 3
3 Rw -= R1
```

Here one shift-subtract replaces three shift-adds. The worst case is now alternating 1s and 0s in the multiplier, requiring at most one-half the number of sequence steps.

A further improvement can be made in the algorithm. Some numbers (such as 55 and 119) have a series of 1s, then a single 0, then another series of 1s ($119 = 1110111$ binary). The algorithm would generate a shift-subtract, then a shift-add by one place. Here is the sequence for 119:

R1 * 119:

```
1 Rw = R1
2 Rw <<= 3
3 Rw -= R1
4 Rw <<= 1
5 Rw += R1
6 Rw <<= 3
7 Rw -= R1
```

```
#include <stdio.h>
/* Program to generate a "star-chain" sequence to replace
multiplication by a positive integer constant with a
series of add, subtract, and shift-left instructions.
Assumes two machine "registers". Instructions are
formed on a temporary stack, then output. A stack
element's magnitude is the shift amount, the sign
indicates subsequent add (plus) or subtract (minus). */

long mult; /* 32-bit signed constant multiplier */
int flag, cnt, stkptr, stack[16], last_cnt, last_shift, ts;

int trim_trailing(one_zero) int one_zero;
{
    int c;
    for (c=0; ((mult & 1) == one_zero); c++, mult >>= 1);
    return c;
}

main()
{
    stkptr = 0; /* init. stack pointer */
    printf("\nEnter integer multiplier"); scanf("%d", &mult);
    if (mult > 0)
    {
        last_cnt = 0;
        last_shift = trim_trailing(0); /* cut trailing 0's */
        while (1)
        { /* decompose "mult", build stacked instructions */
            cnt = trim_trailing(1); /* count low-order 1's */
            if (cnt > 1)
            { /* more than 1 bit, use shift-subtract */
                flag = 0;
                if (last_cnt == 1)
                { /* shift k, sub, shift 1, add -- */
                    shift k+1, sub */
                    /* overwrite last entry */
                    stack[stkptr-1] = -(cnt+1);
                }
                else
                    stack[stkptr++] = -cnt;
            }

            /* will need another shift-add */
            else flag = 1;

            /* "mult" fully decomposed, time to output */
            if (mult == 0) break;

            /* count low-order zeros */
            last_cnt = trim_trailing(0) + flag;
            stack[stkptr++] = last_cnt; /* shift-add */
        }
    }

    /* now output code from stack */

    print("\nRw = R1"); /* load working register */
    while (stkptr > 0)
    {
        ts = stack[--stkptr]; /* get top stack element */
        if (ts < 0) printf("\nRw <<= %d\nRw -= R1", -ts);
        else
            printf("\nRw <<= %d\nRw += R1", ts);
    }

    if (last_shift != 0) printf("\nRw <<= %d", last_shift);
    else
        printf("\nRw = 0"); /* special case for mult = 0 */
}
```

Code Example 1: The star-chain algorithm in C

THE DOCTOR MAKES HOUSECALLS!



Don't wait to hear the diagnosis from friends and co-workers . . . get it straight from the Doctor in your own home. Subscribe to **Dr. Dobb's Journal** and enjoy the convenience of having your personal copy delivered to your home or office each month.

And you'll save over \$5 off the cover price!

Every issue of **Dr. Dobb's Journal** will bring you indispensable programming tools like algorithms, coding tips, discussions of fundamental design issues, and actual program listings. You'll find regular coverage of:

- Popular languages such as C, Assembly, Forth, Pascal, Ada, Modula-2, BASIC, FORTRAN, and Cobal.
- 68000 and 80x86 architectures
- MS-DOS, and Unix operating systems
- Usable techniques and practical applications of AI and object-oriented programming research.
- New product reviews, and lively discussion of professional issues in software design.
- Compilers, cross assemblers and much more!

Dr. Dobb's Journal of Software Tools . . . the magazine that has lived up to its reputation as the foremost source of technical tools since 1976. One year (12 information-packed issues) is just **\$29.97** - to subscribe simply mail in the attached card. But do it today . . . you won't want to miss *any* of the exciting issues we have planned!

**Dr. Dobb's Journal of
Software Tools**
FOR THE PROFESSIONAL PROGRAMMER

Dr. Dobb's Journal of Software Tools . . . the Rx for programmers

SUBSCRIBE AND SAVE

Subscribe to **Dr. Dobb's Journal**
and save over \$5—a 15% savings
off the cover price!

—Please charge my: — Visa — MC — American Express
 — Payment enclosed — Bill me later
Card # _____ Exp. date _____
Signature _____
Name _____
Address _____
City _____ State _____ Zip _____

ONLY \$29.97

Canada & Mexico add \$10 for surface mail. All other countries add \$27 for airmail. All foreign subscriptions must be pre-paid in U.S. dollars drawn on a U.S. bank. Please allow 6–8 weeks for delivery of first issue.
A Publication of M & T Publishing, Inc.

3440

SUBSCRIBE AND SAVE

Subscribe to **Dr. Dobb's Journal**
and save over \$5—a 15% savings
off the cover price!

—Please charge my: — Visa — MC — American Express
 — Payment enclosed — Bill me later
Card # _____ Exp. date _____
Signature _____
Name _____
Address _____
City _____ State _____ Zip _____

ONLY \$29.97

Canada & Mexico add \$10 for surface mail. All other countries add \$27 for airmail. All foreign subscriptions must be pre-paid in U.S. dollars drawn on a U.S. bank. Please allow 6–8 weeks for delivery of first issue.
A Publication of M & T Publishing, Inc.

3440

Comments & Suggestions

Dear Reader,

Dr. Dobb's has a long tradition of listening to its readers. We like to hear when something really helps or, for that matter, bothers you. In this hectic world of ours, however, it is often difficult to take the time to write a letter. This card provides you with a quick and easy way to correspond and, if you include your name and address, we may use appropriate comments in The Letters column. Simply fill it out and drop it in the mail.

—Ed.

Which articles or departments did you enjoy the most this month? Why?

Comments or suggestions: _____

Name: _____

Address: _____

344



NO POSTAGE
NECESSARY
IF MAILED
IN THE
UNITED STATES


BUSINESS REPLY MAIL

FIRST CLASS PERMIT NO. 790 REDWOOD CITY, CA

POSTAGE WILL BE PAID BY ADDRESSEE

Dr. Dobb's Journal of
Software Tools
FOR THE PROFESSIONAL PROGRAMMER

P.O. BOX 27809
SAN DIEGO, CA 92128



NO POSTAGE
NECESSARY
IF MAILED
IN THE
UNITED STATES

BUSINESS REPLY MAIL

FIRST CLASS PERMIT NO. 790 REDWOOD CITY, CA

POSTAGE WILL BE PAID BY ADDRESSEE

Dr. Dobb's Journal of
Software Tools
FOR THE PROFESSIONAL PROGRAMMER

P.O. BOX 27809
SAN DIEGO, CA 92128



PLACE
STAMP
HERE

Dr. Dobb's Journal of
Software Tools
FOR THE PROFESSIONAL PROGRAMMER

501 GALVESTON DR.
REDWOOD CITY, CA 94063

*Dr. Dobb's Journal
of Software Tools . . .
the R_x for programmers*

INTEGER MULTIPLICATIONS

(continued from page 35)

Steps 2 through 5 can be combined by incrementing the shift count in step 2 and omitting steps 4 and 5, giving the following sequence for $R1 * 119$:

$R1 * 119$:

```
1  Rw = R1
2  Rw <= 4
3  Rw -= R1
4  Rw <= 3
5  Rw -= R1
```

This sequence (32-bit operands) would require about 46 clocks on a 68000, which is faster than a single 16-bit multiplication. It would require five words of code, as compared to the two or three words required for a subroutine call. It seems clear that star-chain sequences can provide a way to readily optimize multiplication by a constant.

An Actual Implementation

The C program shown in Code Example 1, page 35, implements the star-chain algorithm. It prompts the user for the multiplier (which must be positive) and prints out the star-chain sequence. It would be easy to convert the program to generate code steps for use in an optimizing compiler.

The program works in two steps: the first step builds the sequence on a last-in, first-out stack; the second step outputs the sequence from the stack. Note that, because the multiplier is 32 bits long, the stack need only hold 16 elements; there is no danger of overflow. Each stack element holds a shift-add or shift-subtract. The encoding uses the sign of the stack element to indicate shift-add (plus) or shift-subtract (minus). The magnitude of the stack element is the shift count. The function *trim_trailing* is used to count the number of low-order 0s or 1s in the multiplier. Note that, as written, *mult* must be a global variable because *trim_trailing* operates on it. The variable *flag* is used to signal the shift-subtract optimization.

The program shown works only for positive multipliers, which is always the case in array addressing. To make it handle negative multipliers, simply call it with the absolute value of the multiplier and then output a

"negate" instruction.

The sequences that this program produces are not unique. For example, $R1 * 119$ can be written:

$R1 * 119$:

```
1  Rw = R1
2  Rw <= 3
3  Rw -= R1
4  R1 = Rw
5  Rw <= 4
6  Rw += R1
```

This sequence is derived by factoring $119 = 7 \times 17$. Steps 1 through 3 are a multiplication by 7, and steps 4 through 6 multiply by 17. The alter-

nate sequence here is not shorter or faster than the one generated by the algorithm, but factoring can yield improvements in some cases. (Note that the multiplicand register $R1$ is overwritten in step 4. The star-chain algorithm described in this article does not destroy the multiplicand.) The problem with the factoring approach is that it can take a great deal of time to find the factors (or it may require a large table of factorizations).

DDJ

Vote for your favorite feature/article.
Circle Reader Service No. 3.

Now for
VAX C

The Wrapping is off the Latest Evolution of C DESIGNER C++

Designer C++ is OASYS' full implementation of AT&T's enhancements to the C language

FEATURES:

- ▶ Optional strong type checking
- ▶ Overloading of function names and operators
- ▶ Optional guaranteed initialization of data structures
- ▶ Data abstraction
- ▶ Dynamic typing (virtual functions)
- ▶ Optional user-defined implicit type conversion

- Works with your present C Compiler
- Functions as a Pre-processor Translator — handles regular C code with no changes
- Type-checking and other features are optional — you can turn them off
- Already thousands of users at commercial sites
- Complete documentation: *C++, A User's Guide* by Bjarne Stroustrup of AT&T (Addison-Wesley, 1986)

The only commercially-available C++ customized to operate on PC's, micros, minis, and mainframes with popular C compilers, including:

VAX C
LATTICE
MICROSOFT

GREEN HILLS
WIZARD
WHITESMITH'S

We Specialize in: Cross/Native Compilers: C, Pascal, FORTRAN, Ada, LISP — Assemblers/Linkers — Symbolic Debuggers — Simulators — Interpreters — Profilers — QA Tools — Design Tools — Comm. Tools, — OS Kernels — Editors — VAX & PC Attached Processors and more
We Support: 880xx, 80x86, 320xx, 68xx, 80xx; Clipper, and dozens more

A DIVISION OF XEL **Oasys**

60 Aberdeen Ave., Cambridge, MA 02138 (617) 491-4180

Designer C++ is a joint trademark of XEL, Inc. and Glocksenspiel, Ltd of Dublin, Ada is a trademark of the U.S. Government (AJPO)

Circle no. 254 on reader service card.

WRITE FASTER IN ANY LANGUAGE.

ASM

386, 286, 186,
86, 96, 51

intel

PL/M

386, 286, 186,
86, 96, 51

intel

C

386, 286, 186,
86, 96

intel

Fortran

186, 86

intel

If you develop software for any product based on an Intel microcontroller or microprocessor, including the 80386, the unique debug hooks in the Intel languages will help get the job done faster.

In fact, when used with Intel debuggers and emulators, Intel development languages can provide more debug data than any other high-level language.

Debug hooks let you

symbolically debug in the same high-level language you wrote in without having to deal with machine or hex code. Which means 80.386 reads as 80.386, not 50 62 D0 C5.

Because the location of both code and data are easily specified with our locator, it is easier for you to develop ROM-based firmware.

Since Intel languages

produce identical object code regardless of the host, you can write code at a PC running DOS, a VAX*/VMS terminal, or an Intel Development System.

Pascal
286, 186, 86

intel

**Software
Debuggers**
PMON 386, Pscope 86

intel

Utilities
Relocator, Linker,
Librarian

intel

AEDIT
Programmers'
Editor

intel

Different members of the same design team can therefore choose the most effective combination of languages and systems to get the job done faster.

Intel post-sales support can also help you get the job done faster. We invented the microprocessor. We know microprocessors and languages for Intel architectures better than anyone else.

When you buy an Intel language, you have access to our customer hotline. So if you ever have a question you can talk directly to a trained

applications specialist who understands our products. And can give you the right answers. Faster.

To order today, or get more information—including a free catalog of our development tools—call toll-free 1-800-87-INTEL.

The sooner you call, the faster you'll get the job done.

intel[®]

© 1986 Intel Corporation

*VAX is a registered trademark of Digital Equipment Corporation.

Circle no. 179 on reader service card.

ATTENTION

C-PROGRAMMERS

File System Utility Libraries

All products are written entirely in K&R C. Source code included, No Royalties, Powerful & Portable.

BTree Library

75.00

- High speed random and sequential access.
- Multiple keys per data file with up to 16 million records per file.
- Duplicate keys, variable length data records.

ISAM Driver

40.00

- Greatly speeds application development.
- Combines ease of use of database manager with flexibility of programming language.
- Supports multi key files and dynamic index definition.
- Very easy to use.

Make

59.00

- Patterned after the UNIX utility.
- Works for programs written in every language.
- Full macros, File name expansion and built in rules.

Full Documentation and Example Programs Included.

ALL THREE PRODUCTS FOR — **149.00**

For more information call or write:

1343 Stanbury Drive
Oakville, Ontario, Canada
L6L 2J5
(416) 825-0903

softfocus

Credit cards accepted.

Dealer inquiries invited.

Circle no. 259 on reader service card.

80386

SOFTWARE DEVELOPMENT TOOLS

The Phar Lap 80386 Software Development Series:

386|ASM/LINK by Phar Lap (MS-DOS®) \$495
Full-featured macro assembler and linker. Includes a debugger and 32-bit protected mode runtime environment.

80386 High-C™ by MetaWare (MS-DOS®) \$895

80386 Professional Pascal™ (MS-DOS®) \$895
by MetaWare

UNIX™ and VAX/VMS® cross tools (call)

The wait for professional software development tools for the 80386 is over! Whether you are upgrading an existing IBM PC application to the '386, moving a mainframe application down to a PC, or writing the next PC best-seller, the Phar Lap 80386 Software Development Series is for you. It is an integrated line of products which provides everything you'll need to create and run 80386 protected mode applications under MS-DOS.

(617) 661-1510

Phar Lap Software, Inc. "The 80386 Software Experts"

60 Aberdeen Ave.

Cambridge, MA 02138

Circle no. 343 on reader service card.

COMPRESSING IMAGES

Listing One (Text begins on page 16.)

```

/* Listing one */
/* Subroutines for converting a pixel image
   to a quadtree and output the quadtree as
   locational codes

Written by: Ronald G. White

External routines:
    px2quad - only entry point
*/

#include <stdio.h>

/* Define structure for each node */
typedef struct qnode {
    struct qnode *child[4]; /* pointers to each child */
    struct qnode *next;    /* used during output */
    int color;
    int ntype;              /* see below for types */
    int locode;             /* location code */
} QNODE, *PNODE;

/* Node types: */
#define LEAF 1              /* no children */
#define BLEND 2             /* color of >2 kids */
#define WASH 3              /* color irrelevant */

extern getpix(); /* return pixel color at given posn */
extern putllc(); /* output location code and color */

static int toplevel; /* top level of tree (root node) */

px2quad(size)
int size;
/* entry point for these routines. Control routine to
   create a quadtree from the pixel image and output it
   as locational codes

input:
    size - size of the image rounded up to nearest
           power of two
*/
{
    PNODE crtnode(), proot;

    /* Create the root node */
    proot = crtnode();

    /* Calculate the toplevel number */
    toplevel = 0;
    while (size > 1) {
        toplevel++;
        size >>= 1; /* divide by two */
    }

    /* Build the quad tree */
    proot->locode = 1;
    addnode(proot, toplevel);

    /* Output it as location codes */
    outtree(proot);
}

static PNODE crtnode()
/* create a quadtree node and initialize it

output:
    returns a pointer to the node
*/
{
    int i;
    PNODE newnode;

    /* Get space for it */
    newnode = (PNODE) malloc(sizeof(QNODE));
    if (newnode == NULL) {
        /* Something went wrong */
        fprintf(stderr,
            "crtnode: malloc failure; unable to continue\n");
        exit(1);
    }

```



```

}

/* Initialize it */
for (i = 0; i < 4; i++) {
    newnode->child[i] = NULL;
}
newnode->color = 0;
newnode->ntype = LEAF;
return(newnode);
}

static addnode(pnode, level)
int level;
PNODE pnode;
/* add a new node to the quad tree
If the node is not at the bottom level, four child
nodes are created and added below the current node.
Otherwise the node color is set to that of the
corresponding pixel.

input:
    pnode    - pointer to the current node
    level    - level number of the current node
*/
{
    int i;
    int newlevel;
    PNODE crtnode(), newchild;

    /* if this node is not at the bottom level,
    * add four children below this node
    */
    if (level > 0) {
        newlevel = level - 1;
        for (i = 0; i < 4; i++) {
            newchild = crtnode();
            pnode->child[i] = newchild;
            newchild->locode = (pnode->locode << 2) + i;
            addnode(newchild, newlevel);
        }

        /* Remove any unnecessary children */
        condense(pnode);

        /* bottom level; get actual pixel color */
    } else {
        pnode->color = getcolor(pnode->locode);
    }
}

static condense(pnode)
PNODE pnode;
/* examine children of the current node and
remove any that are unnecessary

input:
    pnode - pointer to current node
*/
{
    int colcnt[4];
    int colors[4];
    int i, j;
    int maxclr = 0;
    int nkids;
    int childclr;
    PNODE pchild;

    /* Initialization */
    for (i = 0; i < 4; i++) {
        colcnt[i] = 0;
    }

    /* Determine colors of children */
    for (i = 0; i < 4; i++) {
        pchild = pnode->child[i];
        if (pchild->ntype == WASH) {
            /* this child has no color */
            continue;
        }

        childclr = pchild->color;
    }
}

```

(continued on next page)

99⁴⁴/₁₀₀% UNIX EQUIVALENT Power Tools

- TOOL BOX 1 \$25
cat cp expand fold more mv newer
page rm unexpand
- TOOL BOX 2 \$30
diff fgrep head od see tail tee uniq
wc xcp
- SYSSAKE \$25
with advanced features from the
new UNIX Version 8

For MSDOS and CP/M

I/O redirection • wildcard expansion
exclusions • full documentation

NIRVONICS inc

P.O. Box 5062

Plainfield, NJ 07061

(201) 561-2155

Trademarks — UNIX: Bell Labs, MSDOS: Microsoft, CP/M: Digital Research

Circle no. 331 on reader service card.


SCIENTIFIC/ENGINEERING GRAPHICS TOOLS for the IBM PC

FORTRAN/Pascal tools: **GRAFMATIC** (screen graphics)
and **PLOTMATIC** (pen plotter driver)

These packages provide 2D and 3D plotting capabilities
for programmers writing in a variety of FORTRAN/Pascal
environments. We support MS, R-M and IBM FORTRAN
and more. PLOTMATIC supports HP or Houston Instru-
ment plotters.

Don't want to program? Just ask for **OMNILOT!** Menu-
driven, fully documented integrated scientific graphics.
Write or call for complete information and ordering in-
structions.

GRAFMATIC – PLOTMATIC – OMNILOT [S] & [P]



Microcompatibles, 301 Prelude Drive, Silver Spring, MD 20901
(301) 593-0683

Circle no. 286 on reader service card.

Listing One (Listing continued, text begins on page 16.)

```

/* loop through colors found so far:
do we have a match?
note: we'll always "break" out of
this loop because there can be at
most four different colors.
*/

for (j = 0; j < 4; j++) {
    if (colcnt[j] == 0) {
        /* new color */
        colors[j] = childclr;
        colcnt[j] = 1;
        break;
    } else if (childclr == colors[j]) {
        /* existing color */
        colcnt[j]++;
        if (colcnt[j] > colcnt[maxclr]) {
            maxclr = j;
        }
        break;
    }
}

/* Set node color */
pnode->color = colors[maxclr];

/* Remove redundant children -- if more than
one child node has the same color as the
current node, then it contains redundant
information. If the redundant node is a
leaf node, it can just be removed. If it
is not a leaf node, mark it as a WASH type
and ignore it during output.
*/

nkids = 4;
if (colcnt[maxclr] > 1) {
    /* Loop through the four children */
    for (i = 0; i < 4; i++) {
        pchild = pnode->child[i];

        /* If child node is already a WASH,
nothing else can be done to it
*/
        if (pchild->ntype == WASH) {
            continue;
        }

        childclr = pchild->color;

        /* Check for color match */
        if (childclr == pnode->color) {

            /* If child is leaf, release */
            if (pchild->ntype == LEAF) {
                relnode(pchild);
                pnode->child[i] = NULL;
                nkids--;
            }

            /* otherwise, mark it as a WASH */
            } else {
                pchild->ntype = WASH;
            }
        }
    }

    /* Reset node type -- a LEAF node has no children */
    if (nkids == 0) {
        pnode->ntype = LEAF;
    }

    /* A BLEND node has a color that represents some
missing children, but still has some other
children that are a different color.
*/
    } else if (colcnt[maxclr] > 1) {
        pnode->ntype = BLEND;
    }

    /* A WASH node is necessary in the quadtree because
it points to existent children nodes, but will not
be output because its information (i.e. color) is
available either in child nodes or parent nodes.
*/
    } else {
        pnode->ntype = WASH;
    }
}

relnode(pnode);
PNODE pnode;
/* release a node

input:
    pnode - pointer to node to release
*/
{
    free((char *) pnode);
}

static getcolor(lcode)
int lcode;
/* get the color of the pixel corresponding to a
bottom level node whose position is given by a
locational code

input:
    lcode - locational code of bottom level node

output:
    returns pixel color
*/
{
    int dir;
    int col = 0;
    int level;
    int row = 0;
    int shift;

    /* Convert node locational code to pixel row & column
by looping through direction codes in locational
code for each level from top to bottom
*/
    for (level = toplevel; level > 0; level--) {

        /* shift last row & col values left one bit */
        col <<= 1;
        row <<= 1;

        /* calculate the position of the direction
code for this level and extract it
*/
        shift = (level - 1) * 2;
        dir = (lcode >> shift) & 0x3;

        /* increment the col value if quadrant is in
left half, i.e. NE or SE child
*/
        if (dir == 1 || dir == 3) {
            col++;
        }

        /* increment the row value if quadrant is in
bottom half, i.e. SW or SE child
*/
        if (dir == 2 || dir == 3) {
            row++;
        }
    }

    /* return pixel color */
    return(getpix(col, row));
}

static outtree(proot)
PNODE proot;
/* output the relevant nodes in the quad tree
*/
{
    /* proot - pointer to the root node
*/
    {
        (continued on page 44)
    }
}

```

(continued on page 44)

Clarify your source code

C, BASIC, Pascal, dBASE, Modula-2 programmers: be more productive with two new utilities from Aldebaran Laboratories

"Occasionally, a utility comes along that makes a programmer's life much easier. SOURCE PRINT is such a program. It contributes to the programmer's job by organizing code into a legible format and by helping to organize the documentation and debugging process."

— PC Magazine
Sept. 16, 1986

Source Print and Tree Diagrammer both have easy-to-use menus with point-and-shoot file selection, and let you search for files containing a given string. For IBM PC and compatibles with 256K.

Join thousands of programmers who are working more efficiently using Source Print and Tree Diagrammer. Order these indispensable tools today. We ship immediately, and there's no risk with our 60-day money-back guarantee. **Order both and save. Only \$115.00.**

800-257-5773 Dept. 53
In California:

800-257-5774 Dept. 53

MasterCard, VISA, American Express, COD. Add \$5 for shipping.

Source Print and Tree Diagrammer are trademarks of Aldebaran Labs. dBASE is a trademark of Ashton Tate.

Source Print™

organizes your source code, simplifies debugging, and makes documentation a snap! It lists one or more source files with informative page headings and optional line numbers, while offering invaluable features:

The Index (Cross-Reference list) saves you time by showing exactly where variables are used and where functions, procedures, and routines are called.

\$75⁰⁰

Locations where new values may be assigned to variables are shown, making it easy to track down that mysterious value change.

Structure Outlining solves the problem of hard-to-see nested control structures by automatically drawing lines around them.

Automatic Indentation of source code and listings reduces your editing time and ensures indentation accuracy.

Plus . . . Source Print generates a table of contents listing functions and procedures. Keywords can be printed in boldface on most printers. Multi-statement BASIC lines can be split for readability. Functions and procedures can be drawn by name from one or more source files to form a new file.

```
04-08-86 13:45:44 dem1.pro
Sun 04-08-86 13:45:57

PUBLIC value, val1, val2, val3
USE value[1] INDEX data
DATE/TIME= "12/10/85"
DO WHILE date1 <= date2 "01/01/86"
  date1 = date1 + 1
  $$$$ NEW ENTER date1: " get da
5
6
7
8
9
10
11
12
13
14
15
16
17
18
19
20
21
22
23
24
25
26
27
28
29
30
31
32
33
34
35
36
37
38
39
40
41
42
43
44
45
46
47
48
49
50
51
52
53
54
55
56
57
58
59
60
61
62
63
64
65
66
67
68
69
70
71
72
73
74
75
76
77
78
79
80
81
82
83
84
85
86
87
88
89
90
91
92
93
94
95
96
97
98
99
100
101
102
103
104
105
106
107
108
109
110
111
112
113
114
115
116
117
118
119
120
121
122
123
124
125
126
127
128
129
130
131
132
133
134
135
136
137
138
139
140
141
142
143
144
145
146
147
148
149
150
151
152
153
154
155
156
157
158
159
160
161
162
163
164
165
166
167
168
169
170
171
172
173
174
175
176
177
178
179
180
181
182
183
184
185
186
187
188
189
190
191
192
193
194
195
196
197
198
199
200
201
202
203
204
205
206
207
208
209
210
211
212
213
214
215
216
217
218
219
220
221
222
223
224
225
226
227
228
229
230
231
232
233
234
235
236
237
238
239
240
241
242
243
244
245
246
247
248
249
250
251
252
253
254
255
256
257
258
259
260
261
262
263
264
265
266
267
268
269
270
271
272
273
274
275
276
277
278
279
280
281
282
283
284
285
286
287
288
289
290
291
292
293
294
295
296
297
298
299
300
301
302
303
304
305
306
307
308
309
310
311
312
313
314
315
316
317
318
319
320
321
322
323
324
325
326
327
328
329
330
331
332
333
334
335
336
337
338
339
340
341
342
343
344
345
346
347
348
349
350
351
352
353
354
355
356
357
358
359
360
361
362
363
364
365
366
367
368
369
370
371
372
373
374
375
376
377
378
379
380
381
382
383
384
385
386
387
388
389
390
391
392
393
394
395
396
397
398
399
400
401
402
403
404
405
406
407
408
409
410
411
412
413
414
415
416
417
418
419
420
421
422
423
424
425
426
427
428
429
430
431
432
433
434
435
436
437
438
439
440
441
442
443
444
445
446
447
448
449
450
451
452
453
454
455
456
457
458
459
460
461
462
463
464
465
466
467
468
469
470
471
472
473
474
475
476
477
478
479
480
481
482
483
484
485
486
487
488
489
490
491
492
493
494
495
496
497
498
499
500
501
502
503
504
505
506
507
508
509
510
511
512
513
514
515
516
517
518
519
520
521
522
523
524
525
526
527
528
529
530
531
532
533
534
535
536
537
538
539
540
541
542
543
544
545
546
547
548
549
550
551
552
553
554
555
556
557
558
559
560
561
562
563
564
565
566
567
568
569
570
571
572
573
574
575
576
577
578
579
580
581
582
583
584
585
586
587
588
589
590
591
592
593
594
595
596
597
598
599
600
601
602
603
604
605
606
607
608
609
610
611
612
613
614
615
616
617
618
619
620
621
622
623
624
625
626
627
628
629
630
631
632
633
634
635
636
637
638
639
640
641
642
643
644
645
646
647
648
649
650
651
652
653
654
655
656
657
658
659
660
661
662
663
664
665
666
667
668
669
670
671
672
673
674
675
676
677
678
679
680
681
682
683
684
685
686
687
688
689
690
691
692
693
694
695
696
697
698
699
700
701
702
703
704
705
706
707
708
709
710
711
712
713
714
715
716
717
718
719
720
721
722
723
724
725
726
727
728
729
730
731
732
733
734
735
736
737
738
739
740
741
742
743
744
745
746
747
748
749
750
751
752
753
754
755
756
757
758
759
760
761
762
763
764
765
766
767
768
769
770
771
772
773
774
775
776
777
778
779
780
781
782
783
784
785
786
787
788
789
790
791
792
793
794
795
796
797
798
799
800
801
802
803
804
805
806
807
808
809
810
811
812
813
814
815
816
817
818
819
820
821
822
823
824
825
826
827
828
829
830
831
832
833
834
835
836
837
838
839
840
841
842
843
844
845
846
847
848
849
850
851
852
853
854
855
856
857
858
859
860
861
862
863
864
865
866
867
868
869
870
871
872
873
874
875
876
877
878
879
880
881
882
883
884
885
886
887
888
889
890
891
892
893
894
895
896
897
898
899
900
901
902
903
904
905
906
907
908
909
910
911
912
913
914
915
916
917
918
919
920
921
922
923
924
925
926
927
928
929
930
931
932
933
934
935
936
937
938
939
940
941
942
943
944
945
946
947
948
949
950
951
952
953
954
955
956
957
958
959
960
961
962
963
964
965
966
967
968
969
970
971
972
973
974
975
976
977
978
979
980
981
982
983
984
985
986
987
988
989
990
991
992
993
994
995
996
997
998
999
1000
1001
1002
1003
1004
1005
1006
1007
1008
1009
1010
1011
1012
1013
1014
1015
1016
1017
1018
1019
1020
1021
1022
1023
1024
1025
1026
1027
1028
1029
1030
1031
1032
1033
1034
1035
1036
1037
1038
1039
1040
1041
1042
1043
1044
1045
1046
1047
1048
1049
1050
1051
1052
1053
1054
1055
1056
1057
1058
1059
1060
1061
1062
1063
1064
1065
1066
1067
1068
1069
1070
1071
1072
1073
1074
1075
1076
1077
1078
1079
1080
1081
1082
1083
1084
1085
1086
1087
1088
1089
1090
1091
1092
1093
1094
1095
1096
1097
1098
1099
1100
1101
1102
1103
1104
1105
1106
1107
1108
1109
1110
1111
1112
1113
1114
1115
1116
1117
1118
1119
1120
1121
1122
1123
1124
1125
1126
1127
1128
1129
1130
1131
1132
1133
1134
1135
1136
1137
1138
1139
1140
1141
1142
1143
1144
1145
1146
1147
1148
1149
1150
1151
1152
1153
1154
1155
1156
1157
1158
1159
1160
1161
1162
1163
1164
1165
1166
1167
1168
1169
1170
1171
1172
1173
1174
1175
1176
1177
1178
1179
1180
1181
1182
1183
1184
1185
1186
1187
1188
1189
1190
1191
1192
1193
1194
1195
1196
1197
1198
1199
1200
1201
1202
1203
1204
1205
1206
1207
1208
1209
1210
1211
1212
1213
1214
1215
1216
1217
1218
1219
1220
1221
1222
1223
1224
1225
1226
1227
1228
1229
1230
1231
1232
1233
1234
1235
1236
1237
1238
1239
1240
1241
1242
1243
1244
1245
1246
1247
1248
1249
1250
1251
1252
1253
1254
1255
1256
1257
1258
1259
1260
1261
1262
1263
1264
1265
1266
1267
1268
1269
1270
1271
1272
1273
1274
1275
1276
1277
1278
1279
1280
1281
1282
1283
1284
1285
1286
1287
1288
1289
1290
1291
1292
1293
1294
1295
1296
1297
1298
1299
1300
1301
1302
1303
1304
1305
1306
1307
1308
1309
1310
1311
1312
1313
1314
1315
1316
1317
1318
1319
1320
1321
1322
1323
1324
1325
1326
1327
1328
1329
1330
1331
1332
1333
1334
1335
1336
1337
1338
1339
1340
1341
1342
1343
1344
1345
1346
1347
1348
1349
1350
1351
1352
1353
1354
1355
1356
1357
1358
1359
1360
1361
1362
1363
1364
1365
1366
1367
1368
1369
1370
1371
1372
1373
1374
1375
1376
1377
1378
1379
1380
1381
1382
1383
1384
1385
1386
1387
1388
1389
1390
1391
1392
1393
1394
1395
1396
1397
1398
1399
1400
1401
1402
1403
1404
1405
1406
1407
1408
1409
1410
1411
1412
1413
1414
1415
1416
1417
1418
1419
1420
1421
1422
1423
1424
1425
1426
1427
1428
1429
1430
1431
1432
1433
1434
1435
1436
1437
1438
1439
1440
1441
1442
1443
1444
1445
1446
1447
1448
1449
1450
1451
1452
1453
1454
1455
1456
1457
1458
1459
1460
1461
1462
1463
1464
1465
1466
1467
1468
1469
1470
1471
1472
1473
1474
1475
1476
1477
1478
1479
1480
1481
1482
1483
1484
1485
1486
1487
1488
1489
1490
1491
1492
1493
1494
1495
1496
1497
1498
1499
1500
1501
1502
1503
1504
1505
1506
1507
1508
1509
1510
1511
1512
1513
1514
1515
1516
1517
1518
1519
1520
1521
1522
1523
1524
1525
1526
1527
1528
1529
1530
1531
1532
1533
1534
1535
1536
1537
1538
1539
1540
1541
1542
1543
1544
1545
1546
1547
1548
1549
1550
1551
1552
1553
1554
1555
1556
1557
1558
1559
1560
1561
1562
1563
1564
1565
1566
1567
1568
1569
1570
1571
1572
1573
1574
1575
1576
1577
1578
1579
1580
1581
1582
1583
1584
1585
1586
1587
1588
1589
1590
1591
1592
1593
1594
1595
1596
1597
1598
1599
1600
1601
1602
1603
1604
1605
1606
1607
1608
1609
1610
1611
1612
1613
1614
1615
1616
1617
1618
1619
1620
1621
1622
1623
1624
1625
1626
1627
1628
1629
1630
1631
1632
1633
1634
1635
1636
1637
1638
1639
1640
1641
1642
1643
1644
1645
1646
1647
1648
1649
1650
1651
1652
1653
1654
1655
1656
1657
1658
1659
1660
1661
1662
1663
1664
1665
1666
1667
1668
1669
1670
1671
1672
1673
1674
1675
1676
1677
1678
1679
1680
1681
1682
1683
1684
1685
1686
1687
1688
1689
1690
1691
1692
1693
1694
1695
1696
1697
1698
1699
1700
1701
1702
1703
1704
1705
1706
1707
1708
1709
1710
1711
1712
1713
1714
1715
1716
1717
1718
1719
1720
1721
1722
1723
1724
1725
1726
1727
1728
1729
1730
1731
1732
1733
1734
1735
1736
1737
1738
1739
1740
1741
1742
1743
1744
1745
1746
1747
1748
1749
1750
1751
1752
1753
1754
1755
1756
1757
1758
1759
1760
1761
1762
1763
1764
1765
1766
1767
1768
1769
1770
1771
1772
1773
1774
1775
1776
1777
1778
1779
1780
1781
1782
1783
1784
1785
1786
1787
1788
1789
1790
1791
1792
1793
1794
1795
1796
1797
1798
1799
1800
1801
1802
1803
1804
1805
1806
1807
1808
1809
1810
1811
1812
1813
1814
1815
1816
1817
1818
1819
1820
1821
1822
1823
1824
1825
1826
1827
1828
1829
1830
1831
1832
1833
1834
1835
1836
1837
1838
1839
1840
1841
1842
1843
1844
1845
1846
1847
1848
1849
1850
1851
1852
1853
1854
1855
1856
1857
1858
1859
1860
1861
1862
1863
1864
1865
1866
1867
1868
1869
1870
1871
1872
1873
1874
1875
1876
1877
1878
1879
1880
1881
1882
1883
1884
1885
1886
1887
1888
1889
1890
1891
1892
1893
1894
1895
1896
1897
1898
1899
1900
1901
1902
1903
1904
1905
1906
1907
1908
1909
1910
1911
1912
1913
1914
1915
1916
1917
1918
1919
1920
1921
1922
1923
1924
1925
1926
1927
1928
1929
1930
1931
1932
1933
1934
1935
1936
1937
1938
1939
1940
1941
1942
1943
1944
1945
1946
1947
1948
1949
1950
1951
1952
1953
1954
1955
1956
1957
1958
1959
1960
1961
1962
1963
1964
1965
1966
1967
1968
1969
1970
1971
1972
1973
1974
1975
1976
1977
1978
1979
1980
1981
1982
1983
1984
1985
1986
1987
1988
1989
1990
1991
1992
1993
1994
1995
1996
1997
1998
1999
2000
2001
2002
2003
2004
2005
2006
2007
2008
2009
2010
2011
2012
2013
2014
2015
2016
2017
2018
2019
2020
2021
2022
2023
2024
2025
2026
2027
2028
2029
2030
2031
2032
2033
2034
2035
2036
2037
2038
2039
2040
2041
2042
2043
2044
2045
2046
2047
2048
2049
2050
2051
2052
2053
2054
2055
2056
2057
2058
2059
2060
2061
2062
2063
2064
2065
2066
2067
2068
2069
2070
2071
2072
2073
2074
2075
2076
2077
2078
2079
2080
2081
2082
2083
2084
2085
2086
2087
2088
2089
2090
2091
2092
2093
2094
2095
2096
2097
2098
2099
2100
2101
2102
2103
2104
2105
2106
2107
2108
2109
2110
2111
2112
2113
2114
2115
2116
2117
2118
2119
2120
2121
2122
2123
2124
2125
2126
2127
2128
2129
2130
2131
2132
2133
2134
2135
2136
2137
2138
2139
2140
2141
2142
2143
2144
2145
2146
2147
2148
2149
2150
2151
2152
2153
2154
2155
2156
2157
2158
2159
2160
2161
2162
2163
2164
2165
2166
2167
2168
2169
2170
2171
2172
2173
2174
2175
2176
2177
2178
2179
2180
2181
2182
2183
2184
2185
2186
2187
2188
2189
2190
2191
2192
2193
2194
2195
2196
2197
2198
2199
2200
2201
2202
2203
2204
2205
2206
2207
2208
2209
2210
2211
2212
2213
2214
2215
2216
2217
2218
2219
2220
2221
2222
2223
2224
2225
2226
2227
2228
2229
2230
2231
2232
2233
2234
2235
2236
2237
2238
2239
2240
2241
2242
2243
2244
2245
2246
2247
2248
2249
2250
2251
2252
2253
2254
2255
2256
2257
2258
2259
2260
2261
2262
2263
2264
2265
2266
2267
2268
2269
2270
2271
2272
2273
2274
2275
2276
2277
2278
2279
2280
2281
2282
2283
2284
2285
2286
2287
2288
2289
2290
2291
2292
2293
2294
2295
2296
2297
2298
2299
2300
2301
2302
2303
2304
2305
2306
2307
2308
2309
2310
2311
2312
2313
2314
2315
2316
2317
2318
2319
2320
2321
2322
2323
2324
2325
2326
2327
2328
2329
2330
2331
2332
2333
2334
2335
2336
2337
2338
2339
2340
2341
2342
2343
2344
2345
2346
2347
2348
2349
2350
2351
2352
2353
2354
2355
2356
2357
2358
2359
2360
2361
2362
2363
2364
2365
2366
2367
2368
2369
2370
2371
2372
2373
2374
2375
2376
2377
2378
2379
2380
2381
2382
2383
2384
2385
2386
2387
2388
2389
2390
2391
2392
2393
2394
2395
2396
2397
2398
2399
2400
2401
2402
2403
2404
2405
2406
2407
2408
2409
2410
2411
2412
2413
2414
2415
2416
2417
2418
2419
2420
2421
2422
2423
2424
2425
2426
2427
2428
2429
2430
2431
2432
2433
2434
2435
2436
2437
2438
2439
2440

```



```

* input:
*   size - size of the original image
*/
{
    int lcode, color;
    int corner[2];
    int side;

    /* Make the image size global */
    orgsize = size;

    /* Read and display each node */
    while (getnrxn(&lcode, &color) != EOF) {

        /* Convert loc code to corners, side of square */
        square(lcode, corner, &side);

        /* Fill in the square */
        fillrec(corner[0], corner[1], side, side, color);
    }

square(lcode, corner, pside)
int lcode;
int corner[2];
int *pside;
/* convert quadtree locational code to corner and side
of the square represented by the corresponding node.

input:
    lcode - locational code for this node

output:
    corner - upper left corner of quadrant
    pside - the size of the quadrant in pixels
*/
{
    int dir;
    int shift;

    corner[0] = corner[1] = 0;
    *pside = orgsize;

    /* Find the beginning of the code */
    for (shift = 30;
        ((lcode >> shift) & 0xff) == 0; shift -= 2);

    /* Convert node locational code to corner row &
    column by looping through direction codes in
    locational code for each level from top down.
    */
    for (shift -= 2; shift >= 0; shift -= 2) {

        /* The side of the square is reduced by a
        factor of two each level down.
        */
        *pside >>= 1;

        /* extract the direction code */
        dir = (lcode >> shift) & 0x3;

        /* increment the col value if quadrant is
        in left half, i.e. NE or SE child
        */
        if (dir == 1 || dir == 3) {
            corner[0] += *pside;
        }

        /* increment the row value if quadrant is
        in bottom half, i.e. SW or SE child
        */
        if (dir == 2 || dir == 3) {
            corner[1] += *pside;
        }
    }
}

```

End Listings

Does this look familiar?
What if each change
you made to your
program was ready to
test in seconds instead
of minutes?



"The SLR tools will change the way you write code. I don't use anything else.", Joe Wright

RELOCATING MACRO ASSEMBLERS • Z80 • 8085 • HD64180

- Generates COM, Intel HEX, Microsoft REL, or SLR REL
- Intel macro facility
- All M80 pseudo ops
- Multiple assemblies via command line or indirect command file
- Alternate user number search
- ZCPR3 and CP/M Plus error flag support, CP/M 2.2 submit abort
- Over 30 user configurable options
- Descriptive error messages
- XREF and Symbol tables
- 16 significant characters on labels (even externals)
- Time and Date in listing
- Nested conditionals and INCLUDE files
- Supports math on externals

\$49.95

requires Z80 CP/M compatible systems with at least 32K TPA

SLR Systems

1622 N. Main St., Butler, PA 16001

(412) 282-0864 (800) 833-3061

Circle no. 78 on reader service card.

Publication Quality Scientific Graphics

Over 100 C routines make
scientific plotting easy


Graphic 3.0

- linear, log, & polar plots
- bar charts & Smith charts
- contour plots with labels
- 3-D curves, 3-D surfaces
- 4 curve types, 8 markers, errorbars
- 14 fonts, font editor
- unlimited levels of superscripts
- 4096 x 3120 resolution in 16 colors on EGA, Tecmar, Sigma boards
- zoom, pan, window and merge plots
- high resolution printer dumps

SOURCE INCLUDED for *personal* use only

\$350. Demo \$8

256k, IBM, AT&T, Corona PCs, DOS 2.xx, 3.xx
Most boards, printers, and plotters supported
Microsoft, Lattice, DeSmet, Aztec, C86 compilers



Scientific Endeavors Corporation

Route 4, Box 79 Kingston, TN 37763 (615) 376-4146

Circle no. 210 on reader service card.

THE PROGRAMMER'S SHOP

helps save time, money and cut frustrations. Compare, evaluate, and find products.

RECENT DISCOVERY

Sapiens V8 - virtual memory management for C programmers on PCs provides 8M workspace, 64-bit emulation, virtual stack library and heap. Link to MS, Lattice, Aztec. PC \$ 300

AI-Expert System Dev 1

Arity System-incorporate with C programs, rule & inheritance MS \$ 259
Auto-Intelligence - by IntelligenceWare PC \$ 749
Expteach - Powerful, no limit on memory size. Samples PC \$ 349
Intelligence/Compiler - rules, frames PC \$ 749

AI-Lisp

Microsoft MuLisp 85 MS \$ 179
PC Scheme LISP - by TI PC \$ 85
TLC LISP - classes, compiler. MS \$ 225
TransLISP - learn fast MS Call
TransLISP PLUS
Optional Unlimited Runtime \$ 150
PLUS for MSDOS \$ 179
Others: IQ LISP (\$155), UNX LISP (\$59), IQC LISP (\$269), WALTZLISP (\$139)

AI-Prolog

APT - Active Prolog Tutor - build applications interactively PC \$ 65
ARITY Standard - full, 4 Meg
Interpreter - debug, C, ASM PC \$ 319
COMPILER/Interpreter-EXE PC \$ 699
With Exp Sys, Screen - KIT PC \$1129
LPA MacProlog Complete - incremental compiler and an interpreter MAC \$ 295
LPA MicroProlog - intro MS \$ 85
Prolog-86 - Learn Fast, Standard, tutorials, samples MS \$ 89
Prolog-86 Plus - Develop MS \$ 229
TURBO PROLOG by Borland PC \$ 69

AI-Other

METHODS - SMALLTALK has objects, windows, PC \$ 69
Q'NIAL - Combines APL with LISP. PC \$ 349
Source or binary. PC \$ 995
Smalltalk-80 - Xerox improved PC \$ 89
Smalltalk/V-graphics PC \$ 89

Atari ST & Amiga

We carry full lines of Manx, Lattice, & Metacomco.
Amiga - LINT by Gimpel Amiga \$ 79
Cambridge LISP Amiga \$ 200
Lattice C ST, Amiga \$ 139
Lattice Text Utilities Amiga \$ 75
Megamax - tight, full ST \$ 200

FEATURES

C Scape - capture Dan Bricklin's, 1-2-3, Turbo screens & more, convert to C. Plus full screen generation package - tiled, pop-up windows with scrolling, validation. Source PC \$ 179

PolyBoost - Run 2 to 10 times faster with software accelerator. Speeds disk access, screen display, keyboard input. PC \$ 69

National Accounts

MIS, Engineering, and Research departments get special FREE consulting, product comparisons, reports, newsletters. Compare approaches to COBOL, C, AI. PURCHASING AGENTS - get help and special service finding products, negotiating license agreements, with billing and more. Call 800-446-1185.

Our Services:

- Programmer's Referral List
- Compare Products
- Help find a Publisher
- Evaluation Literature FREE
- BBS-7PM to 7AM 617-826-4086
- Dealers Inquire
- Newsletter
- Rush Order
- Over 700 products
- National Accounts Center

Basic

Basic Development System - for BASICA; Adds Renum, more. PC \$ 105
Basic Development Tools by Sterling Castle PC \$ 89
Basic Windows by Syscom PC \$ 95
BetterBASIC - all RAM, modules
Structure. Full BASICA PC \$ 129
8087 Math Support PC \$ 75
Run-time Module PC \$ 169
Better Tools - for Better Basic PC \$ 95
CADSAM FILE SYSTEM-full MS \$ 69
GoodBas - maintain code PC \$ 95
LPI Basic - MS compatible UNIX \$1100
Prof. Basic - Interactive, debug PC \$ 75
8087 Math Support PC \$ 45
QuickBASIC V2.0-New interface PC \$ 69
TRUE Basic - ANSI PC \$ 119
Run-time Module PC \$ 129

Cobol

Macintosh COBOL - full MAC \$ 459
MBP - Lev. II, native MS \$ 819
Microfocus Professional Cobol PC \$2295
VS Workbench PC \$3379
Microsoft COBOL MS \$ 439
Microsoft Cobol Tools - xref, debugger w/source support. PC \$ 209
Realia - very fast MS \$ 819
Ryan McFarland COBOL MS \$ 649
COBOL-8X MS \$ 895
Screenplay - by Flexus.
Interactive screen mgmt. PC \$ 175

Editors for Programming

BRIEF Programmer's Editor PC Call
EMACS by UniPress - powerful, multifile, windows Source:\$929 \$ 299
Epsilon - like EMACS, full C-like language for macros. PC \$ 155
KEDIT - like XEDIT PC \$ 105
Lattice Screen Editor - multiwindow, multitasking Amiga \$ 89 MS \$ 109
PC/EDT - macros PC \$ 250
PC/VI - by Custom Software MS \$ 109
Personal REXX PC \$ 109
PMATE - power, multitask PC \$ 119
SPF/PC - fast, virtual memory PC \$ 139
XTC - multitasking PC \$ 79

C Libraries-Communications

Asynch by Blaise PC \$ 135
Essential Comm Library PC \$ 135
With Debugger PC \$ 199
Greenleaf Comm Lib. PC \$ 139
Multi-Comm - add multitasking, use w/Multi-C PC \$ 149
Software Horizons pack 3 PC \$ 119

RECENT DISCOVERY

r-tree - report generation for ctree. Multiple file handling, fixed or variable length. Many built-in functions like Boolean, computational functions, string, date handling, numeric to string conversion. Layout control. Source in C. PC \$249

C Language-Compilers

AZTEC C86 - Commercial PC \$499
C86 by CI - 8087, reliable MS \$299
Datalight C - fast compile, good code, 4 models, Lattice compatible, Lib source. Dev's Kit PC \$ 77
HOT C - new, intriguing PC \$ 85
Lattice C - from Lattice MS \$289
Mark Williams - w/debugger MS \$369
Microsoft C 4.0- Codeview MS \$279
Wizard C MS \$359

C Language-Interpreters

C-terp by Gimpel - full K & R MS \$229
C Trainer - by Catalytix PC \$ 89
INSTANT C - Source debug, Edit to Run-3 seconds, .OBJs MS \$379
Interactive C by IMPACC Assoc. PC \$225
Introducing C-self paced tutorial PC \$105
Run/C Professional MS \$179
Run/C Lite MS \$ 97

C Libraries-General

Blackstar C Function Library PC \$ 79
C Essentials - 200 functions PC \$ 83
C Food by Lattice-ask for source MS \$ 99
C Scientific Subroutines - Peerless MS \$135
C Tools Plus (1 & 2) - Blaise PC \$135
C Utilities by Essential - Comprehensive screen graphics, strings, source. PC \$137
C Worthy Library - Complete, machine independent MS \$269
Entelekon C Function Library PC \$119
Entelekon Superfont for C PC \$ 45
Greenleaf Functions-portable, ASM \$139
PforCe by Phoenix - objects PC \$229

C Libraries-Files

FILES: C Index by Trio - full B + Tree, vary length field, multi compiler /File is object only MS \$ 89
/Plus is full source MS \$319
CBTREE - Source, no royalties MS \$ 99
CTree by Faircom - no royalties MS \$319
dbQUERY - ad Loc, SQL - based MS \$159
dbVISTA - full indexing, plus optional record types, pointers, Network. Object only - MS C, LAT, C86 \$155
Source - Single user MS \$425
Source - Multiuser MS \$845
dBASE Tools for C PC \$ 65
dbc Isam by Lattice MS \$179
dBx - translator MS \$319
w/source to library MS \$499

FEATURE

Uniware Cross Development Tools include 68000 C compiler. Development Package with compiler, assembler, link editor, and utilities, 17 cross assemblers for Intel, TI, Motorola, Zilog, etc. - relocatable, macros. MS Call

We support MSDOS (not just compatibles), PC DOS, Xenix-86, CPM-80, Macintosh, Atari ST, and Amiga.

THE PROGRAMMER'S SHOP

provides complete information, advice, guarantees and every product for Microcomputer Programming.

AI TOOLS

Expert System Shells and professional language implementations, smart decision support packages make practical AI power in your applications, planning. Call one of our AI specialists today.

Order before 3/31/87 and mention this ad for these special prices.

| | List | Normal | SPECIAL |
|------------------------------|--------|--------|---------|
| Insight 2 + Expert Shell | \$ 485 | \$ 389 | \$ 309 |
| LPA MicroProlog Professional | \$ 395 | \$ 339 | \$ 289 |
| Arity Compiler with Expert | | | |
| Shell Interpreter | \$ 795 | \$ 699 | \$ 589 |
| Exsys | \$ 395 | \$ 309 | \$ 259 |
| Texas Instruments | | | |
| PC Easy | \$ 495 | \$ 439 | \$ 349 |
| Personal Consultant Plus | \$2950 | \$2599 | \$1899 |

C Support-Systems

| | |
|----------------------------------|----------|
| Basic-C Library by C Source | PC \$139 |
| C Sharp - realtime, tasks. | PC \$600 |
| C ToolSet - DIFF, xref, source | MS \$ 95 |
| The HAMMER by OES Systems | PC \$149 |
| Lattice Text Utilities | MS \$ 89 |
| Multi-C - multitasking | PC \$149 |
| PC LINT-Checker. Amiga \$89 | MS \$107 |
| SECURITY LIB-add encrypt to MSC, | |
| C86 programs. Source \$229 | PC \$115 |
| Quickshell - script compiler | PC \$349 |

C-Screens, Windows, Graphics

| | |
|--------------------------------|----------|
| C Power Windows by Entelekon | PC \$109 |
| dBASE Graphics for C | PC \$ 69 |
| Curses by Lattice | PC \$ 89 |
| ESSENTIAL GRAPHICS - fast | PC \$199 |
| GraphiC - mono version | PC \$217 |
| GraphiC - new color version | PC \$295 |
| Greenleaf Data Window | PC \$189 |
| w/source | PC \$339 |
| Multi-Windows - use w/ Multi-C | PC \$295 |
| Screen Ace Form Master | PC \$195 |
| Vitamin C - screen I/O | PC \$199 |
| Windows for C - fast | PC \$159 |
| Windows for Data - validation | PC \$239 |
| ZView - screen generator | MS \$189 |

Debuggers

| | |
|----------------------------------|----------|
| 386 Debug | PC \$149 |
| Advanced Trace-86 by Morgan | |
| Modify ASM code on fly. | PC \$125 |
| CODESMITH - visual, modify | |
| and rewrite Assembler | PC \$107 |
| C SPRITE - data structures | PC \$129 |
| DSD87 - by Soft Advances | PC \$ 89 |
| Periscope I - own 16K | PC \$239 |
| Periscope II - symbolic, "Reset | |
| Box," 2 Screen | PC \$109 |
| Periscope II-X - software only | PC \$ 85 |
| Pfix-86 Plus Symbolic Debugger | |
| by Phoenix - windows | PC \$229 |
| Showcase by Test Software | PC \$135 |
| Software Source by Atron - | |
| Lattice, MSC, Pascal, Windows | |
| single step, 2 screen, log file. | MS \$115 |
| w/Breakswitch | \$199 |

FEATURE

Multi-Comm - Multitasking/user communications. Use with Cytek's Multi-C; interrupt-driven, ROMable; XMODEM, ASCII or binary transfer. MS \$149

Fortran & Supporting

| | | |
|--------------------------------------|-----|----------|
| 50:More FORTRAN - math, | | PC \$ 99 |
| source | | |
| ACS Time Series | | MS \$419 |
| Forlib+ by Alpha | | MS \$ 59 |
| MACFortran by Microsoft | MAC | \$229 |
| MS Fortran link to C | | MS \$209 |
| No Limit - Fortran Scientific | | PC \$115 |
| RM/Fortran | | MS \$389 |
| Scientific Subroutines - Matrix | | MS \$139 |
| Statistician by Alpha | | MS \$249 |
| Strings and Things - register, shell | PC | \$ 55 |

Multilanguage Support

| | | |
|------------------------------------|----|----------|
| BTRIEVE ISAM | | MS \$199 |
| BTRIEVE/N-multiuser | | MS \$469 |
| CODESIFTER - Profiler. | | MS \$ 99 |
| HALO Graphics - 115 + devices. | | |
| Animation, engineering, business. | | |
| Any MS language, Lattice, C86 | PC | \$209 |
| Informix - by RDS | PC | \$639 |
| Informix 4GL - application builder | PC | \$799 |
| Opt Tech Sort - sort, merge | MS | \$119 |
| PANEL | MS | \$219 |
| PolyLibrarian by Polytron | MS | \$ 79 |
| PVCS Version Control | MS | \$329 |
| QMake by Quilt Co. | MS | \$ 84 |
| Rtrieve - Xtrieve option | MS | \$119 |
| Screen Sculptor - slick, thorough, | | |
| fast, BASIC, PASCAL. | PC | \$ 95 |
| Xtrieve - organize database | MS | \$199 |
| ZAP Communications - VT 100 | PC | \$ 89 |

Pascal and Supporting

| | | |
|------------------------------------|-----|-------|
| ALICE - learn Pascal, Turbo | | |
| compatible, interpreter | PC | \$ 68 |
| Exec - Chain Programs | MS | \$ 79 |
| MetaWINDOW - graphics toolkit | PC | \$115 |
| MetaWINDOWS PLUS - | | |
| enhanced | PC | \$185 |
| Microsoft PASCAL - faster | MS | \$189 |
| MICROTEC PASCAL - 5 memory models, | | |
| "Iterators", 65 bit 8087 strings | MS | \$665 |
| Pascal Extender - access user | | |
| interface, toolbox | MAC | \$ 65 |
| Pascal Pac with Tidy - formatter, | | |
| utilities | PC | \$ 69 |
| Pascal Tools - strings, screen | PC | \$109 |
| Pascal Tools 2 - by Blaise | MS | \$ 85 |
| Pascal 2 - tight, fast | MS | \$329 |
| TurboHALO - 150 routines, IBM | | |
| EGA, Hercules, more | PC | \$ 85 |

RECENT DISCOVERY

The Documentor - for dBASE program flow chart, tree diagrams, .DBF documentation, variable/field concordance, hierarchy charts. Macros, searches, configure options. MS \$ 295

Other Languages

| | | |
|----------------------------------|-----------|--------|
| APL*PLUS/PC | PC | \$ 469 |
| CLIPPER-dBASE Compiler | MS | \$ 429 |
| dBXL by Word Tech | PC | \$ 129 |
| Lattice RPF II Compiler | PC | \$ 719 |
| MasterForth - Forth '83 | MAC or PC | \$ 109 |
| Microsoft MASM - faster | MS | \$ 98 |
| Modula-2/86 Compiler by Logitech | | |
| w/8087 (\$ 99), 512K (\$145). | PC | \$ 62 |
| Pasm - by Phoenix | MS | \$ 109 |
| PC Forth + - by Laboratory | | |
| Microsystems | PC | \$ 205 |
| SNOBOL4+ - great for strings | MS | \$ 85 |
| Turbo Edit/ASM - by Speedware | PC | \$ 85 |

Xenix-86 & Supporting

| | | |
|----------------------------------|--|--------|
| Basic - by Microsoft | | \$ 239 |
| Cobol - by Microsoft | | \$ 639 |
| Cobol Tools - by Microsoft | | \$ 319 |
| Fortran or Pascal - by Microsoft | | \$ 439 |
| MicroFocus Lev. II Compact COBOL | | \$ 795 |
| Panel | | \$ 539 |
| RM/Cobol | | \$ 949 |
| RM/Fortran | | \$ 549 |
| Xenix Complete System | | \$1049 |

Other Products

| | | |
|------------------------------------|----|--------|
| 386 Assembler/Linker | PC | \$ 459 |
| ASMLIB - 170 + routines | PC | \$ 129 |
| BSW Make - like UNIX make | MS | \$ 85 |
| Compact Source Print | PC | \$ 59 |
| Dan Bricklin's Demo Program | PC | \$ 59 |
| dBrief - Customize BRIEF for dBASE | | |
| development. with BRIEF \$275. | PC | \$ 95 |
| H Test/H Format - XT Fix | PC | \$ 89 |
| Help/Control - on line help | PC | \$ 109 |
| Interactive Easyflow-HavenTree | PC | \$ 129 |
| Link & Locate - tools to work with | | |
| Intel and Tektronix projects. | MS | \$ 329 |
| LMK - like UNIX make | MS | \$ 139 |
| Microsoft Windows | PC | \$ 69 |
| Software Development Kit | PC | \$ 329 |
| MKS Toolkit - Unix, vi, awk | PC | \$ 119 |
| PDisk - cache, tree | PC | \$ 89 |
| PMaker - by Phoenix | PC | \$ 79 |
| Polymake by Polytron | MS | \$ 79 |
| PS MAKE by UniPress | MS | \$ 79 |
| SECRET DISK by Lattice | PC | \$ 89 |
| SoftEst - Manage projects. | MS | \$ 350 |
| Source Print - by Aldebaran | PC | \$ 89 |
| Synergy-Create user interfaces | MS | \$ 375 |
| Texsys - control source | MS | \$ 89 |
| Tom Rettig's Library - dBASE | PC | \$ 89 |
| Tree Diagrammer | PC | \$ 59 |
| Visible Computer: 8088 | PC | \$ 65 |

Circle no. 133 on reader service card.

Note: All prices subject to change without notice. Mention this ad. Some prices are specials. Ask about COD and POs. Formats: 3" laptop now available. plus 200 others. UPS surface shipping add \$3/item.

Call for a catalog, literature, advice and service you can trust



HOURS



8:30 AM - 8:00 PM EST.

800-421-8006

THE PROGRAMMER'S SHOP™

5-D Pond Park Road, Hingham, MA 02043
Mass: 800-442-8070 or 617-826-7531

"YOUR SERVICE IS FABULOUS!!!
... Your information packets are so
enticing; I really want 10 of them. ...
Keep up the good work."

— Dan Bredemeyer
Bredemeyer

Circle no. 133 on reader service card.

Fortran Support for IBM PC/XT/AT & Compatibles

Versions Available For:

Microsoft, Supersoft, RyanMcFarland,
IBM Professional, Lahey, & IBM
Fortran.

Forlib-Plus \$69.95

Supports graphics, interrupt driven communication, program chaining, and file handling/ disk support. A Fortran coded subroutine is included which will plot data on the screen either in linear/linear, log/linear, linear/log, or log/log on the appropriate grid.

Strings & Things \$69.95

Supports string manipulations, command line usage, DOS call capabilities, SHELL generation and data transmission, BATCH file control, music generation, PEEKS and POKES, PORT access, and general register manipulations.

For-Winds \$89.95

Gives the Fortran programmer the capability of generating up to 255 windows on the screen. Each window can be individually scrolled, moved, sized, generated, and removed. Both color and monochrome type displays are supported. Full source code is supplied for customization.

ACS Time Series \$495.00

This is a COMPLETE time series analysis package which contains VERY HIGH SPEED FFTs, Filter generations, convolutions, transfer function calculations, auto and cross spectra calculations, Cepstrum, curve fitting algorithms, coherence calculations, and many other associated routines. The price includes FULL source code.

Fortran Scientific Subroutine Package \$295.00

There are approximately 100 Fortran subroutines included which fall under the following 12 categories:

- 1) Matrix storage and Operations
 - 2) Correlation and Regression,
 - 3) Design Analysis (ANOVA),
 - 4) Discriminant Analysis,
 - 5) Factor Analysis,
 - 6) Eigen Analysis,
 - 7) Time Series,
 - 8) Nonparametric Statistics,
 - 9) Distribution Functions,
 - 10) Linear Analysis,
 - 11) Polynomial Solutions,
 - 12) Data Screening.
- Full source code is included.



ALPHA COMPUTER SERVICE
5300 ORANGE AVENUE SUITE 108
CYPRESS, CALIFORNIA 90630
(714) 828-0286

California Residents
Include 6% Sales Tax

There are NO license fees

C CHEST

Listing Ten (Text begins on page 96.)

```
1 #include <stdio.h>
2 #include <stdarg.h>
3
4 ferr( fmt )
5 char   *fmt;
6 {
7     /* ferr() is used for fatal error processing. It
8      * is used just like printf(). However, it exits
9      * the program with a status of 1 immediately after
10     * printing the message. I'm using ANSI, not UNIX
11     * variable argument conventions here.
12     */
13
14     va_list args;
15     va_start( args, fmt );
16     vfprintf( stderr, fmt, args );
17     exit( 1 );
18 }
```

End Listing Ten

Listing Eleven

```
#include <ascii.h>

#define min(a,b)    ((a) < (b) ? (a) : (b))
#define max(a,b)    ((a) > (b) ? (a) : (b))

typedef unsigned char UCHAR;

#ifdef DEBUG
#   define D(x)  x /* For debugging, expands to it's argument when */
#   define D(x)  /* DEBUG is true, otherwise expands to an */
#   define D(x)  /* empty string. */
#else
#   define D(x)
#endif

#define MAXLTRAP 100 /* Largest line number on which we can set a line
                     * trap.
                     */

#define MAXSTR 257 /* Maximum string width (this will limit both the
                  * input and output widths
                  */

#define MAXPAGE 511 /* Max page number which can be given with the
                   * "-o" command line switch
                   */

#define MAXARGS 10 /* Max # of arguments in a macro */
#define MAXNEST 10 /* Max level of macro nesting */
#define MAXMBUF 256 /* Largest macro stored in memory. Larger */
                   /* macros are written to files. */

/*-----
 * Special characters:
 *
 * These symbols are used internally to pass information
 * from the character-oriented input functions to the
 * (in nrinp.c) to the multiple-byte character processing
 * functions (in nrtext.c and nrout.c). They are all
 * two-character sequences. Of these, VMOVE, HMOVE, and
 * CH_FONT are also used in the 16-bit wide CTYPE characters
 * discussed below.
 */

#define VMOVE ( 0xf8 ) /* Vertical motion */
#define HMOVE ( 0xf9 ) /* Horizontal motion */
#define CH_FONT ( 0xfa ) /* Change font */
#define CH_ATTRIB ( 0xfb ) /* Change attribute in current font */
#define SOFT_HYPHEN ( 0xfc ) /* A soft hyphen goes here. */
#define ZWIDTH ( 0xfd ) /* Next character is zero width */
#define UP_SPACE ( 0xfe ) /* Unpaddable space */
#define LITCHAR ( 0xff ) /* next character goes to printer is
                          * literal (it goes to the printer
                          * unchanged.
                          */

/*-----
 * Default fonts and attributes:
 *
 * BOLD, OVER, and ITALICS are attributes which may apply to any font. PREVIOUS
 * turns off these attributes but doesn't spring a change font macro. ROMAN
 * replaces the current font with the roman font and also clears all
 * attributes.
 */

#define BOLD 'B' /* Bold face */
#define OVER 'O' /* Overstrike */
#define ITALICS 'I' /* Italics */
#define PREVIOUS 'P' /* Previous */
#define ROMAN 'R' /* Roman */

/*-----
 * Legal adjustment modes
 */

#define BOTH 'b'
#define ALT_BOTH 'n'
#define LEFT 'l'
#define RIGHT 'r'
#define CENTER 'c'
```

(continued on page 53)

Turbo Tech Report Speaks Your Language.

Turbo Pascal
Articles and
Reviews

News and
commentary

A disk filled
with Turbo Pascal
code!



The newsletter/disk publication for Turbo Pascal® users

Are you a devoted Turbo Pascal programmer, tired of reading about other languages? Are you looking for powerful utilities written in Turbo Pascal that you can use to develop software or incorporate into your programs? Are you interested in improving and expanding your Turbo Pascal programming skills?

Then you deserve a subscription to *Turbo Tech Report*, the bimonthly newsletter/disk publication from the publishers of *Dr. Dobb's Journal* and *Micro/Systems Journal*. Each issue delivers more than 250K of Turbo Pascal source code programs on disk, and 20+ pages of articles, Turbo Pascal software and book reviews, and analysis and commentary. It's the only publication delivering such focused technical articles with code on disk—and it doesn't waste your time with information about other programming languages. Each valuable issue contains:

- **Articles** on topics like speedy 3D graphics, mathematical expression parsers, creating global gotos, memory resident and AI applications and more—all written by Turbo experts.

- **Reviews** of the latest Turbo Pascal software programs from companies like Borland

International, Blaise Computing, Media Cybernetics, Nostradamus, TurboPower Software, and more!

- **News and commentary** detailing the latest products and developments in the Turbo Pascal programming community.

- **A disk filled with Turbo Pascal code!** You'll get the Turbo Pascal utilities and routines discussed in the newsletter's articles, as well as applications developed by Turbo users from around the world. You'll receive programs that make labels, generate menus, provide faster screen access, transfer files between CP/M and MS-DOS computers, and more!

If you're an expert Turbo Pascal programmer or a novice interested in expanding your Turbo skills, you need a publication that speaks your language: *Turbo Tech Report*. Subscribe today at the special price of just \$99—that's 33% off the regular price of \$150. To order by credit card, call toll-free 1-800-528-6050 ext. 4001 and ask for item 300. Or mail the attached coupon with your payment to *Turbo Tech Report*, 501 Galveston Drive, Redwood City, CA 94063.

Turbo Pascal is a trademark of Borland International Inc.

SOFTSTRIP® NOW OFFERS YOU SOMETHING NEVER BEFORE AVAILABLE...



CONVENTIONAL DATA HANDLING



THE SOFTSTRIP SYSTEM

A CHOICE.

Until now you were stuck with disks.

No more. Install our unique STRIPPER™ software on your personal computer today and discover the many benefits of the fastest, easiest, least expensive way to handle information.

STRIPPER lets you print — ON PAPER — your own machine readable Softstrip data strips using your dot matrix printer. The Softstrip System Reader reads that information into a computer rapidly. With STRIPPER and the reader, your PC and printer become part of the most versatile information handling system available.

With this system you can do anything you wish with any data you have in your PC — ON PAPER.

DATA ENTRY: Why use keystrokes when you can eliminate them with data strips? Whatever the document - invoices, packing slips, memos, letters, sales reports, the list is endless — simply print a data strip right on the same printed page. Now you have a document that is both human readable and machine readable. A typical document can be entered in only 15 seconds using data strips. And, it ends keystroke errors forever.

DATA DISTRIBUTION: Why copy disks? It's time consuming and expensive. Softstrip data strips will end all that. Simply photocopy as many data strips as you like and send them by mail. Data strips ignore folding, coffee stains, ink marks and, by the way,

magnetic fields. And if you're using telecommunications, you can stop making the phone company rich.

DATA STORAGE AND RETRIEVAL: Why have a file of disks and a file of paper? Eliminate one with Softstrip data strips. File the data strip with the document. Better still, print the strip right on the document. Then put it in a file or binder.

Retrieval is simple. To find existing data, pull the document and its related data strip from the file. They've been stored together. Then use the reader to enter the data. No more hassle trying to match documents with the right disk — if you can find it.

DATA TRANSFER: Why bother with cables, modems and phone lines to move files between computers? A Softstrip data strip generated by an IBM PC can be read into another PC, or compatible, an Apple or even a Macintosh. If you work at home on a Macintosh, make a data strip on your printer, take it into the office and read it into your IBM PC. Simple. And we've created the utilities to let you do that easily. (See Application Notes on opposite page.)

Fascinating, isn't it? Anything you can do with disks can be done with the Softstrip data strip system — faster, easier and at lower cost — ON PAPER.

All you need is STRIPPER software at **\$19.95** and the Softstrip System Reader at **\$199.95**.

Softstrip
COMPUTER READABLE PRINT

The
PC
User's
Edge

NOW! TRANSFER DATA – PROGRAM TO PROGRAM WITH SOFTSTRIP®

Now you can move data between programs quickly and easily using SOFTSTRIP data strips.

Using the Softstrip System, you can move data between computers and such programs as WordStar and MacWrite, dBASE and AppleWorks, Lotus 1-2-3 and Excel and ReadySetGo and many others.

We've created a series of several dozen Application Notes on Softstrip data strips. These lead you through simple steps to make the file transfer as easy as possible, adding even more versatility to your personal computer when you purchase the SOFTSTRIP SYSTEM. The advanced system you've been hearing so much about.

All you need to move data between programs is STRIPPER™ software at **\$19.95** and the Softstrip System Reader at **\$199.95**.

For a complete list of Application Notes, contact your dealer or call Cauzin.

MARCH CASE HISTORY

A major manufacturer and distributor of yachting products is putting SOFTSTRIP data strips to good use moving information from its headquarters to a branch office.

The company has a large mainframe system in operation. However, a substantial amount of internal information is generated off-line using Macintosh and Apple II computers. That information can include memos, spreadsheet data, sales leads and similar information. Some of that information is needed by another office about 50 miles away.

Until the company installed the SOFTSTRIP System, all information had to be sent to the branch office in hardcopy form, where it was rekeyed into the branch's computer.

Now, however, information destined for the branch office is stored during the day and printed out on SOFTSTRIP data strips at the end of the day. Then it is mailed to the branch where its loaded into computers using the SOFTSTRIP reader.

According to the company, the system works extremely well, saving the considerable personnel time required to rekey the data, and it also reduces the chance of errors occurring.



Softstrip

Users' Groups: Call for Special User Group Discounts.

ACT NOW! Don't delay. See your local Softstrip dealer or call us at 1-800-533-7323. In Connecticut: 203-573-0150.

CAUZIN

835 South Main Street
Waterbury, CT 06706
(203) 573-0150

For Europe and Asia Contact:

Softstrip International, Ltd.
53 Bedford Square
London, WC1 B3DP England
01-631-3775 Telex: 263874SOFTST G

Circle no. 307 on reader service card.

This data strip contains IBM2MAC, a utility that runs on the IBM and converts an IBM file to Macintosh format.



Programmer's Paradise Gives You Superb Selection, Personal Service and Unbeatable Prices!

Welcome to Paradise. The MS/PC-DOS and XENIX software source that caters to your programming needs. Discover the Many Advantages of Paradise...

- Lowest price guaranteed
- Latest versions
- Huge inventory, immediate shipment
- Knowledgeable sales staff
- Special orders
- 30-day money-back guarantee

We'll Match Any Nationally Advertised Price.

| LIST OURS | |
|-----------------------------|------------|
| C++ | |
| ADVANTAGE C++ | \$ 495 469 |
| PFORCE++ | 395 CALL |
| C COMPILERS | |
| C-86 PLUS | 497 445 |
| DATALIGHT - C | 60 49 |
| DATALIGHT C DEVELOPER'S KIT | 99 79 |
| LATTICE C 3.2 | 500 269 |
| LATTICE C W/SOURCE | 900 545 |
| LETS C | 75 59 |
| W/CSD DEBUGGER | 150 109 |
| MICROSOFT C 4.0 | 450 275 |
| MARK WILLIAMS C | 495 289 |
| MARKUSOFT C | 395 339 |
| WIZARD C | 450 369 |
| C INTERPRETERS | |
| C-TERP | 300 235 |
| INSTANT C | 500 379 |
| INTRODUCING C | 125 105 |
| RUN/C | 150 89 |
| RUN/C PROFESSIONAL 1.1 | 250 169 |

| | |
|---------------------|---------|
| ASSEMBLERS, LINKERS | |
| 386ASM/LINK | 495 445 |
| ADVANTAGE LINK | 395 349 |
| MACRO-86 | 150 98 |
| PASM-86 | 195 125 |
| PLINK 86 PLUS | 495 325 |
| QUELO 68000 X-ASM | 595 509 |

Lattice Specials

| | |
|-----------------------------|----------|
| C COMPILER | 500 269 |
| C CROSS REFERENCE GENERATOR | 50 35 |
| C FOOD SMORGASBORD | 150 95 |
| C-SPRITE | 175 125 |
| CURSES | 125 85 |
| DBC-III | 250 175 |
| LMK | 195 135 |
| RPG II COMPILER | 750 635 |
| RPG COMBINATION PACK | 1100 939 |
| SECRET DISK | 120 85 |
| SIDETALK | 120 85 |
| TEXT MANAGEMENT UTILITIES | 120 85 |

| | |
|----------------------------------|---------|
| GRAPHICS | |
| ADVANTAGE GRAPHICS | 295 225 |
| ESSENTIAL GRAPHICS | 250 195 |
| GRAPHIC | 350 289 |
| GSS GRAPHICS DEVELOPMENT TOOLKIT | 495 379 |
| GSS KERNEL SYSTEM | 495 379 |
| GSS METAFILE INTERPRETER | 295 239 |
| GSS PLOTTING SYSTEM | 495 379 |
| HALO—ONE LANGUAGE | 300 209 |
| W/TEN FONT PACK | 425 297 |
| HALO—FIVE MICROSOFT LANGUAGES | 595 415 |
| METAWINDOWS | 185 115 |
| METAWINDOWS PLUS | 235 189 |
| METAFONTS | 80 59 |
| METAFONTS PLUS | 235 189 |

C UTILITY LIBRARIES

| | |
|-----------------------------|-----------|
| ASYNC MANAGER | 175 135 |
| BASIC C | 175 129 |
| C ESSENTIALS | 100 85 |
| C FOOD SMORGASBORD | 150 95 |
| W/SOURCE | 300 188 |
| C TOOLS PLUS | 175 135 |
| ESSENTIAL C UTILITY LIBRARY | 185 135 |
| ESSENTIAL COMMUNICATIONS | 185 135 |
| W/BREAKOUT DEBUGGER | 250 195 |
| GREENLEAF FUNCTIONS | 185 135 |
| GREENLEAF COMM | 185 135 |
| THE HAMMER | 195 175 |
| MULTI C | 149 135 |
| MULTI COMM | 149 135 |
| PPORCE | 395 245 |
| TIMESLICER | 295 265 |
| W/LIBRARY SOURCE | 1000 CALL |
| TOPVIEW TOOLBASKET | 250 189 |

SCREEN DISPLAY, WINDOWS FOR C

| | |
|------------------------|-----------|
| C WORTHY | 295 269 |
| CURSES | 125 85 |
| W/SOURCE | 250 184 |
| GREENLEAF DATA WINDOWS | 225 179 |
| W/SOURCE | 395 339 |
| FLASH UP WINDOWS | 75 68 |
| MICROSOFT WINDOWS | 500 319 |
| DEVELOPMENT SYSTEM | 149 109 |
| ON-LINE HELP | 295 219 |
| PANEL | 150 135 |
| POLYWINDOWS | CALL CALL |
| SCREENPLAY (LATTICE) | 195 175 |
| SOFTSCREEN HELP | 275 199 |
| VIEW MANAGER | 225 199 |
| VITAMIN C 3.0 | 99 84 |
| VC SCREEN | 195 145 |
| WINDOWS FOR C | 295 239 |
| WINDOWS FOR DATA | 245 189 |
| Z VIEW | 245 189 |

FILE MANAGEMENT

| | |
|----------------------|---------|
| BTRIEVE | 245 195 |
| XTRIEVE | 245 195 |
| W/REPORT GENERATION | 390 315 |
| BTRIEVE/N | 595 465 |
| XTRIEVE/N | 595 465 |
| W/REPORT GENERATION | 940 750 |
| C TREE | 395 329 |
| R TREE | 295 249 |
| C TREE/R TREE BUNDLE | 650 529 |
| COL | 395 329 |
| DBC III | 250 175 |
| W/SOURCE | 500 379 |
| DBC III PLUS | 750 599 |
| DB VISTA | 195 155 |
| W/SOURCE | 495 425 |
| DB QUERY | 195 155 |
| W/SOURCE | 495 425 |
| FABS | 150 129 |
| FABS PLUS | 195 169 |
| INFORMIX | 795 639 |
| INFORMIX 4GL | 995 799 |
| INFORMIX SQL | 795 639 |
| PHACT | 295 265 |

MAKE, LINT, PROFILE, UTILITIES

| | |
|-----------------------------|-----------|
| C CROSS REFERENCE GENERATOR | 50 35 |
| LMK | 195 135 |
| POLYMAKE | 99 78 |
| OTHER POLYTRON | CALL CALL |
| PMaker | 125 89 |
| PFINISH | 395 235 |
| THE PROFILER | 125 94 |
| PC LINT | 139 105 |
| PRE-C | 295 159 |
| TEXT MANAGEMENT UTILITIES | 120 85 |

DEBUGGERS

| | |
|---------------------|---------|
| ADVANCED TRACE 86 | 175 129 |
| BREAKOUT | 125 99 |
| CODESMITH 86 | 145 105 |
| C-SPRITE | 175 125 |
| CSD SOURCE DEBUGGER | 75 59 |
| PERISCOPE I 3.0 | 345 293 |
| PERISCOPE II 3.0 | 175 145 |
| PERISCOPE II-X 3.0 | 145 109 |
| PFX 86 PLUS | 395 235 |
| XVIEW 86 | 60 49 |

March BUNDLE of the Month

RUN/C Pro- Best-selling C interpreter PLUS Greenleaf Functions or C Utility Library. Convenience disk included—One command loads library!

LIST TOGETHER \$435 OURS \$289

EDITORS

| | |
|--------------|----------|
| BRIEF | 195 CALL |
| CVUE | 75 59 |
| W/SOURCE | 250 195 |
| EDIX | 195 165 |
| EMACS | 295 255 |
| EPILION | 195 159 |
| FIRSTIME (C) | 295 229 |
| KEDIT | 125 105 |
| LSE | 125 89 |
| PMATE | 195 119 |
| PC/VI | 149 129 |
| SPF/PC | 195 149 |
| VEDIT | 150 109 |
| VEDIT PLUS | 185 139 |

ADDITIONAL PRODUCTS

| | |
|-----------------------------|---------|
| DAN BRICKLIN'S DEMO PROGRAM | 75 59 |
| FASTBACK | 175 149 |
| INTERACTIVE EASYFLOW | 150 129 |
| INTERVIEW | 195 129 |
| SOURCE PRINT | 97 87 |
| TREE DIAGRAMMER | 77 69 |
| VENTURA PUBLISHER (XEROX) | 895 805 |

PASCAL COMPILERS

| | |
|------------------|-----------|
| MICROSOFT PASCAL | 300 189 |
| PASCAL 2 | 350 329 |
| TURBO PASCAL | 100 69 |
| OTHER BORLAND | CALL CALL |

TOOLS FOR TURBO PASCAL

| | |
|------------------------|-----------|
| ALICE | 95 68 |
| FIRSTIME | 75 59 |
| FLASH UP WINDOWS | 90 79 |
| TURBO HALO | 129 99 |
| SCREENPLAY | 100 89 |
| SCREEN SCULPTOR | 125 94 |
| T-DEBUG PLUS | 60 50 |
| TURBO EXTENDER | 85 65 |
| TURBO PASCAL ASYNC MGR | 100 84 |
| TURBO PROFESSIONAL | 70 49 |
| TURBO POWER TOOLS PLUS | 100 83 |
| TURBO WINDOWS | 80 65 |
| OTHER TURBO TOOLS | CALL CALL |

NEW Products

ADVANTAGE C++ for XENIX—Take advantage of object-oriented programming methods. Add resiliency and flexibility to your code. Build large and sophisticated programs more productively. Ours \$660

ADVANTAGE Make—Feature-packed MS/PC-DOS version of UNIX MAKE utility. List \$125 Ours \$99

SSP/PC—Fast, extremely accurate library of over 145 math subroutines. Callable from C, FORTRAN, Pascal, BASIC. Ours CALL

TIMESLICER—New Microsoft version. Multitasking, linkable library supporting concurrent tasks and real-time event processing with header files provided for C++, C and assembly. Library source available! Ours \$265

VENTURA PUBLISHER (XEROX)—Desktop publishing software, lightning fast, loaded with features. Create professional-looking documentation at minimal cost! Ours \$805

| | |
|----------------------|-----------|
| BASIC | |
| BETTERBASIC | 199 139 |
| SUMMIT ADD ONS | CALL CALL |
| BETTER TOOLS | 95 89 |
| FINALLY | 99 89 |
| MICROSOFT QUICKBASIC | 99 75 |
| PROFESSIONAL BASIC | 99 75 |
| 8087 MATH SUPPORT | 50 45 |
| PANEL-BASIC | 145 115 |
| TRUE BASIC | 150 105 |
| ADD ONS | CALL CALL |

| | |
|---------------------------|-----------|
| COBOL COMPILERS/UTILITIES | |
| MICROSOFT COBOL | 700 445 |
| MICROSOFT COBOL TOOLS | 350 205 |
| MICROSOFT SORT | 195 139 |
| MICRO/SPF | 175 CALL |
| OPT-TECH SORT | 149 115 |
| REALIA COBOL | 995 785 |
| SCREENPLAY | 175 155 |
| RM/COBOL | 950 639 |
| RM/COBOL 8X | 1250 895 |
| VISUAL COBOL (MBP) | 1150 1015 |

| | |
|--------------------------------|----------|
| FORTRAN COMPILERS/UTILITIES | |
| LAHEY FORTRAN | 477 CALL |
| MICROSOFT FORTRAN | 350 209 |
| RM/FORTRAN | 595 389 |
| ACS TIMES SERIES | 495 419 |
| 87 SFL | 250 225 |
| FOR-WINDS | 90 78 |
| FORLB-PLUS | 70 54 |
| GRAMMATICS OR PLOTMATICS | 135 119 |
| GRAMMATICS AND PLOTMATICS | 240 219 |
| FORTRAN SCIENTIFIC SUBROUTINES | 295 249 |
| STRINGS AND THINGS | 70 54 |

XENIX/UNIX SOFTWARE

| | |
|--|-----------|
| XENIX SYSTEM V (COMPLETE SYSTEM) — SCO | 1295 995 |
| SYSTEM V/AT — MICROPORT | 440 395 |
| OTHER SCO AND MICROPORT | CALL CALL |
| ADVANTAGE C++ | 695 660 |
| BTRIEVE | 595 465 |
| C-ISAM | 319 285 |
| C TREE | 395 329 |
| MICROSOFT BASIC | 350 239 |
| MICROSOFT COBOL | 995 635 |
| MICROSOFT COBOL TOOLS | 450 205 |
| MICROSOFT FORTRAN | 695 439 |
| MICROSOFT PASCAL | 625 545 |
| PANEL | 1250 949 |
| RM/COBOL | 750 549 |
| RM/FORTRAN | 750 549 |

ADDITIONAL LANGUAGES

| | |
|--------------------------|---------|
| API PLUS | 595 429 |
| JANUS ADA/C PACK | 95 89 |
| LOGITECH MODULA 2 | 89 63 |
| PC/FORTH | 150 119 |
| SMALLTALK V | 99 88 |
| TURBO PROLOG | 100 75 |
| CALL FOR OTHERS/ADD-ONS! | |

Terms and Policies

We honor MC, VISA, AMERICAN EXPRESS
No surcharge on credit card or C.O.D. Prepayment by check. New York State residents add applicable sales tax. Shipping and handling \$3.00 per item, sent UPS ground. Rush service available, prevailing rates.

- Programmer's Paradise will match any current nationally advertised price for the products listed in this ad.
- Mention this ad when ordering — some items are specially priced.
- Prices and Policies subject to change without notice.
- Corporate and Dealer inquiries welcome.

1-800-445-7899 In NY: 914-332-4548

Programmer's Paradise
412 River Street, Tarrytown, NY 10591
914-332-4548

Programmer's Paradise



Dr. Dobb's Journal, March 1987

C CHEST

Listing Eleven (Listing continued, text begins on page 96.)

```

/*-----
* Number registers:
*
* The number registers are maintained as an array pointers to NREG
* type objects. The array is kept sorted by register name.
* nname is a pointer to the name, it usually points at nbuf.
*/

typedef struct _nr
{
    char      nname[3];
    int       nfmt;
    int       nval;
    int       incr_amt;
} NREG;

/* Read/write pre-defined number registers: */
extern NREG *Nrpg; /* % Page number
extern NREG *Nrday; /* % dy Day
extern NREG *Nrday; /* % dw day of the week (0 = sun, 6= sat)
extern NREG *Nrhr; /* % h hour
extern NREG *Nrln; /* % ln Current .nm line number
extern NREG *Nrnl; /* % nl Current output line number
extern NREG *Nrm; /* % m minute
extern NREG *Nrmo; /* % mo Month
extern NREG *Nrs; /* % s second
extern NREG *Nryr; /* % yr Year

/* Read only pre-defined number registers: */
extern NREG *Nrhp; /* % hp Current horizontal place on input line
extern NREG *Nrhd; /* % dh Height of most recent diversion
extern NREG *Nrld; /* % dl Width of last completed diversion
extern NREG *Nrargs; /* % $ Number of args at current macro level
extern NREG *Nrlns; /* % c Number of lines read from current macro
extern NREG *Nrvtplace; /* % d Current vert. place in current diversion
extern NREG *Nrfont; /* % f Index in Font[] of current font
extern NREG *Nrindent; /* % i Current indent column
extern NREG *Nrllen; /* % l Current line length
extern NREG *Nrllen; /* % n Length of text portion of previous line
extern NREG *Nroffset; /* % o Current page offset
extern NREG *Nrp; /* % p Current page length
extern NREG *Nrtotrap; /* % t Distance to next trap
extern NREG *Nrfill; /* % u 1 if in fill mode, 0 otherwise
extern NREG *Nrv; /* % v current vertical base-line spacing

/*
* Number register format types. The specified character found in the
* left-most position of the .af command's c argument signifies the
* type. In addition, the number of characters in the arabic padded mode
* determines the fieldwidth of the number.
* The format for arabic numbers is an ascii digit. If this digit is
* '0' or '1' then the number is printed unpadded. If the digit is a '4'
* it is printed in a 4 space field, right justified in the field and
* padded with zeros. The special format READONLY is used by the read
* only pre-defined number registers. They are always arabic format.
*/

#define ARABIC '1' /* 0, 1, 2, ...
#define PADDED '0' /* 000, 001, 002, ...
#define LC_ROMAN 'i' /* 0, 1, ii, iii, iv, v, ...
#define UC_ROMAN 'I' /* 0, 1, II, III, IV, V, ...
#define LC_ALPHA 'a' /* 0, a, b, ... , z, aa, ab ...
#define UC_ALPHA 'A' /* 0, A, B, ... , Z, AA, AB ...
#define LC_ENG 'e' /* zero, one, two, three ...
#define UC_ENG 'E' /* Zero, One, Two, Three ...
#define READONLY 'r' /* Pre-defined, arabic format only

/*-----
*
* Default values of the pre-defined number registers
*/

#define DEF_PAGE 1 /* Page number
#define DEF_WIDTH 0 /* Width of most recent diversion
#define DEF_HEIGHT 0 /* Height of most recent diversion
#define DEF_DAY 1 /* Default day
#define DEF_HORIZ 1 /* Current place on input line
#define DEF_LINE 1 /* Default month
#define DEF_MONTH 1 /* Default year
#define DEF_YEAR 1985 /* # Args in current macro
#define DEF_NARGS 0 /* # Lines read from current input
#define DEF_INLINES 0 /* Vertical place in current diversion
#define DEF_VERT 1 /* Index in Font[] of current font
#define DEF_FONT 0 /* Current indent column
#define DEF_INDENT 0 /* Default line length
#define DEF_LINLEN 80 /* Len of text part of previous line
#define DEF_TEXTLEN 0 /* Page offset
#define DEF_OFFSET 0 /* Page length
#define DEF_PGLEN 66 /* Distance to next trap
#define DEF_TOTRAP 66 /* 1 if in fill mode
#define DEF_FILL 0 /* Default line spacing
#define DEF_LS 1

/*-----
*
* Largest column in which a tab can be set */
typedef int TSTOP[ NUMTABS ];
extern TSTOP Tabstop; /* The tabstop array (see nrqlb1.c)

/*
* Table used by command() to parse command lines:
*/

typedef char *CHARPTR;

```

(continued on next page)

MULTITASKING

Introducing

MultiDos Plus

The new multitasking software for the IBM-PC.

Ideal for developing applications in process control, data acquisition, communications, and other areas. Check these features which make **MultiDos Plus** an unbeatable value.

- Run up to 32 programs concurrently.
- Your software continues to run under DOS. No need to learn a new operating system.
- Use the compilers you already have. Supports software written in any language.
- Operator commands to load/run programs, change priority, check program status, abort/suspend/resume programs.
- Programmatic interface via INT 15H for the following.
 - * Intertask message communication. Send/receive/check message present on 64 message queues.
 - * Task control by means of semaphores. Get/release/check semaphores.
 - * Change priority-128 priority levels.
 - * Suspend task for specified interval.
 - * Spawn and terminate external and internal tasks.
 - * Disable/enable multitasking.
 - * and more!
- Runs most commodity software including: Lotus 1-2-3, Dbase, Wordstar, and others.
- Independent foreground/background displays.
- Access to DOS while applications are running.

Hardware/Software Requirements

IBM PC/XT/AT or true clone. Monochrome/CGA display adaptors or equivalent cards only. Enough memory to hold **MultiDos Plus** (48 KB) and all your application programs. Also may need 4 or 16 KB memory for "hidden screens" for each active task. MS-DOS (or PC-DOS) 2.0 or later operating system.

ONLY \$29.95 + \$2.95 S/H

Outside USA add \$7.95 shipping and handling.

Visa and Mastercard orders call toll-free: 1-800-367-6707. In Mass call 617-651-0091, or send check or money order to:


NANOSOFT
13 Westfield Rd, Natick, MA 01760

MA orders add 5% sales tax. Write for source code and quantity price.

Circle no. 309 on reader service card.

Byte Magazine called it.

"CIARCIA'S SUPER SYSTEM"



The SB180 Single Board Computer

Featured on the cover of Byte, Sept. 1985,
the SB180 lets CP/M users upgrade to a
fast, 4" x 7 1/2" single board system.

- 6MHz 64180 CPU
(Z80 instruction superset), 256K RAM,
8K Monitor ROM with device test, disk
format, read/write.
- Mini/Micro Floppy Controller
(1-4 drives, Single/Double Density,
1-2 sided, 40/77/80 track 3 1/2", 5 1/4"
and 8" drives).
- Measures 4" x 7 1/2" with mounting holes
- One Centronics Printer Port
- Two RS232C Serial Ports
(75-19,200 baud with console port
auto-baud rate select).
- ZCPR3 (CP/M 2.2/3 compatible)
- Multiple disk formats supported
- Menu-based system customization

New Low Prices

SB180-1
SB180 computer board w/256K
bytes RAM and ROM monitor
..... \$299.00

SB180-1-20
same as above w/ZCPR3, ZRDOS
and BIOS source \$399.00

COMM180-S
SCSI interface \$150.00

Now Available

TURBO MODULA-2 \$69.00
TURBO MODULA-2 with
Graphix Toolbox \$89.00

TO ORDER
CALL TOLL FREE
1-800-635-3355

TELEX
643331

For Technical Information or in CT, call:
1-203-871-6170



Micromint, Inc.
4 Park Street
Vernon, CT 06066

C CHEST

Listing Eleven (Listing continued, text begins on page 96.)

```
typedef struct
{
    char      *cmd;          /* Command name */
    int      (*action)();    /* Subroutine to call when cmd found */
    unsigned type : 3;       /* Command type */
    unsigned inhib : 1;      /* 1 ==> Inhibit works */
    char      *def;          /* Default value of numeric argument */
}
CTAB;

/*-----
 * Table of user defined fonts (Fonts) is made up of FONT type.
 * NUMFONTS is the maximum number of user defined fonts.
 * The "widths" array holds the character widths. Maximum
 * number of characters is MAX_CHARS_IN_FONT. Font numbers
 * must be single characters (In the range 0-9) so NUMFONTS
 * must be <= 10. The "resolution" field is the middle argument
 * from the .hd command that was in effect when the .df was
 * executed. If a space is 6 units wide and "resolution" is set to
 * 2, then sending Right str to the printer three times will
 * move the carriage one space to the right. If "resolution" is
 * 1, then the string will have to be sent 6 times to move the
 * same amount.
 */

typedef struct
{
    UCHAR      name;         /* Font name */
    UCHAR      smac[3];      /* Macro to enter new font */
    UCHAR      emac[3];      /* Macro to exit font */
    int      resolution;     /* Min horizontal resolution from .hd */
    UCHAR      *left;        /* String to go left from .hd */
    UCHAR      *right;       /* String to go right from .hd */
    UCHAR      *widths;      /* Array of character widths. */
}
FONT;

#define NUMFONTS      10
#define MAX_CHARS_IN_FONT 256

/*-----
 * Msc #defines and typedefs
 */

#define ISCMD(c) ( (c) == Cmd_chr || (c) == Nobreak )

/*-----
 * #Defines to get at the value fields of the pre-defined
 * number registers (Those marked with an E are saved with a .ev
 * command):
 */

#define PAGE      (Nrpg->nval)      /* Page number */
#define WIDTH     (Nrwl->nval)      /* Width of last completed diversion */
#define HEIGHT    (Nrhd->nval)      /* Height of last completed diversion */
#define DAY       (Nrday->nval)     /* Day */
#define HORIZ     (Nrhp->nval)      /* Current horiz-> place on input line */
#define LINE      (Nrln->nval)      /* Current .nm line number */
#define OLINE     (Nrln->nval)      /* Current output line number */
#define MONTH     (Nrmo->nval)      /* Month */
#define YEAR      (Nryr->nval)      /* Year */
#define NARGS     (Nrargs->nval)    /* # of args at current macro level */
#define INLINES   (Nrlnes->nval)    /* # of lines read from current input */
#define VERT      (Nrvtpl->nval)    /* Vert. place in current diversion */
#define CURFONT   (Nrfont->nval)    /* Currently active font (Font[i]) (E) */
#define INDENT    (Nrindent->nval)  /* Current indent column (E) */
#define LINLEN    (Nrlin->nval)     /* Current line length (E) */
#define TEXTLEN   (Nrtext->nval)    /* Length of text part of prev out line */
#define OFFSET    (Nrffset->nval)   /* Current page offset (E) */
#define PGLLEN    (Nrpllen->nval)   /* Current page length (E) */
#define TOTRAP    (Nrtotrap->nval)  /* Distance to next trap (E) */
#define FILL      (Nrfill->nval)    /* 1 if in fill mode, 0 otherwise (E) */
#define LSPACE    (Nrvtpl->nval)    /* Current line spacing (set w/.ls) (E) */

#define WEEKDAY   (Nrwd->nval)      /* day of the week */
#define HOUR      (Nrhr->nval)      /* hour */
#define MIN       (Nrmm->nval)      /* minute */
#define SEC       (Nrss->nval)      /* second */

/*-----
 * Global vars used by more than one module. (Those marked with an E are
 * saved with a .ev command.) Most of these are declared in nrgbls.h
 * but some are command-line switches and are found in nr.c.
 */

extern int Adjmode; /* Current adjustment mode */
extern int Adjusting; /* One if adjusting lines */
extern int Cmd_chr; /* Command character */
extern int ConC_ul; /* Num of input lines to continuously underline */
extern int DivTrap; /* Location of diversion trap, -1 if none */
extern char Dtrap_name[]; /* Macro to invoke when diversion trap reached */
extern int Divwidth; /* Width of most of last completed diversion */
extern int Esc; /* Current escape character */
extern int Hyphenate; /* Hyphenation is enabled during filling only */
extern int Hyphen_chr; /* Soft hyphen is \<Hyphen_chr>. default = \< */
extern char *Endm; /* Name of macro invoked at end of input */
extern FONT Fonts[]; /* Table of user defined fonts */
extern int H_units; /* Number of horizontal units / inch */
extern int H_space; /* Number of horizontal units in a space */
extern int Ifile; /* Current input file */
extern char *Ifilename; /* Name of current input file */
extern int Inhibit; /* Inhibit text and command processing except .(.) */
extern int Itrap; /* Lines left to current input trap -1 if none */
extern char Itrap_name[]; /* Macro to invoke when Itrap reaches 0 */
extern int Iamacro; /* 1 if Ifile is a macro, 0 if a file */
extern int Iadiv; /* 1 if Ofile is a diversion, 0 if a file */
extern int Leader; /* Current leader character */
extern int Linenum; /* Current output line number
```


DAN BRICKLIN'S DEMO PROGRAM

Read what they're saying about this new concept in prototyping and demo-making:

"A winner right out of the starting gate. After you use DEMO once, you'll wonder how you got along without it."

— PC Magazine, 4/29/86

"Everybody who writes software, either commercially or for in-house applications, should immediately order a copy. Period. No exceptions."

— Soft*letter, 4/20/86

"Its low price, superb performance, and range of applications practically guarantee that it will be widely used. Four Floppy Rating (8.0)"

— InfoWorld, 3/31/86

"Apparently has a hit on its hands with... a development tool for personal computer software that has won rave reviews from early users."

— Computerworld, 4/7/86

"A gem."

— PC Week, 3/18/86

Product of the Month

— PC Tech Journal, 3/86

ORDER NOW!

Thousands of developers are designing better products faster and producing more effective demonstrations using Dan Bricklin's Demo Program. You can, too. Act now!



ONLY \$74.95
617-332-2240

Massachusetts residents add \$3.75. Outside of the U.S.A. add \$15.00.

Requires 256k IBM PC/compatible, DOS 2.0 or later. Supports Monochrome, Color/graphics, and EGA Adaptors (text mode only).



SOFTWARE GARDEN

Dept. D

P.O. Box 373, Newton Highlands, MA 02161

Circle no. 314 on reader service card.

```
extern char **Macv      /* Macros arguments for current macro level */
extern int Nobreak      /* Nobreak character */
extern int Nospace      /* Suppress spacing as per .ns command */
extern int No_cmtl      /* Don't print control characters */
extern int Nm_blanks    /* .nm will number blank lines too if true */
extern int Nm_on        /* Line numbering enabled by .nm cmd */
extern int Nm_mult      /* The M argument of the most recent .nm command */
extern char *Nm_str     /* The S argument of the most recent .nm command */
extern int Nr_cpmod     /* Nroff copy mode, expand \ in macro definitions */
extern int Num_bold     /* Remaining number of input lines to do bold */
extern int Num_center   /* Remaining number of input lines to center */
extern int Num_os       /* Number of input lines to print overstrike */
extern int Num_under    /* Remaining number of input lines to underline */
extern FILE *Ofile      /* Output file descriptor */
extern int Page_ch      /* Translates to page number in 3 part titles */
extern int Plain        /* Suppress all bold, underline, and overstrike */
extern int Ptab[]       /* Proportional spacing table */
extern int Quit         /* Terminate nroff when set by .ex command */
extern int Tab          /* Tab repetition character */
extern int Tabwidth     /* Width of input tab stops */
extern int Tabs_enabled /* Expand tabs only if true */
extern int Tempin       /* Temporary indent column */
extern int Title_len    /* 3 part title line length (set with .lt cmd) */
extern int Verbose      /* Echo commands to stdout as they're executed */
extern int Wordstar     /* Wordstar-mode output */

extern char *Lmarg_str  /* String used in .ml command */
extern char *Rmarg_str  /* String used in .mc command */
extern char *Bd_on      /* Send to printer to turn bold face on */
extern char *Bd_off     /* Send to printer to turn bold face off */
extern char *Ul_on      /* Send to printer to turn underline on */
extern char *Ul_off     /* Send to printer to turn underline off */
extern char *Os_on      /* Send to printer to turn overstrike on */
extern char *Os_off     /* Send to printer to turn overstrike off */
extern int Bold         /* Boldface currently active */
extern int Over         /* Overstrike currently active */
extern int Italics      /* Italics currently active */

extern char *Dn_str     /* Send to printer to send cursor down 1/2 line */
extern char *Up_str     /* Send to printer to send cursor up 1/2 line */
extern int Vs_amt       /* This many \u or \d cmds moves one line */

extern char *Left_str   /* Send to printer to go left */
extern char *Right_str  /* Send to printer to go right */
extern int Hs_amt       /* Above moves 1/n spaces */
```

End Listing Eleven

Listing Twelve

```
/*-----
 * Characters are handled internally as CTYPE's rather than chars.
 * The routines in nrmac.c copy character strings into CTYPE
 * strings. The #defines in this file define the various attribute
 * bits, etc., in a CTYPE:
 *-----
 *
 * pad: character is paddable, only used for spaces.
 * lit: character must be taken literally.
 * width: If 0, character takes no space in output. If 1, the
 * character's width is in the currently active character
 * width table.
 * sh: A soft hyphen precedes this character.
 * os: Overstrike attribute (character is overstruck)
 * bold: Boldface attribute
 * ul: underline attribute
 *
 * 15 14 13 12 11 10 9 8 7 6 5 4 3 2 1 0
 * +-----+-----+-----+-----+-----+-----+-----+-----+
 * | 0 | | pad | width | sh | os | bold | ul | character |
 * +-----+-----+-----+-----+-----+-----+-----+
 *
 * 15 14 13 12 11 10 9 8 7 6 5 4 3 2 1 0
 * +-----+-----+-----+-----+-----+-----+-----+-----+
 * | 1 | vm | hm | cf | amount or font-ID |
 * +-----+-----+-----+-----+-----+-----+-----+
 *
 * vm: vertical motion
 * hm: horizontal motion
 * cf: change font
 */

typedef unsigned int CTYPE;

#define CHR 0x00ff /* Character mask */
#define UNDERLINED 0x0100 /* underlined bit */
#define BOLDFACE 0x0200 /* boldface bit */
#define OVERSTRIKE 0x0400 /* overstrike bit */
#define HYPHEN 0x0800 /* soft hyphen bit */
#define WIDTH_BIT 0x1000 /* width bit */
#define NOPAD_BIT 0x2000 /* space is paddable */

#define MODE_BIT 0x8000 /* Selects one of: */
#define VM_BIT 0x4000 /* Vertical motion */
#define HM_BIT 0x2000 /* Horizontal motion */
#define FONT_BIT 0x1000 /* Change font */

#define SET_UL(c) ((c) & UNDERLINED) /* Underlined */
#define IS_UL(c) ((c) & UNDERLINED)
#define SET_BD(c) ((c) & BOLDFACE) /* Bold */
#define IS_BD(c) ((c) & BOLDFACE)
#define SET_OS(c) ((c) & OVERSTRIKE) /* Overstrike */
#define IS_OS(c) ((c) & OVERSTRIKE)
#define HYPHENATE(c) ((c) & HYPHEN) /* Soft hyphen */
#define UNHYPHENATE(c) ((c) & ~HYPHEN)
#define HAS_HYPHEN(c) ((c) & HYPHEN)

#define CLRWIDTH(c) ((c) & ~WIDTH_BIT)
#define SETWIDTH(c) ((c) & WIDTH_BIT)
```

(continued on next page)

A Reconfigurable Programmer's Editor With Source Code

ME is a high quality programmer's text editor written specifically for the IBM PC. It contains features only found in the more expensive programmer's text editors. These features include:

- Multiple Windows
- Column cut and paste
- Regular Expressions
- C-like Macro Language
- Keyboard Macros
- Reconfigurable Keyboard

New commands and features may be added to the editor by writing programs in its macro language. The language resembles C, and it's extremely easy to write and examine macros when you are not dealing with a parenthesized language like LISP. The macro languages comes with a rich set of primitives for handling strings and changing the editor environment.

The source code option lets you see how text editors are written, and gives you real-world applications of various data structures. You will also learn how to write interpreters by examining code to the macro language compiler and interpreter.

A unique advantage of the source code option is that many programmers will have the opportunity to examine the code, improve parts of it, and add additional features. The best of these improvements and enhancements will be incorporated into future releases, which, as a registered source code user, you will receive updates for.

The code is written in C, and conforms to the ANSI standard. This allows the code to be compiled with any compiler that supports the ANSI standard. A few of the string handling and input-output routines are written in 8086 assembly language for speed.

The source code option is perfect for OEMs and VARs who want to add a text editor to their applications.

Price for program and on-line documentation — \$34.95

Price for editor with complete source code — \$84.95

Special offer — New York Word word processor — \$19.95 — Split screen, mail merge, hyphenation, math, regular expressions

MAGMA SYSTEMS

138-23 Hoover Ave., Jamaica, NY 11435

Circle no. 313 on reader service card.

C CHEST

Listing Twelve (Listing continued, text begins on page 96.)

```
#define HASWIDTH(c)      ( ((c) & (MODE_BIT | WIDTH_BIT)) -- \
                          ((c) & (MODE_BIT | WIDTH_BIT)) )

#define CWIDTH(c)        (HASWIDTH(c) ? Fonts[CURFONT].widths[(c)&CHR] : 0)
#define SPACE_SIZE      ( Fonts[CURFONT].widths[ ' ' ] )

#define SETNOPAD(c)      ((c) |= NOPAD_BIT)
#define PADTABLE(c)      (! ((c) & NOPAD_BIT) )

#define ISCHAR(c)        ((c) & MODE_BIT) == 0

#define CHAR(c)          ((c) & CHR )
#define ATTRIBUTES(c)    ((unsigned)(c) >> 8 )

#define TO_CTYPE(c)      ((CTYPE)(c) | WIDTH_BIT)
#define WHITE(c)         ( !((c) & MODE_BIT) && PADTABLE(c) && CHAR(c) == ' ' )

#define FVAL(c)          ( (int)((UCHAR)(c)) )
#define MVAL(c)          ( (int)((int)(c)) << 4) >> 4 )

#define ISFONT(c)        ( ((c) & (MODE_BIT | FONT_BIT)) == \
                          (MODE_BIT | FONT_BIT) )

#define VERTICAL(c)      ( ((c) & (MODE_BIT | VM_BIT)) == \
                          (MODE_BIT | VM_BIT) )

#define HORIZONTAL(c)    ( ((c) & (MODE_BIT | HM_BIT)) == \
                          (MODE_BIT | HM_BIT) )

#define ISMOTION(c)      ( VERTICAL(c) || HORIZONTAL(c) )

#define MOTION(amt)      ( ((CTYPE)(amt) & 0xfff) | (MODE_BIT | HM_BIT) )
```

End Listing Twelve

Listing Thirteen

```
/* Length of text portion of current line. */

#define TLEN      (LINLEN - (INDENT + Tempin)) /* in spaces */
#define U_TLEN    ( TLEN * SPACE_SIZE )      /* in units */
```

End Listing Thirteen

Listing Fourteen

```
/*-----
 *                               NR.C
 *
 * (c) 1987, Allen I. Holub, All rights reserved
 *
 * This module contains the nroff main() routine, and all
 * support for command line processing.
 *-----
 */

#include <stdio.h>
#include <fcntl.h>
#include <getargs.h>
#include <bitmap.h>
#include <signal.h>
#include "nr.h"

/* Variables set by command line switches. The non-static
 * variables are used in other modules. The others are used
 * by various routines in nroff.c
 */

static char *Pagelist = NULL; /* Bit map used for -o option */
static char *Plist = ""; /* List of pages to print */
int Plain = 0; /* suppress bold, underline, etc. */
int Stop = 0; /* Stop output every N pages */
int No_cntl = 0; /* Don't print any control characters
 * except \n. Used in nroff.c
 */

static int Verbose = 0; /* echo commands as they're executed */
static int Fpage = 1; /* Number of the first page. We can't
 * use the PAGE number register
 * because number registers don't
 * exist yet.
 */

static int Even = 0; /* Print only even pages */
static int Odd = 0; /* Print only odd pages */
static int Unbuf = 0; /* Don't buffer the input stream */
extern int do_mfile(); /* Defined below, processes -m */
extern int do_tstr(); /* Defined below, processes -t */
extern int do_rreg(); /* Defined below, processes -r */

static ARG Argtab[] =
{
    {'c', BOOLEAN, &No_cntl, "don't print (C)ontrol characters" },
    {'d', BOOLEAN, &Odd, "print only o(D)d pages" },
    {'e', BOOLEAN, &Even, "print only (E)ven pages" },
    {'m', PROC, (int *) &do_mfile, "prepend (M)acro: /lib/tmac/<str>.mac" },
    {'n', INTEGER, &Fpage, "(N)umber first page N" },
    {'o', STRING, (int *) &Plist, "print (O)nly pages in list (<str>)" },
    {'p', BOOLEAN, &Plain, "Suppress bold, underline, overstrike" },
    {'r', PROC, (int *) &do_rreg, "set number (R)eg: -r<num> -r(<xx><num>)" },
    {'s', INTEGER, &Stop, "(S)top every n pages" },
    {'t', PROC, (int *) &do_tstr, "set s(T)ring: -t<str> -t(<xx><str>)" },
    {'u', BOOLEAN, &Unbuf, "Don't buffer input for debugging" },
    {'v', BOOLEAN, &Verbose, "(V)erbose mode, echo input commands" }
};
```


Listing Fourteen (Listing continued, text begins on page 96.)

```

{
    INLINES = 0;
    sprintf(nbuf, MACFILE, name);
    Ifilename = nbuf;

    if( !( Ifile = fopen(nbuf, "r") ) )
    {
        err("Can't open macro file: %s\n", nbuf);
        exit( 1 );
    }

    process( Ifile, Ifilename, 0, 0 );
    fclose( Ifile );
}

/*-----*/
do_tstr( str )
char *str;
{
    /* Called by getargs() when -t is encountered.
     * Given -tx<str> or -t(xx<str> initializes
     * register x or xx to <str>.
     */

    static char line[ MAXSTR ];
    char name[4];
    extern sgetc();

    name[2] = name[1] = 0;

    if( *str )
    {
        if( (name[0] = *str++) == '(' )
        {
            if( *str && *(str + 1) )
            {
                name[0] = *str++;
                name[1] = *str++;
            }
        }

        Ifile = (FILE *)&str;
        getline( line, 0, sgetc );
        ds(name, line );

        return;
    }

    fprintf(stderr, "Illegal string name on command line");
}

/*-----*/
do_rreg(str)
char *str;
{
    /* Processes -r command line argument. Given
     * -rx<str> or -r(xx<str> initializes number
     * register x or xx to <str>.
     */

    char name[4];
    name[2] = name[1] = 0;

    if( *str )
    {
        if( (name[0] = *str++) == '(' )
        {
            if( *str && *(str + 1) )
            {
                name[0] = *str++;
                name[1] = *str++;
            }
        }

        putnreg(name, 0, atoi(str), 0, 1, 0);
        return;
    }

    fprintf(stderr, "Illegal register name on command line");
}

/*-----*/
onintr()
{
    /* Treat a Ctrl-C or Ctrl-Break as if we've
     * executed a .ex command.
     */

    signal( SIGINT, onintr );
    mac_clean(); /* Delete all macro disk files */
    exit( 1 );
}

/*-----*/
usage()
{
    exit( 1 );
}

/*-----*/

```

```

main(argc, argv)
int argc;
char **argv;
{
    /* Initialize:
     * default, monospaced, font
     * text module
     * pre-defined number registers
     */
    df("R", "");
    init_text();
    init_nreg();

    signal( SIGINT, onintr ); /* Treat ^C like .ex */

    argc = getargs(argc, argv, Argtab,
        sizeof(Argtab)/sizeof(ARG), usage);

    PAGE = Fpage; /* Number of first page of
     * document as per -n argument.
     */

    if( *Plist || Even || Odd )
        get_pglist();

    Ofile = stdout;

    do { /* process a single input file */
        INLINES = 0;

        if( argc <= 1 )
        {
            Ifilename = "";
            Ifile = stdin;
        }
        else
        {
            Ifilename = **argv;
            Ifile = fopen( Ifilename, "r" );
            if( !Ifile )
            {
                err("Can't open input file <%s>\n",
                    Ifilename);
                break;
            }
        }

        /* The setvbuf call puts us into unbuffered
         * input mode.
         */

        if( Unbuf )
            setvbuf( Ifile, NULL, _IONBF, 0 );

        process( Ifile, Ifilename, 0, 0 );
        fclose( Ifile );
    } while( --argc > 1 && !Quit );

    brk(); /* Flush output buffer */

    /* Do the end macro if there is one. If we
     * don't clear Quit before expanding the macro,
     * getline() will return end of file and the macro
     * won't be executed.
     */

    if( *Endm )
    {
        Quit = 0;
        expand_macro(Endm);
    }

    mac_clean(); /* Delete all macros disk files */
    exit( 0 );
}

```

End Listing Fourteen

Listing Fifteen

```

/*
 * NRCMD.C
 *
 * Copyright (c) 1987, Allen I. Holub. All rights reserved.
 *
 * This module contains the routines to process individual
 * commands. Routines are accessed via the Cmdtab (see nr.c
 * and below
 */

#include <stdio.h>
#include <ctype.h>
#include "nr.h"

extern CTAB Cmdtab[];
extern int Ctabsize;
extern char *skipto(), *skipspace(); /* in tools.lib */
extern char *bsearch();

/*-----*/

cmdcmp( matchstr, cp )
register unsigned char *matchstr;
register CTAB *cp;
{
    /* Comparison routine used by search called in
     * command() below.
     */
}

```



```

register unsigned int  l, r;

D( printf("comparing %2.2s ", matchstr) );
D( printf("and %2.2s, " , cp->cmd) );

l = matchstr[0];
r = (cp->cmd)[0];

if( l == r )
{
    l = matchstr[1];
    r = (cp->cmd)[1];

    if( isspace(l) )
        l = 0;
}

D( printf("returning %d\n", l - r) );
return( l - r );
}

/*-----*/
int      numarg(s, offset)
char    **s;
int      *offset;
{
    /* Get value of a numeric argument from *s. If the
     * number is followed by an i, inches are converted
     * to spaces. If the number is preceded by a '+' or
     * a '-' offset is set to 1. The argument may be an
     * expression and spaces are ignored. However the
     * argument must have been enclosed in double quotes
     * for a space to be part of the argument. S is
     * advanced past the numeric component and any
     * trailing whitespace. Return the value of the
     * argument.
     */

    int      error;
    extern int  getvar(), null();
    extern double  parse();
    double    val = 0.0;

    if( **s )
    {
        if ( **s == '+' )
        {
            *offset = 1;
            (*s)++;
        }
        else if( **s == '-' )
            *offset = 1;

        val = parse( s );
    }

    return( (int)val );
}

/*-----*/
splitfields( cur, next )
char    **cur, **next;
{
    /*
     * Split cur into two fields. Modify next to point
     * at the beginning of the second or at end of line.
     *
     * Leading and trailing white space around the first
     * field is skipped quoted arguments are recognized
     * as being a single field, even if the quoted
     * string contains whitespace.
     */

    register char  *p;
    p = *cur;
    p = skipSPACE(p, Esc);
    if( *p == '"' )
    {
        *cur = ++p;
        p = skipto('"', p, Esc);
    }
    else
    {
        *cur = p;
        p = skipto(' ', p, Esc);
    }

    if( *p )
        *p++ = '\0'; /* Terminate current field */
    p = skipSPACE( p, Esc ); /* Skip to next field */
    if( *p == '"' ) /* strip any quotes */
        *skipto('"', ++p, Esc) = 0;

    *next = p;
}

/*-----*/
command( first )
char    *first;

```

(continued on next page)

FOR THE PRO^{essional}grammer

Find out why the PROs use HIGH SCREEN™, the professional User-Interface Development Tool that goes far beyond simple screen generators like Screen Sculptor™ or Saywhat?!™ (Trade-up available).

HIGH SCREEN™ includes:

- Complete, powerful and super fast screen editor.
- Automatic field checking: variable type, range . . . Field by field or full screen option.
- Help and window management (up to 26 pop-up windows per screen). For batch files also.
- Easy Pull-down menu management.
- Extra goodies for the PRO:
 - on-line extended character set
 - scrolling within a zone
 - ability to call a screen for reference from DOS or any language editor
 - library feature to gather screens
 - Royalty free. Not copy protected.

Language independent screens: the same copy of HIGH SCREEN™ works with Basic(s), Pascal(s), C, Cobol, Fortran, dBase, Assembler, etc.

For IBM PC/XT/AT and true compatibles. DOS 2.00+. 256K RAM.

Softway, Inc.

(415) 397-4666

PC/SOFT Product Line
500 Sutter St., Suite 222
San Francisco, CA 94102

HIGH SCREEN™ is \$129 (CA res. add tax)
S&H USA \$5, CND \$10
Visa, M/C welcome. (risk-free 30 day trial)

Trademarks / Owner: Screen Sculptor / The Software Bottling Company; Saywhat?! / The Research Group; IBM PC/XT/AT / IBM Corporation; dBase / Ashton-Tate.

Circle no. 372 on reader service card.

EXIM ToolKit

BASIC Programming Support from EXIM Services

EXIM Services announces the EXIM ToolKit. A growing Library of over 65 Assembler and BASIC Programming Modules:

- | | |
|---------------------------|-----------------------|
| ■ Video/Screen Management | ■ I/O File Management |
| ■ DOS Environment Support | ■ Date Arithmetic |
| ■ Data BASE Management | ■ General Purpose |

Increase Productivity, Decrease Development Time and Add Functionality to Your Applications.

A must addition for software developers using Microsoft QuickBASIC or IBM compilers. This high quality, low cost library offers developers the advantages of power and sophistication.

Window or Frame Screens and Messages . . . Save/Restore Full or Partial Screens . . . Accelerated Screen Displays . . . Horizontal/Vertical Scroll-Full or Partial Screen . . . Display "Pop Up" Help Screens . . . Find the First/Next Directory Entry . . . Sorting . . . etc.


Easy to use, high quality, the EXIM ToolKit is being offered for only \$65.00 plus \$5.00 shipping and handling, with a full money back guarantee.

"If you are not completely satisfied, return the diskettes and documentation within 30 days of purchase for a complete refund."

Do not be left behind. Bring your applications up to date with this NO RISK offer.

No licensing or royalty fees are required to distribute applications using the EXIM ToolKit.

EXIM SERVICES OF N.A.
P. O. BOX 5417
CLINTON, NEW JERSEY 08809



(201) 735-7640

Circle no. 371 on reader service card.

INTERWORK

A Concurrent Programming Toolkit

Interwork is a "C" program library which allows you to write your programs as a set of cooperating concurrent tasks. Very useful for simulation, real-time applications, and experimentation with parallel programming.

FEATURES

- Supports a very large number of tasks (typically more than 100) limited only by available memory. Low overhead per task results in very fast context switching.
- Provides a full set of inter-task communication (ITC) facilities, including shared memory, locks, semaphores, blocking queues, and UNIX-style signals. Also has building blocks for constructing your own ITC facilities.
- Handles interrupts (DOS version) and integrates them into task scheduling. Supply your own interrupt handlers or block tasks on interrupts.
- Lets you trace task switches and inter-task communication.
- Comes with complete documentation including a user's manual and reference manual of commands.

Interwork is available for the following systems:

| Hardware | Operating System | Price |
|------------------|---------------------|-------|
| IBM PC, XT, AT | PC-DOS 2.0 or later | \$129 |
| IBM PC AT | XENIX* | \$159 |
| DEC VAX; SUN III | UNIX 4.2BSD | \$249 |

PC-DOS version is compatible with DeSmet, Lattice, and Microsoft C compilers.

Please specify hardware and operating system when ordering. Shipping and handling included; COD orders add \$2.50. Send check or money order to:



Block Island Technologies
Innovative Computer Software

13563 NW Cornell Road, Suite 230, Portland, Oregon 97229-5892
(503) 241-8971

*Trademarks: UNIX, AT&T Bell Laboratories, Inc.; XENIX, Microsoft, Inc.; VAX, Digital Equipment Corporation

Circle no. 263 on reader service card.

C CODE FOR THE PC

source code, of course

| | |
|--------------------------------|-------|
| GraphiC 3.0 hi-res color plots | \$300 |
| Panache C Program Generator | \$125 |
| QC88 C Compiler | \$90 |
| Concurrent C | \$45 |
| Coder's Prolog in C | \$45 |
| Biggerstaff's System Tools | \$40 |
| Translate Rules to C | \$30 |
| LEX | \$25 |
| YACC & PREP | \$25 |
| tiny-c interpreter & shell | \$20 |
| C Tools | \$15 |

The Austin Code Works

11100 Leafwood Lane
Austin, Texas 78750-8409
(512) 258-0785

Circle no. 250 on reader service card.

Free shipping on prepaid orders

No credit cards

Circle no. 250 on reader service card.

C CHEST

Listing Fifteen

(Listing continued, text begins on page 96.)

```

/* Process a command found in "first". Do this by finding
 * the command in Cmdtab. If the command is found then
 * the associated subroutine (in the Cmdtab) is executed.
 *
 * The calling convention depends on the command type.
 * There are 4 types:
 *
 * type 0:      .xx <optional string>
 * type 1:      .xx <number> <optional string>
 * type 2:      .xx <string> <number> [optional tail]
 * type 3:      .xx <string> <optional string>
 *
 * A <string> is passed null terminated with leading and
 * trailing white space or quotes stripped. A <number>
 * is passed as an int. An <optional string> is passed
 * without trailing white space or leading and trailing
 * quotes stripped.
 *
 * Type 0: (* action) ( str, dobreak );
 * char *str;
 *
 * Type 1: (* action) ( val, str, offset, dobreak );
 * Type 2: (* action) ( val, str, offset, dobreak, tail);
 * double val;
 * char *str;
 * char *tail;
 *
 * Type 3: (* action) ( leftstr, rightstr, dobreak );
 * char *leftstr, *rightstr;
 *
 * Note that command() will mess up the input string,
 * putting a null after the first character. If you need
 * to keep the string around for longer than one command,
 * copy it somewhere safe.
 */

```

```

extern CTAB *search(); /* routine to search for cmd */
register CTAB *cmd; /* current command */
char *second; /* points at second argument */
char *p; /* general-purpose pointer */
int val = 0; /* value of numeric argument */
int offset = 0; /* true if val is an offset */
int rval = 0; /* return value */
int dobreak; /* True if a normal Cmd char,
 * false if a nobreak command
 * char.
 */

```

```

dobreak = (*first++ == Cmd_chr);

while( *first && (*first & 0x7f) <= ' ' )
    first++;

if( !*first ) /* This is a comment line */
    return 0;

cmd = (CTAB *) bsearch(first, Cmdtab, Ctabsize,
    sizeof(CTAB), cmdcmp);

if( !cmd )
{
    /* Command isn't in the table. See if it's a
     * macro. Print an error message if it isn't.
     */
    if( !expand_macro( first ) )
        err("%2s not a command or macro\n", first);

    return 0;
}

if( Inhibit && cmd->inhib ) /* Input is inhibited. See */
    return 0; /* See doif() in nrmsc.c */
/* for details. */

offset = 0; /* advance past the actual */
first += 2; /* command. */

if( cmd->type == 0 )
{
    first = *first ? skipspace(first, Esc) : cmd->def;

    if( *first == '#' )
        *skipto('!', ++first, Esc) = 0;

    rval = ( *(cmd->action) ) ( first, dobreak );
    goto exit;
}

splitfields( &first, &second );

switch( cmd->type )
{
case 1:
    p = *first ? first : cmd->def;
    val = numarg( &p, &offset );
    rval = ( *(cmd->action) ) ( val, second, offset,
        dobreak );
    break;

case 2:
    p = *second ? second : cmd->def;

```



```

val = numarg( &p, &offset );
p = skipspace(p, Esc);
if( *p == '\n' )
    *skipto('\n', ++p, Esc) = '\0';

rval = (*(cmd->action))( val, first, offset,
                        dobreak, p );
break;

case 3:
    rval = (*(cmd->action))( *first? first: cmd->def,
                            second, dobreak );
    break;

default:
    err("*** Internal Error, bad type: %d in Cmdtab\n",
        cmd->type );
    break;
}

exit:
return( cmd->inhib ? 0: rval );
}

```

End Listing Fifteen

Listing Sixteen

```

#include <stdio.h>
#include <hash.h>
#include "nr.h"

/*-----
 * NREG.C
 *
 * Copyright (c) 1987, Allen I. Holub. All rights reserved.
 * This module holds routines for manipulating and accessing
 * number registers.
 *-----
 */

static int Regnum = 0; /* Used to print number registers */
HASH_TAB *Nregs = 0; /* Hash table that holds number
                      /* registers.
                      */

/*-----
init_nreg()
{
    extern NREG *putnreg();
    int garbage;

    Nregs = maketab( 127 );

    Nrpq = putnreg( "q", ARABIC, DEF_PAGE, 0, 1, 1);
    Nrags = putnreg( "s", READONLY, DEF_NARGS, 0, 1, 1);
    Nrlines = putnreg( "c", READONLY, DEF_INLINES, 0, 1, 1);
    Nrplace = putnreg( "d", READONLY, DEF_VERT, 0, 1, 1);
    Nrfont = putnreg( "f", READONLY, DEF_FONT, 0, 1, 1);
    Nrindent = putnreg( "i", READONLY, DEF_INDENT, 0, 1, 1);
    Nrilen = putnreg( "l", READONLY, DEF_LINLEN, 0, 1, 1);
    Nrilen = putnreg( "n", READONLY, DEF_TEXTLEN, 0, 1, 1);
    Nroffset = putnreg( "o", READONLY, DEF_OFFSET, 0, 1, 1);
    Nrplen = putnreg( "p", READONLY, DEF_PGLEN, 0, 1, 1);
    Nrtotrap = putnreg( "t", READONLY, DEF_TOTRAP, 0, 1, 1);
    Nrfill = putnreg( "u", READONLY, DEF_FILL, 0, 1, 1);
    Nrvt = putnreg( "v", READONLY, DEF_LS, 0, 1, 1);
    Nrld = putnreg( "dl", ARABIC, DEF_WIDTH, 0, 1, 1);
    Nrld = putnreg( "dn", ARABIC, DEF_HEIGHT, 0, 1, 1);
    Nrld = putnreg( "dy", ARABIC, DEF_DAY, 0, 1, 1);
    Nrld = putnreg( "h", ARABIC, 0, 0, 1, 1);
    Nrld = putnreg( "hp", ARABIC, DEF_HORIZ, 0, 1, 1);
    Nrld = putnreg( "ln", ARABIC, DEF_LINE, 0, 1, 1);
    Nrld = putnreg( "nl", READONLY, 1, 0, 1, 1);
    Nrld = putnreg( "m", ARABIC, 0, 0, 1, 1);
    Nrld = putnreg( "mo", ARABIC, DEF_MONTH, 0, 1, 1);
    Nrld = putnreg( "a", ARABIC, 0, 0, 1, 1);
    Nrld = putnreg( "wd", ARABIC, 0, 0, 1, 1);
    Nrld = putnreg( "yr", ARABIC, DEF_YEAR, 0, 1, 1);

    time( &HOUR, &MIN, &SEC, &garbage );
    date( &MONTH, &DAY, &YEAR, &WEEKDAY );
    WEEKDAY++; /* Translate 0-6 to 1-7 for compatibility */
}

/*-----
not_deletable( name )
char *name;
{
    /* Return true if name is a pre-defined but not read
     * only number register.
     */

    register int c1, c2;

    c1 = name[0];
    c2 = name[1];

    return( ( c1 == 'q' && c2 == 0 ) ||
            ( c1 == 'd' && c2 == 'h' ) ||
            ( c1 == 'd' && c2 == 'l' ) );
}

```

(continued on next page)



to C

the dBx™ translator

- dBx produces quality C direct from dBASE II or III programs.
- Move dBASE programs to UNIX or other machines.
- Improve program speed and reliability
- Support multi-user/network applications.
- With power guidebook of conversion hints.
- Includes full screen handler and uses your current C database manager.
- May be used to move existing programs or help dBASE programmers learn C easily.
- For MSDOS, PC DOS, UNIX, XENIX, Macintosh, AMIGA. (Uses ANSI.SYS driver on MSDOS, CURSES under UNIX)
- Priced from \$350, also available from distributors.

dBx is a trademark of **Desktop Ai**

1720 Post Road E., Westport, CT 06880 MCIMAIL - DESKTOPAI
Phone - 203-255-3400 Telex - 6502972226MCI

Circle no. 258 on reader service card.

Programmers: Turbocharge your productivity with PL/PC

PL/PC is a new programming language based in large part on APL (A Programming Language) with Modula-2 control structures. It offers an integrated interactive programming environment for the rapid implementation of applications.

Structured programming is supported with Modula-2 control structures, block structured declaration of subroutines and automatic paragraphing of subroutines. Multi-dimensional arrays are easily manipulated with the large set of PL/PC array operators. Fundamental data types are extended to include complex numbers and strings. A full-featured full screen text editor is included, the editor will automatically position the cursor at the point in the source code where the last compile-time or run-time error was detected. Data are edited with a spreadsheet like data editor. English keywords are used instead of APL symbols, eliminating the requirements for special keyboard, character generator and printer. DOS files can be structured to be manipulated as a single data item of any dimension or data type. Graphic applications are supported with routines to draw lines, points, polygons, circles, conic sections and manipulation of data to/from screen. Debugging facilities include tracing, stopping, single-stepping, timing and profiling.

A demonstration version is available for US\$16. The demo version comes with a reference manual and it has a limit of six global variables. The standard version is priced at US\$89 and the 8087 version at US\$159. All prices include airmail postage and handling.

PL/PC requires an IBM PC or compatibles with at least 360K of memory and DOS 2.11 or higher.

Creative Computer Software

117 York St., Sydney, NSW 2000, Australia.
Phone: (02) 261 1611 Fax: (02) 264 7161

Circle no. 348 on reader service card.

Listing Sixteen (Listing continued, text begins on page 96.)

```

    ( c1 == 'd' 44 c2 == 'y' ) ||
    ( c1 == 'h' 44 c2 == 'p' ) ||
    ( c1 == 'l' 44 c2 == 'n' ) ||
    ( c1 == 'm' 44 c2 == 'o' ) ||
    ( c1 == 'y' 44 c2 == 'r' ) );
}

/*-----*/
NREG      *putnreg(name, fmt, val, offset, create, incr_amt)
char       *name;
int        fmt, val, offset;
{
    /* Change the value of any field of a number
     * register called "name." If the number register
     * does not exist and "create" is true, then create
     * it. Offset is treated as follows:
     *
     *      offset < 0 number register not modified
     *      offset == 0 number register = val
     *      offset > 0 number register += val
     *
     * If fmt is non-zero put it into the format field,
     * else leave the nfmt field alone. Ditto with
     * incr_amt. Number registers who's format is
     * READONLY can't be modified. Return a pointer to
     * the register if it was found or created or
     * NULL if register not found and/or not created.
     */

    register NREG      *pnode;

    if ( *name == '\0' )
        return NULL;

    if ( !(pnode = (NREG *) findsym( Nregs, name )) )
    {
        if ( !create )
        {
            err("Number register doesn't exist\n");
            return NULL;
        }

        pnode = (NREG *) addsym( Nregs, name, sizeof(NREG));
        pnode->nfmt = ARABIC ;
        pnode->nval = 0 ;
        pnode->incr_amt = 1 ;
    }

    if ( pnode->nfmt == READONLY )

```

```

    {
        err("Can't modify a read/only number register\n");
        return (NREG *) 0;
    }

    if ( incr_amt )
        pnode->incr_amt = incr_amt ;

    if (fmt)
        pnode->nfmt = fmt;

    if ( offset >= 0 )
    {
        if ( offset )
            pnode->nval += val ;
        else
            pnode->nval = val ;
    }

    return(pnode);
}

/*-----*/
rm_nreg(name)
char *name;
{
    /* Remove number register "name" if it exists.
     */

    register NREG      *node;

    if ( !(node = (NREG *) findsym( Nregs, name )) )
        err("Can't find number register <%1.2s>\n", name );

    else if ( node->nfmt == READONLY || not_deletable(name) )
        err("May not delete pre-defined number register\n");

    else
        delsym( Nregs, (BUCKET *) node );
}

/*-----*/
prnt( name, p )
NREG *p;
{
    printf("%2s = %4d (format = %c, incr by %d)",
           name, p->nval, p->nfmt, p->incr_amt);
}

```

'C' THE BEST METACOMCO'S LATTICE C



**"C" COMPILER
FOR ATARI ST
and AMIGA**

Full implementation of
Kerninghan and Ritchie —
Based on Lattice's very successful
range of 8086/88 C Compilers.

—also available—

Macro Assembler - Professional development system ST - \$ 79.95
Amiga - \$ 99.95

BCPL - NEW! Full standard BCPL compiler - ST \$149.95

Lattice 'C' - The well known Lattice 'C' compiler - ST \$149.95

Cambridge Lisp - The interpreter/compiler - ST & Amiga \$199.95

MCC Pascal - Fast ISO/ANSI standard compiler - ST & Amiga \$ 99.95

Metacomco MAKE - NEW! UNIX-like MAKE utility for the ST... \$ 69.95

MENU+ - Best selling ST MENU generator \$ 29.95

Metacomco SHELL - NEW! Amiga's intelligent programming shell \$ 69.95

Metacomco TOOLKIT - Smartest tools available for the Amiga... \$ 49.95

Cambridge LISP - CPM-68K - \$295. Call for Sinclair QL products. Languages come with full documentation, libraries & screen editor. ST languages include MENU+ and provide full interfaces to GEM VDI and AES functions. Metacomco provides experienced technical support and keeps its customers informed of new products and upgrade releases.

METACOMCO

5353 #E Scotts Valley Dr.
Scotts Valley, CA 95066

Registered trademarks: Lattice - Lattice, Inc; Atari ST -
Atari; UNIX - Bell Labs; Amiga - Commodore Amiga.

Contact your local dealer or call:
Tel: (US) 800-AKA-META (CA) (408) 438-7201
BIX: mhll Compuserve: 73247.522
Add 6 1/2% tax if CA resident



Circle no. 358 on reader service card.

HELP! C

PROGRAMMERS

On-Line HELP! Function Library

HELP! is an on-line utility library that gives your software instant, context-sensitive, pop-up HELP! windows at the touch of a key. Link your C code with the HELP! library, tell HELP! which window is current, and HELP! does the rest — fast. HELP! writes directly to video memory with no flicker or snow.

HELP! Runs on PCs and compatibles, B+W or CGA. Source code is available.

HELP! Composer

Compose your HELP! windows interactively. Control HELP! window text, size, colors, position, borders, titles. The HELP! Composer runs as a standalone utility or link it along with your programs to watch each HELP! window take form against the backdrop of your own screen designs. The HELP! Composer builds an ASCII text file to describe all the HELP! windows for each application.

Complete Windows and Pop-Down Menu Library

A bonus: Use the window and pop-down menu functions from the HELP! library in your own programs. This is a complete C window package. Open and close windows, fill windows with text, scroll, select with a cursor bar, promote a window from the background, move a window.

Window Text Editor

Use the full-featured, window-oriented HELP! Text Editor to collect text data into your application. Open a window and call the editor.

HELP! links with programs compiled by most MS-DOS C compilers: Aztec, C—C86, Datalight, DeSmet, Eco—C88, High C, Lattice, Lets C, Microsoft, Whitesmiths, Wizard. Most memory models are supported. The HELP! distribution package includes libraries, a C demo program, and a complete Programmer's Manual.

HELP! \$49. HELP! with Source Code: \$149. Demo diskette: \$10, deducted from your order. Specify compiler. MasterCard and VISA are accepted. (FL residents add 5% sales tax.)

C SOFTWARE TOOLSET

2983 Newfound Harbor Drive — Merritt Island, FL 32952 — (305) 453-0257

Circle no. 235 on reader service card.


```

    printf( (++Regnum % 2) ? "\t\t" : "\r\n" );
}

pr_nregs()
{
    /* Print out the values of all the number registers
    */

    Regnum = 0;
    ptab( Nregs, prnt );
    printf("\r\nThere are %d number registers\r\n", Regnum);
}

/*-----*/

int      nrtoi( p, fmt )
char     *p ;
int      *fmt ;
{
    /* Return the value of the number reg. variable
    * whose name is in string. Fmt is modified to be
    * the contents of the registers format field.
    * If *p is a +, the number register is
    * auto pre-incremented, if it's a -, it's pre-
    * decremented. If it's 0, it isn't modified.
    * Non-existent number registers evaluate to 0.
    */

    int     rval = 0 ;
    int     i = 0 ;
    NREG    *node ;

    *fmt = ARABIC; /* Default error return values */

    if( !*p )

        err("Missing number register name\n");
    else
    {
        if( *p == '-' || *p == '+' )
            i = (*p++ == '+') ? 1 : -1 ;

        if( node = (NREG *) findsym(Nregs, p) )
        {
            *fmt = node->nfmt ;
            node->nval += ( node->incr_amt * i );
            rval = node->nval ;
        }
    }

    return( rval );
}

```

End Listing Sixteen

Listing Seventeen

```

/* NRGLBLS.C: Global variables used by several modules
 *
 * Copyright (c) 1987, Allen I. Holub.
 * Global variables used by the various nroff routines
 */

#include <stdio.h>
#include "nr.h"

/*-----*/

/* Nodes for pre-defined number registers

*/

NREG    *Nrpg ;
NREG    *Nrargs ;
NREG    *Nrlines ;
NREG    *Nrplace ;
NREG    *Nrfont ;
NREG    *Nrindent ;
NREG    *Nrllen ;
NREG    *Nrilen ;
NREG    *Nrtoffset ;
NREG    *Nrtoplen ;
NREG    *Nrtotrap ;
NREG    *Nrfill ;
NREG    *Nrdbl ;
NREG    *Nrld ;
NREG    *Nrldy ;
NREG    *Nrhp ;
NREG    *Nrln ;
NREG    *Nrmo ;
NREG    *Nrnl ;
NREG    *Nrly ;
NREG    *Nrdrw ;
NREG    *Nrhr ;
NREG    *Nrzm ;
NREG    *Nrsc ;
NREG    *Nrvc ;

/*-----*/

/* Tabstop is an array of tabstops, indexed by column number.
 * 0 means no tab stop in that column, 'R' means right
 * adjusting, 'L' is left adjusting, 'C' is centering. Tab
 * positions are all increments of spaces from the left
 * margin. The leftmost column is column 1. tabs are set
 * and cleared by tabset() and tabclr() (in nrmsc.c). They
 * are used in nrtext.c
 */

```

(continued on next page)

Ever Program On A Silver Platter??

How much would you expect to pay for a 32 bit MC 68000 computer that's a mainframe condensed down into a keyboard? How about \$177.00!!!!? If it makes you feel any better simply add a zero to the price when you order! But that's actually our price!!! The most powerful computer money can ever buy is now the most inexpensive computer money can buy!!! So don't buy the name! Buy the power!! The power is **not** in the name!

If **you** had the opportunity to work amongst Machine Code ROM Designers, VAX & UNIX wizards in a research laboratory, designing an MC 68000 based computer that's 2nd to none. . .

What would you come up with?? And what would you call it??

Well It's Already Been Done!!

They Called It The QL For The Quantum Leap It Is!!

Absolutely a Quantum Leap beyond what you know & use - and it's truly like Programming on a Silver Platter!!

The QL Desktop Minicomputer: Designed by SRL Labs, manufactured by Samsung. A total Quantum Leap beyond all the rest! Virtual Memory, Multitasking Job Control, Multiuser Networking, Drives in Cache Memory, with Automatic Directories & File Names up to 36 characters! Everything is built into ROM! QDOS, Networking, 32 Bit SuperBasic: a totally concurrent non-destructive environment. Unlimited quantities & lengths of: Variables, Program Lines, CONsoles & Buffers. Dynamic RAM Disk-ing! Even a System Variables Brain Page Screen! Built-in DCE & DTE Serial Ports.

Imagine a 32 bit SuperBasic structured like Turbo Pascal, always there with QDOS in a UNIX-like multitasking job controlled environment with access to 32768 fully channelled windows, devices & files by EACH job! 3 Major Compilers exist for SuperBasic source alone! TURBO, SUPERCHARGE, LIBERATOR. Also runs "C", Pro Pascal, Pro Fortran 77, LISP, BCPL, 68000 Assemblers, JCL, APL, Forth-83, 65C02 or 8088 Cross Assembly. Generate native 68000 code. Compile SuperBasic source code or ANY other language and then multitask and control it in QDOS or even with SuperBasic in the Interpreter! The list of ALL the Superior Features would fill this entire journal!

Assembled QL comes WITH Integrated WP, SS, DB & Presentation Graphics Program Package by PSION! Also available in a built, final assembly KIT Form for another \$25.00 LESS!!! PLUS: FREEWARE Demos & Utilities with all purchases!

Call: (201) 328-8846

QLine BBS: 328-2919


Technical Info & Assistance - -

Our Phones are Manned 24 Hours a Day

Lot Purchases Available. We Direct Distribute.

Quantum Computing, Box 1280, Dover, NJ 07801

Circle no. 144 on reader service card.



No minimum order
Please call for current prices because prices are subject to change. Shipping & insurance extra \$1.00 for packing materials. **Orders received by 9 PM CST can usually be delivered the next morning, via Federal Express Standard Air (at \$6.00, or Priority One (at \$13.00!**

Listing Eighteen

```

/*-----
 * NRINP.C: Input and escape sequence processing. Also
 * contains process(), the highest level input
 * processing routine.
 *
 * (c) 1987, Allen I. Holub, All rights reserved
 *-----*/

#include <stdio.h>
#include <ctype.h>
#include "nr.h"

#define ishex(c) (('0' <= (c) && (c) <= '9') || \
                ('A' <= (c) && (c) <= 'F'))

#define tohex(c) (('0' <= (c) && (c) <= '9') ? (c) - '0' \
                : ((c) - 'A') + 0x0a)

/*-----
 * Used by escape to tell
 * process to abort the
 * current process.
 *-----*/
static int Abort_process = 0;

/* Used by chfont() */
static int New_font = 0;

extern char *expandstr(char*, char*, int); /* nrmac.c */
extern char *cpy( char*, char* ); /* tools.lib */
/*-----*/

gnum( inp, ifile, nextc )
int (*inp)(), *nextc ;
FILE *ifile;
{
    /* Get a decimal number from input, the number can be
     * given explicitly or as a number register
     * (ie. \ln(xx- is legal, it will draw as many '-'s
     * as are specified in the \n(xx number register. The
     * number is returned and *c is modified to hold the
     * first nondigit.
     */

    int c, i, sign = 1 ;
    UCHAR name[4];

    if( (c = (*inp)(ifile)) == Esc )
    {
        if( (c = (*inp)(ifile)) == 'n' )
        {
            gname( name, inp, ifile, 1 );
            i = nrtol( name, &c );
            c = (*inp)(ifile) ;
        }
        else
            err("Must use number or number register\n");
    }
    else
    {
        if( c == '-' )
        {
            sign = -1 ;
            c = (*inp)(ifile);
        }
        else if ( c == '+' )
            c = (*inp)(ifile);

        for( i = 0 ; isdigit(c) ; c = (*inp)(ifile) )
        {
            i = (i * 10) + (c - '0') ;
        }

        *nextc = c;
        return i * sign ;
    }
}

/*-----
gname( name, inp, ifile, nreg )
char *name;
int (*inp)();
FILE *ifile;
{
    /* Get a string or number register name from inp and
     * put it into name. In the case of an autoincrement
     * ( \n- (xx for example ), a leading - or + is put
     * into the name too.
     */

    register int c;

    c = (*inp)(ifile) ;

    if( nreg && (c == '+' || c == '-') )
    {
        *name++ = c ;
        c = (*inp)(ifile) ;
    }

    if( c == '(' )
    {
        *name++ = (*inp)(ifile);
        *name++ = (*inp)(ifile);
    }
}

```

(continued on next page)

QuickBASIC just got quicker with QuickPak

QuickPak is a superb collection of enhancements, subroutines, and instructional material designed to help you get the most out of programming in BASIC.

- Powerful assembly language routines to give your programs more speed, more power, and full access to DOS and BIOS services. SORT all or part of a string array with one command! Complete windowing capability — display help screens instantly, overlay text. FIND any string or sub-string within an entire array regardless of capitalization — accepts wildcards. READ directories into your programs from any drive or path. READ/WRITE disk sectors — create your own DOS utilities! MANY, many more programs included.
- Professionally written QuickBASIC routines and functions. Powerful input routines for text, dates, and numbers. Menus, scroll bars, date/time functions, and much more.
- The Assembly Tutor — a complete guide to learning assembly language from a BASIC perspective. Learn how to create your own routines and extensions.
- Tips and Tricks book — packed with clever ideas and techniques to help you be a better programmer.

You get all this, all of the source code for every program included, and a thirty-day money back guarantee for only \$69.00.

No royalties are required for using any of the QuickPak routines in your programs. Not copy protected, of course.




by

CRESCENT SOFTWARE

64 Fort Point Street, East Norwalk, CT 06855
(203) 846-2500

QuickPak requires Microsoft QuickBASIC or BASCOM, DOS 2.0 or higher. Visa, M/C, C.O.D., or checks accepted.

Circle no. 379 on reader service card.



Megamax C

for the

Atari ST

"Don't even think about another C compiler" Antic Sept. '86

and Introducing:

Mac-to-GS C & Mac-to-GS Pascal

Macintosh to Apple IIGS cross compilers. The fastest development systems for the IIGS.

Megamax Development Systems

Box 851521 • Richardson, TX 75085
(214) 987-4931 • Telex 5106018356

Circle no. 352 on reader service card.

Listing Eighteen (Listing continued, text begins on page 96.)

```

    }
    else
        *name++ = c ;
    *name = 0 ;
}

/*-----*/
#define get_quote(str) if( (*inp)(ifile) != '\'' ) \
    { \
        err("Missing quote in %s\n", str ); \
        break; \
    } \
    else

/*-----*/

int escape( tstart, target, copymode, inp, ifile, maxch)
UCHAR *tstart, **target;
int (*inp)();
FILE *ifile;
{
    /* {
    * Expand escape sequences, using inp() to get
    * additional input when required. Expand at most maxch
    * characters. Target is modified to point past the
    * expanded string. The input character following the
    * escape sequence is returned.
    *
    * Tstart is the array into which characters go. *target
    * is the current location in that array. The input
    * character following the escape sequence is returned.
    *
    * Note that the string "\t" will actually put a tab
    * character (unexpanded) into the input stream. An ASCII
    * 'I' or a 'T', will have been expanded by getline().
    *
    * Copy mode is a subset of normal mode used for macro
    * definitions. In normal copy mode (Nr_cpmode == 0) the
    * only recognized escape sequences are "\n" and
    * "\newline". Other sequences are just copied to the
    * target string. In nroff-compatible copy mode
    * (Nr_cpmode != 0), the following are recognized:
    *
    * \. \[ \& \$ \n \r \<newline>
    *
    * Nested \* expansions are supported and the strings
    * can contain other escape sequences (like \nx). Note
    * that nesting is handled recursively in that
    * expandstr(), called below, will call escape() to
    * expand internal escape sequences. For reasons of
    * nroff compatibility \[ is mapped to .[ and \] will
    * cause process() to terminate immediately after doing
    * the line on which the \] was found, as if it had
    * seen a .)
    */

    register int i; /* temporary */
    int c; /* current input character */
    int j; /* temporary */
    int linechar; /* line-drawing character */
    UCHAR *bp; /* general-purpose pointer */
    UCHAR *dest; /* pointer to target array */
    UCHAR name[8]; /* string or number reg name */
    static UCHAR temp[80]; /* buffer used by itoascii() */
    /* to translate number */

#ifdef DEBUG
    printf("escape:targ=0x%x, cpmode=%d, inp=0x%x, maxch=%d",
        target, copymode, inp, maxch);
    printf("\nescape: macv = 0x%x\n", Macv);
    for( i=0; Macv[i] != 0; i++)
        printf("escape: %2d: <%2.2s>\n", i, Macv[i]);
#endif

    dest = *target;

    /* Cases in the following switch are expanded whether
    * or not we're in copy mode. "c" holds the character
    * following the escape character.
    */

    switch( c = (*inp)(ifile) )
    {
        case '\n':
            /* Throw away input up to the newline or end of
            * file. Then delete all white space preceding the
            * comment. Use "goto exit" in order to avoid
            * getting another input character.
            */

            while( (c = (*inp)(ifile)) != '\n' && c != EOF )
                ;

            while( /*--dest == ' ' || *dest == '\t' */
                if( dest < tstart )
                    break;
                ++dest ;
            goto exit ;

        case '\n': /* line continuation, just eat the \n */
            goto newchar;

        default:
            if( copymode && !Nr_cpmode )
                /* In non-nroff copy mode, only \" and \<CR>
                * are recognized. Everything else goes
                * through to the output.
                */

                *dest++ = Esc ;
                *dest++ = c ;
                goto newchar;

            /* Cases in the following switch are expanded either in
            * nroff-compatible copy mode or when not in copy mode
            * of any sort (because of the goto branch in the default
            * case of the previous switch()). They are not expanded
            * in normal copy mode.
            */

            switch( c )
            {
                case '.':
                case '!':

                    *dest++ = LITCHAR ;
                    *dest++ = c;
                    HORIZ++;
                    goto newchar;

                case '$': /* \SN 1 <= N <= 9 */

                    /* Expand macro arguments. The leftmost one is in
                    * Macv[0] but, for nroff compatibility we access
                    * it as $1. $0 can not be accessed.
                    */

                    if( !Macv )
                    {
                        err("\$<num> can only be used in a macro\n");
                        goto newchar;
                    }

                    if( (i = (*inp)(ifile) - '0') < 1 || i > 9 )
                    {
                        err("\$n: invalid number, 1 <= n <= 9\n");
                        goto newchar;
                    }

                    for( bp = Macv[i-1]; *bp && --maxch >= 0; )
                    {
                        HORIZ++;
                        *dest++ = *bp++;
                    }
                    goto newchar;

                case 'n': /* \nx or \n(xx */

                    gname( name, inp, ifile, 1 );
                    i = nrtoi( name, &j );

                    if( j == READONLY )
                        j = ARABIC;

                    i = itoascii(temp, j, i);

                    if( maxch < i )
                        err("Buffer too small to expand register\n");
                    else
                    {
                        dest = cpy( dest, temp );
                        HORIZ += i;
                    }
                    goto newchar;

                case '*': /* \*(xx or \*x */

                    gname( name, inp, ifile, 0 );
                    bp = dest ;
                    dest = expandstr( name, dest, maxch );
                    HORIZ += dest - bp ;
                    goto newchar;

                default:

                    if( copymode ) /* We're in nroff-compatible */
                    { /* copy mode */
                        if( c != Esc )
                            *dest++ = Esc ;

                        *dest++ = c ;
                        goto newchar;
                    }
                    break;
            }

            /* Cases in the following switch are expanded only
            * when we're not in copy mode of any sort.
            */

            switch( c )
            {
                case ' ': *dest++ = UP_SPACE; HORIZ++; break;
                case '0': *dest++ = 'T'; HORIZ++; break;
                case '|': /* ignored */ break;
                case '^': /* ignored */ break;
            }

```

(continued on page 68)

ON COMMAND:

Writing a Unix-Like Shell for MS-DOS by Allen Holub

This book and ready-to-use program demonstrate how to write a Unix-like shell for MS-DOS. *On Command* includes an enhanced, working version of Holub's popular Unix-like shell, along with a detailed description of the Shell and complete C source code. The techniques you'll learn are applicable not only to MS-DOS, but to most other programming environments as well.

You'll find how to do interpretive control flow, a thorough discussion of low-level DOS interfacing and significant examples of C programming at the system level.

The Shell's supported features include: read, editing, aliases, history, redirection and pipes, Unix-like command syntax, DOS-compatible prompt support, and C Shell-based shell scripts. (A new Shell variable expands to the contents of a file so a program can produce text that is used by Shell scripts.) The Unix-like control flow includes: if/then/else; while; foreach; switch/case; break; continue.

The ready-to-use program and all C source code are included on disk. The Shell works on IBM PC's and compatibles.

/UTIL

When used with the shell, this collection of utility programs and subroutines provide you with a fully functional subset of the Unix environment! Utilities include: cat; cp; date; du; echo; grep; ls; mkdir; mv; p; pause; printevn; rm; rmdir; sub; and chmod. Complete source code and manual are included.

Receive On Command and /UTIL for only \$59.95!

TO ORDER: Return this coupon with your payment to: M&T Books, 501 Galveston Dr., Redwood City, CA 94063. Or, call **TOLL-FREE 800-533-4372** Mon.-Fri 8 a.m.-5 p.m. In CA call 800-356-2002.

YES! Please send me **On Command:**
writing a Unix-like Shell for MD-DOS
with disk for \$39.95 _____

Send me **/UTIL** for \$29.95 _____

Send me both **On Command** and **/UTIL**
for only \$59.95 _____

Subtotal _____

CA residents add sales tax _____ % _____

Add \$2.25 per item for shipping _____

TOTAL _____

Name _____

Address _____

City _____

State _____ Zip _____

☐ Check enclosed. Make payable to M&T Publishing.
Please Charge my ☐ VISA ☐ M/C ☐ AMEX

Card No. _____

Exp. Date _____

Signature _____

3125D

SquishTM

The Answer to sprawling files and vanishing disk space

Short on disk space?

Your remedy is **Squish**, a unique 40K resident program.

Squish compresses large databases up to **90%**!

Text files, spreadsheets, etc. by up to 60%.

Now for the best part...

Your other software (dBASE III, R:BASE, etc.)

can read or even update "squished files"

while the files stay compressed on disk...

without doing anything to your other software!



For information to order:

Sundog Software Corporation

264 Court Street, Brooklyn, NY 11231, (718) 855-9141

Trademarks/Owners: dBASE III/Ashton-Tate, Inc.; R:BASE/Microim, Inc.

\$79

+ \$5.00 S/H

30-day money-back guarantee

so you have nothing to lose

and a lot of free disk space to gain!

PC, XT, AT, 100% compatibles.

DOS 2.0 or above.

Circle no. 374 on reader service card.

FULL AT&T C++ for half the price of our competitors!

Guidelines announces its port of **version 1.1** of AT&T's C++ translator. As an object-oriented language, C++ includes: classes, inheritance, member functions, constructors and destructors, data hiding, and data abstraction. 'Object-oriented' means that C++ code is more readable, more reliable and more reusable. And that means faster development, easier maintenance, and the ability to handle more complex projects. C++ is **Bell Labs' answer to Ada and Modula 2**. C++ will more than pay for itself in saved development time on your next project.

C++

from GUIDELINES for the IBM PC: \$195

Requires IBM PC/XT/AT or compatible with 640K and a hard disk.

Note: C++ is a *translator*, and requires the use of Microsoft C 3.0 or later.

Here is what you get for \$195:

- The full AT&T v1.1 C++ translator.
- Libraries for stream I/O and complex math.
- "The C++ Programming Language", the definitive 327-page tutorial and description by Bjarne Stroustrup, designer of C++.
- Sample programs written in C++.
- Installation guide and documentation.
- 30 day money back guarantee.

To order:

send check or money order to:

GUIDELINES SOFTWARE
P.O. Box 749
Orinda, CA 94563

To order with Visa or MC,
phone (415) 254-9393.
(CA residents add 6% tax.)

C++ is ported to the PC by Guidelines under license from AT&T.

Call or write for a free C++ information package.

Circle no. 351 on reader service card.

Listing Eighteen (Listing continued, text begins on page 96.)

```

case 'N' : *dest++ = '\n';          break;
case '-' : *dest++ = '-';          break;
case 'g' : *dest++ = LITCHAR;      break;
case 'z' : *dest++ = ZWIDTH;       break;

case 't' : *dest++ = LITCHAR; /*fall through*/
case 'T' : *dest++ = '\t';        break;

case 'a' : *dest++ = LITCHAR; /*fall through*/
case 'A' : *dest++ = SOH;         break;

case 'o' : /* superimpose \o'abcd' */

    get_quote("\o");
    while((c = (*inp)(ifile)) != '\0' && maxch > 4)
    {
        maxch -- 2;
        *dest++ = ZWIDTH;
        *dest++ = (c != Esc) ? c : (*inp)(ifile);
    }

    *dest++ = HMOVE;
    *dest++ = Hs_amt;
    break;

    HORIZ++;

case 'x' : /* \x<2-hex-digits */

    c = (*inp)(ifile); /* c = MS digit */
    i = (*inp)(ifile); /* i = LS digit */
    c = toupper(c);
    i = toupper(i);

    if( !ishex(c) || !ishex(i) )
        err("\x must be followed by two hex digits\n");
    else
    {
        /* \xNN takes up space. If you need to have
        * a zero width escape sequence get to the
        * output in right-adjusted text, use the
        * .ou command or \fx mechanism.
        */

        *dest++ = (tohex(c) << 4) | tohex(i);
        HORIZ++;
    }
    break;

case '[' :

    *dest++ = '[';
    *dest++ = '[';
    HORIZ += 2;

    if( c = (*inp)(ifile) == Esc )
        c = (*inp)(ifile);

    goto exit;

case ']' :

    /* Setting Abort_process to nonzero forces
    * process() to terminate AFTER processing the
    * current line. It has the same effect as a .}
    * command at the beginning of the next line.
    * All text following the \{ on the line is
    * discarded.
    */

    Abort_process = 1;

    while( (c = (*inp)(ifile)) != '\n' && c != EOF )
        ;

    goto exit;

case 'e' : /* \e printable version of the */

    *dest++ = LITCHAR; /* current escape character */
    *dest++ = Esc;
    HORIZ++;
    break;

case 'f' : /* Change font \f(RBIOPx) */

    if( maxch < 2 )
    {
        err("No room in input buffer\n");
        break;
    }

    switch( c = (*inp)(ifile) )
    {
        case BOLD:
        case ITALICS:
        case OVER: *dest++ = CH_ATTRIB; break;
        default: *dest++ = CH_FONT; break;
    }

    *dest++ = c;
    break;

case 'r' : /* up 1 line */
case 'u' : /* up 1/2 line */
case 'd' : /* down 1/2 line */

    if( maxch > 2 )
    {
        *dest++ = VMOVE;
        *dest++ = ( c == 'r' ) ? -Vs_amt :
        ( c == 'u' ) ? -max( Vs_amt/2, 1 ) :
        /* c == 'd' */ max( Vs_amt/2, 1 );
    }
    break;

case 'h' : /* \h'N' \h'Nu' Horizontal motion */
case 'v' : /* \v'N' \v'Nu' vertical motion */

    if( maxch < 2 )
        break;

    get_quote("\v or \h");

    *dest++ = (c == 'v') ? VMOVE : HMOVE;
    j = c;
    i = gnum(inp, ifile, &c);

    if( c != 'u' )
        *dest++ = i * ((j == 'v') ? Vs_amt : Hs_amt);
    else
    {
        *dest++ = i;
        get_quote("\v or \h");
    }

    break;

case 'l' : /* horizontal line \l'Nc' */
case 'L' : /* vertical line \L'Nc' */

    /* Note that you can't use an escape sequence for
    * the line character (as in \l'10\x85'). You can
    * say:
    * .ds li \l'10\x85'
    * \{li
    * however.
    */

    get_quote("\l'Nc' or \L'Nc'");

    j = (c == 'l'); /* j = 1 if horizontal */
    i = gnum(inp, ifile, &c); /* i = N in \L'Nc' */

    if( c == '\0' )
        linechar = j ? '_' : '|';
    else
    {
        linechar = c;
        get_quote("\l or \L");
    }

    while( --i >= 0 && --maxch > 4 )
    {
        if( !j )
            *dest++ = ZWIDTH;

        *dest++ = linechar;

        if( !j )
        {
            *dest++ = VMOVE;
            *dest++ = Vs_amt;
        }
    }

    if( maxch < 0 )
        err("line drawn by \l or \L is too long\n");

    break;

default :

    if( c == Hyphen_chr ) /* \& */
        *dest++ = SOFT_HYPHEN;
    else
        *dest++ = c; /* \<any char> */

    HORIZ++;
    break;
}

newchar:
c = (*inp)( ifile );
exit:
*target = dest;
return( c );
}

/*-----
 * Sgetc() is used to process a mode 2 process() call.
 */

sgetc(s)
    UCHAR **s;
{
    return **s ? ((*s)++) : EOF;
}

/*-----
chgfont( c )
{
    /* If New_font is non-zero a font-change

```

(continued on page 72)



**The best
new programs
from one of the
best-known
publishers.**

C++

ADVANTAGE C++

- New object-oriented language lets you develop large and complex programs with greater resilience, fewer bugs.
- Write reliable, reusable code that is easier to understand and maintain.
- Fully compatible with existing C programs and tools.
- All the benefits of C without its limitations.
- Available for Lattice and Microsoft C compilers.



MULTI-TASKING

TimeSlicer

- Create multitasking and real-time applications in C now!
- No need to interface with the OS. Tasks can be created, suspended or terminated at run-time.
- Optimize processor usage and transparency.
- Create more efficient and portable programs.
- Compatible with Lattice C, Microsoft C, ADVANTAGE C++ and object-oriented programming.
- Includes header files for C and assembly language and example programs with source code.



LINKER

ADVANTAGE Link

- Fastest, most powerful PC-DOS overlay linker.
- First linker to take full advantage of EMS.
- Accepts Microsoft and Phoenix command files.
- Supports 53 commands; more than any other linker.
- Compatible with Microsoft CodeView and Pfix Plus.



C COMPILER

ADVANTAGE C

- Newest technology based on AI and advanced design.
- Unmatched execution speed.
- Productive, easy-to-manage compilation environment.
- Advanced optimization routines; implements register variables.
- Over 250 library functions; full ANSI C library.
- Supports any size memory model (S,M,L).
- Microsoft C compatibility; recompiles most applications without source code changes.



GRAPHICS

ADVANTAGE Graphics

- Complete C programming graphics library.
- Create bar and pie charts with one command.
- Automates easily.
- 10 popular font styles.
- No royalties or run-time fees.



We make the best software even better.

After 10 years of publishing software, we know what's important to you. We're committed to full service that goes beyond just selling you the best software at competitive prices. Our expert staff can help you choose the right programs and provide full technical support. Count on Lifeboat for the complete solution to all your programming needs.

Call for the latest products from:

Blaise • Computer Innovations • CompuView • Creative Programming • Cytec • DMA • Essential • FairCom • Flexus • GSS • Gimpel • Greenleaf • Informix • Lattice • Microsoft • Media Cybernetics • Morgan Computing • Opt-Tech Data • Oregon Software • Periscope • Phar Lap • Phoenix • Rational Systems • Realia • Roundhill • SoftCraft • Software Bottling • Unipress • Vermont Creative • Wizard Systems • and more

Call **1-800-847-7078**

In NY **914-332-1875**

or your local Lifeboat Authorized Dealer.

The Full-Service Source for Programming Software.

LIFEBOAT

**55 South Broadway
Tarrytown, NY 10591
Telex #510-601-7602**

INTERNATIONAL SALES OFFICES

Australia/New Zealand:
Charlton Distributors
Phone: (64) (09) 766-361
Canada: Scantel Systems
Phone: (416) 449-9252

England: Grey Matter, Ltd.
Phone: (44) 364-53499
System Science, Ltd.
Phone: (44) (01) 248-0962
France: Compusol
Phone: (45) 30.07.37

Italy: Lifeboat Associates Italia
Phone: (02) 464601
Japan: Lifeboat, Inc.
Phone: (03) 293-4711
Spain: Micronet, S.A.
Phone: (34) 1-262-3304

The Netherlands: SCOS
Automation BV
Phone: (31) 20-10 69 22
West Germany: MEMA
Computer GmbH
Phone: (69) 34-7226
Omnitex
Phone: (76) 23-61820

The fastest, tightest code.



(Though the same can hardly be said of the name.)

We have to tell you, we had a hard time getting the name down this short.

Because Microsoft's new FORTRAN Compiler actually has a far longer list of features.

It uses the same optimizer and code generator technology that made our C Compiler the industry leader.

And we've added special loop optimizations that give you the

smallest, fastest FORTRAN code a PC can handle.

"Now Microsoft's FORTRAN Optimizing Compiler generates such fast code that an IBM PC/XT approaches the speed of the VAX."

Peter Osgood, MIT, Project Athena, Director of the Real Time Lab Project.

This compiler has already passed the toughest test there is. It's been

Microsoft FORTRAN Optimizing Compiler Version 4.0.

- ◆ Full ANSI FORTRAN 77 Compiler with Fastest Executable Code for MS-DOS. NEW!
 - ◆ Uses the Microsoft C optimizing technology, plus loop optimization. NEW!
- | Execution Speed
(in Seconds) | Microsoft
FORTRAN
v. 4.0 | Ryan-McFarland
FORTRAN
v. 2.11 | IBM Professional
FORTRAN
v. 1.22 |
|---------------------------------|--------------------------------|--------------------------------------|--|
| Sieve | 7.97 | 9.33 | 38.51 |
| Whetstone | 53.82 | 58.67 | 79.04 |
| Lookup | 5.82 | 18.61 | 26.02 |
- ◆ Fully GSA certified for ANSI 77 compatibility with no errors at the highest level. NEW!

- ◆ Numerous IBM VS and DEC VAX extensions. NEW!
- ◆ Microsoft CodeView: Window-oriented source-level debugger. NEW!
 - Debug using your original source code, the resulting disassembly or both intermingled.
 - Watch and change the values of your local and COMMON variables as you debug.
 - Set conditional breakpoints on variables, expressions or memory; trace and single step.
 - Watch and change registers and flags as you execute.
 - Easily debug graphics oriented programs since program output is kept separate from debugger output.

ANSI-certified as Full ANSI FORTRAN 77, and 100% error-free.

"The Microsoft FORTRAN Optimizing Compiler let us port the 200,000 line Boeing Mathematical Library (BCSLIB) with virtually no changes. This ANSI FORTRAN 77 code was ported directly from Cray, CDC, DEC, IBM and other mainframes and workstations."

*Ivor Philips, Boeing Computer Services, Program Manager
Mathematical Software Libraries.*

We've also included the same advanced intrinsic math functions found on VAX® and IBM® VS systems. Add

Compiler v. 4.0 with CodeView™

improvements like our new HUGE memory model, and porting the biggest mainframe programs has never been easier.

Among the many additions we've made to our package is our exclusive CodeView™ windowing debugger. It lets you trace through programs at any level you want, from source code to assembly language.

You can open windows, and watch both variables (local and COMMON) and CPU registers change. You can set conditional breakpoints using variables and expressions.

Debugging gets even easier with the compiler's advanced diagnostics. Detailed error messages are thoroughly explained and cross-referenced in our new manuals.

Documentation that has been completely revised and expanded with tons of examples.

If we're talking your language, use one of the numbers below for more details about the Microsoft® ANSI FORTRAN 77 Optimizing Compiler

Version 4.0 with CodeView,

and the name of your nearest dealer.

(Even if the call's toll-free, it may be a good idea to refer to it as "FORTRAN 4" for short.)

Microsoft® FORTRAN

The High Performance Software.

Call (800) 426-9400. In Washington State or Alaska, (206) 882-8088. In Canada, (416) 673-7638.

Microsoft and MS-DOS are registered trademarks and CodeView is a trademark of Microsoft Corporation. IBM is a registered trademark of International Business Machines Corporation. VAX is a registered trademark of Digital Equipment Corporation.

Medium, Large and Huge Memory Model Libraries. NEW!
x models with NEAR, FAR and new HUGE pointers.
Common blocks and arrays greater than 64K.
Choose from three math libraries and generate in-line 8087/80287
instructions or floating point calls:
floating point emulator (utilizes 8087/80287 if installed)
8087/80287 coprocessor support
alternate math package—extra speed without an 8087/80287
link your FORTRAN routines with Microsoft C (v. 4.0 or higher), Microsoft
BASIC (v. 3.3 or higher) or Microsoft Macro Assembler.
Largest number of 3rd party support libraries available.

- ◆ Provides more detailed diagnostic error messages (almost twice as many as competitors) and extensive documentation with non-ANSI 77 features highlighted. NEW!
- ◆ Proven reliability—tested with over 2.5 million lines of code compiled and executed.
- ◆ MS-DOS® network support with file / record locking and sharing.
- ◆ Microsoft Program Maintenance Utility rebuilds your applications after your source files have changed. NEW!
- ◆ Other utilities including faster overlay linker (links over 1Mbyte object code), library manager, EXE file compression utility, EXE file header utility, MS-DOS environment setting utility and setup utility.

BRING YOUR HARD DISK BACK UP TO SPEED WITH H.D. TUNEUP!

The harder you work, the more files you put on your hard disk, the faster DOS works to fragment those files. Fragmented files make you wait longer for file loads and saves. **H.D. Tuneup** rearranges the data on your hard disk for the fastest possible file i/o times. Your disk will speed along like new.

"Much better than Disk Optimizer™"
- Philadelphia, PA

Requires IBM PC/XT/AT compatibility, DOS 2.x or higher and at least 196K. Hard disks up to 32mb may be tuned, along with most 5.25" diskettes.

ONLY \$39.95 + \$3.00 shipping (US/Canada)

SofCap Inc.

P.O. Box 131

Cedar Knolls, NJ 07927

Visa (201) 386-5876 MasterCard

If you want the absolute best possible performance from your hard disk:

TUNE IT UP WITH H.D. TUNEUP

Disk Optimizer is TM SoftLogic Solutions. H.D. Tuneup is TM SofCap.

Circle no. 349 on reader service card.



AUSTRALIA'S FAVORITE
C COMPILER
Now Available in the U.S.A.

THE
HI-TECH C COMPILER

Available for:
Z80, 8088/86/286, 68000
MS-DOS, CP/M, ATARI ST
Cross compilers also available.

Features:

- ★ Smallest code from ANY compiler.
- ★ Macro assembler, linker, librarian, debugger included.
- ★ Can produce ROM code.
- ★ Full library source.
- ★ Excellent diagnostics.

AND MUCH MORE -
**THIS IS A COMPLETE
PRODUCTION-QUALITY
COMPILER**

\$129
plus postage and handling

**HI-TECH
SOFTWARE**
The leading edge of Software Technology

Order from: SOFTFOCUS
1343 Stanbury Drive, Oakville
ONTARIO Canada L6L2J5
(416) 825 0903 or (416) 844 2610

JAPAN: Southern Pacific Ltd. (045) 314 9514
AUSTRALIA: Hi-Tech Software (07) 38 6971

Circle no. 376 on reader service card.

C CHEST

Listing Eighteen

(Listing continued, text begins on page 96.)

```

* request is appended to the front of the
* next input line. Chgfont() is called
* from the routine that processes the .ft
* request [ ft() in nrprocs.c ] and also
* when an environment is restored (by
* pop_env() in nrmac.c).
*/

New_font = c;

}

/*-----*/

int  getline(target, copymode, inp)
int  (*inp)();
UCHAR *target;
{
    /* Get an input line & put it into target. Get at most
    * MAXSTR characters. The input file, ifile, is either
    * an input file or an input macro depending on the
    * state of the global ismacro. Return 1 on success
    * or 0 on end of file. Lines ending with <Esc><newline>
    * are continued to the next line, otherwise newline
    * terminates the line. The newline character is not
    * put into the string. Tabs (^I) are expanded to a
    * sequence of spaces (^t is expanded into a ^I by
    * escape(). This ^I will be processed by in the text()
    * module. Trailing white space is stripped from the line.
    *
    * Copymode is just passed through to escape() (which
    * expands escape sequences).
    */

    register UCHAR *rp ;
    register int  c ;
    UCHAR *p ;

    if( Quit ) /* Quit is set by the .ex command */
        return 0; /* pretend we've seen end of file */

    INLINES++ ; /* Increment number of input lines */

    p = target ;
    c = (*inp)(ifile);

    while( (p - target) < MAXSTR )
    {
        if( c == '\n' || c == EOF )
            break;

        if( c != Esc )
        {
            *p++ = c ;
            c = ( *inp )( ifile ) ;
        }
        else
            c = escape(target, &p, copymode, inp, ifile,
                        MAXSTR - (p-target));
    }

    *p = 0;

    if( Tabs enabled ) /* Expand tabs and leaders */
        Datab( target );

    if( New_font && !ISCMD(*target) )
    {
        /* This is a kludge but it's the most convenient
        * way to get a font change into the input stream
        * at the correct place. We can't just change
        * fonts when the .ft is executed because we
        * might be filling and .ft doesn't cause a break
        */

        memcpy( target+2, target, (p-target) + 1 );
        switch(New_font)
        {
            case PREVIOUS:
            case BOLD:
            case ITALICS:
                target[0] = CH_ATTRIB;
                break;

            default:
                target[0] = CH_FONT;
                break;
        }

        target[1] = New_font ;
        New_font = 0;
    }

    return( !(c == EOF && p == target) );
}


/*-----*/

process( nifile, nifilename, mode, nmacy ) /*
FILE *nifile ; /* Input file descriptor */
char *nifilename ; /* Name of input file */
int mode; /* processing mode (see below) */
char **nmacy ; /* Macro arguments */
{
    /* This routine actually does the processing of a file
    * or a macro. It is a 2nd order recursive routine. That
    * is process() is called recursively every time the
    * input is changed (by a .so command, a macro expansion,
    * etc.). Macy is an argv-like array of arguments to
    * macros. Ifile is a pointer to either a FILE or to a
    */
}

```

(continued on page 74)

Unleash The Most Powerful Development Tools On The Planet DOS.



UNIFY DBMS/DOS. The UNIX World Leader Brings A New Dimension To DOS Application Development.

What happens as the DOS world expands? As a new generation of hardware takes over? As networking becomes more important? The potential is enormous. But until now, the tools to achieve it have been limited.

Now a leader from another world unleashes that potential: UNIFY® DBMS. The leading relational DBMS in the UNIX™ world. And now, the most advanced set of application development tools in the DOS world.

With UNIFY DBMS, DOS developers have new power to build more sophisticated applications than ever before possible.

The power to write high performance "C" programs that will access the data base, using Unify's Direct Host Language Interface.

The power of an industry standard query language—SQL.

The power of unmatched speed in production applications. Only UNIFY DBMS is specifically engineered for transaction throughput. With unique performance features like PathFinder™ Architecture multiple access methods, for the fastest possible data base access.



The power of comprehensive program development and screen management tools. Plus a state-of-the-art fourth generation report-writer.

What's more, with UNIFY DBMS, the potential of networked applications becomes a reality. Unlike DBMS systems which were originally single-user (and which have a long stretch to accommodate more users), UNIFY DBMS is a *proven* multi-user system.

And because UNIFY DBMS/DOS is the best of two worlds, it offers you the most powerful benefit of all: DBMS applications that can grow as your needs grow. From single user DOS. To networked DOS. To multi-user UNIX. All without changing your applications.

Call the Unify Information Hotline for our free booklet: The New DOS World. (503) 635-7777



UNIFY
CORPORATION

4000 Kruse Way Place
Lake Oswego, OR 97034

Modula-2

IBM PC/DOS

Native Code Compiler

This is a full implementation of Niklaus Wirth's Modula-2 language. Our product is not an interpreter, but a true 8086 compiler, using state-of-the art techniques. A Unix-like "make" utility is included which provides automatic recompilation of modified source programs.

The code generator produces object module input for the DOS link utility. You may combine your Modula-2 programs with code from other languages such as Assembler. The software also operates on PC compatibles using MS/DOS. All the run time source code is included. None of the software is copy protected, and is fully supported and maintained by farbware. No royalties are charged for the use of the run time object. A complete and comprehensive reference manual is included in the purchase price. The manual is available separately for \$25.00.

Site licenses and quantity discounts are available.

\$89.95 Complete

farbware
1329 Gregory
Wilmette, IL 60091
(312) 251-5310

Master Card and Visa Accepted

Circle no. 340 on reader service card.

A PROGRAMMER'S TOOL BOX

SCREEN MASTER

ONLY
\$99⁹⁵

A DP MANAGER'S
BEST FRIEND

PURE GENIUS IS NOT ENOUGH
(YOU STILL NEED THE RIGHT TOOLS)

- DESIGN MENUS
- CREATE PROTOTYPES
- CREATE TUTORIALS
- CAPTURE SCREENS
- CREATE DEMOS
- RUN TIME MODULE

ENHANCE HIGH LEVEL LANGUAGES WITH FULL
ACCESS TO ALL CAPABILITIES IN YOUR OWN CODE

"source code was reduced by one third..."

"15 minutes to design a sophisticated screen..."

Scott McCaffrey, Musco of PA

"In a word, fantastic..."

"...I just returned my copy of Dan Bricklin's

Demo Program." Thomas Emr, Dir. of Marketing - ADP Inc.

GENESIS
DATA SYSTEMS

5403 Jonestown Rd., Harrisburg, PA 17112
(717) 652-1200

Circle no. 373 on reader service card.

C CHEST

Listing Eighteen

(Listing continued, text begins on page 96.)

```

* macro descriptor returned by mopen() (in nrmac.c)
* according to the state of mode. The following modes
* are recognized
*
* 0 Input is from a file or stream and Ifile is
*   a FILE pointer.
* 1 Input is from a macro and Ifile is a macro
*   pointer returned from mopen()
* 2 Input is from a string and Ifile is a pointer
*   to that string. Note that mode two commands
*   are processed with the current file (ie.
*   ifile, nifilename and nmacv are ignored).
*
* Process returns immediately if command() returns true.
*
* This routine is extremely recursive. Be careful with
* static variables (ie. don't use them).
*/

UCHAR line [MAXSTR] ;
UCHAR *oiname, **omacv ;
int oinlines, oismacro ;
FILE *oifile ;
int oinhibit ;
int mgetc(), fgetc();

#ifdef DEBUG
printf("Mode %d process call: ", mode);
printf("file <0x%x> named <%s>, macv @ 0x%x\n",
        nifile, nifilename, nmacv);

printf("%s processing started (from %s, line %d)\n",
        nifilename, Ifilename, INLINES);
#endif

oinhibit = Inhibit ;
oinlines = INLINES ; /* Save program state on */
oifile = Ifile ; /* the stack */
oiname = ifilename ;
oismacro = ismacro ;
omacv = macv ;

INLINES = 0 ; /* Create new program state */
Ifile = nifile ;
Ifilename = nifilename ;
Ismacro = mode ;
Macv = nmacv ;

if (mode == 2)
{
    Ifile = (FILE *) nifile; /* Ifile is a string ptr */
    getline( line, 0, sgetc);

    if (Verbose)
        printf( "\n%s:<%s>\n", Ifilename, line );

    Inhibit = oinhibit ;
    INLINES = oinlines ;
    Ifilename = oiname ;
    Ifile = oifile ;
    Ismacro = oismacro ;
    Macv = omacv ;

    if ( ISCMD( *line ) )
        command( line );
    else
        text( line );
}
else
{
    while( getline(line, 0, Ismacro ? mgetc : fgetc) )
    {
        if (Verbose)
            printf( "\n%s:<%s>\n", Ifilename, line );

        if ( *line == FF )
            command( ".bp" );

        else if ( ! ISCMD(*line) )
            text( line );

        else if ( command(line) )
            break;

        if ( Abort_process )
        {
            Abort_process = 0;
            if ( command(".") )
                break;
        }
    }

    Inhibit = oinhibit ;
    INLINES = oinlines ;
    Ifilename = oiname ;
    Ifile = oifile ;
    Ismacro = oismacro ;
    Macv = omacv ;
}

#ifdef DEBUG
printf("%s: processing done (returning to %s, line %d)\n",
        nifilename, Ifilename, INLINES);
#endif

#endif

return 0;

```

End Listings

Unbiased Advice.

Our friendly, non-commissioned salespeople are always prepared to assist you. We also have experienced technical consultants who can answer questions, help you compare products and send you detailed product information tailored to your needs. Since we're not affiliated with any software publisher or manufacturer, we'll give you an unbiased look at the products we carry.

High Quality.

We stock hundreds of high quality software development tools specifically for IBM personal computers and compatibles. And as new products become available, we'll sell only those that meet our high standards for quality and value.

Manufacturer Support.

The products we sell are the latest versions and come with the same technical support as if buying directly from the manufacturer.

Return Guarantees.

Our goal is customer satisfaction and that's why we offer a 30-day documentation evaluation period or a 30-day return guarantee on most of our products. Please call for specific details.

Immediate Shipment.

Most products are in stock and are ready for shipment from our large inventory.

Discounts.

You'll save money on all of your software purchases from Programmer's Connection. Our ads show both the discount and retail prices for each product so you'll always know exactly how much you'll save.

FREE Shipping.

Shipping is FREE if you have your order shipped via standard UPS anywhere in the USA. We can also express your order to you with no special fees and we'll only charge you the shipping carrier's standard rate. Many other companies profit from overcharges plus special fees for express shipments.

Credit Cards.

We'll charge your credit card at the time we ship your order. Other companies may charge your credit card at the time they take your order so they can use your money interest-free while you wait for your shipment.

No Sales Tax.

Customers outside of Ohio are not charged state sales tax. Ohio residents are charged 6 percent.

No Hidden Charges.

Quite simply, the prices you see on the next two pages are all you pay. We don't charge extra for standard UPS shipping, credit cards, COD orders, purchase orders or special handling.

PROGRAMMER'S CONNECTION

When you need programmer's development tools, Programmer's Connection is your best one-stop source. We've specialized in development software for IBM personal computers since 1984 and are experienced in providing a full range of quality products and customer services.

At Programmer's Connection, you get all of the benefits of buying directly from the manufacturer and none of the drawbacks. So call us today and discover the advantages of our one-stop service for yourself. You'll be glad you did!

programmer's connection

apl language

| | | |
|---------------------------------------|-----|-----|
| APL*PLUS/PC by STSC | 595 | 429 |
| APL*PLUS/PC Spreadsheet Mgr by STSC | 195 | 139 |
| APL*PLUS/PC Tools Vol 1 by STSC | 295 | 199 |
| APL*PLUS/PC Tools Vol 2 by STSC | 85 | 59 |
| Financial/Statistical Library by STSC | 275 | 195 |
| Pocket APL by STSC | 95 | 69 |
| STATGRAPHICS by STSC | 795 | 579 |

artificial intelligence

| | | |
|--|------|------|
| 1st-CLASS by Programs in Motion | 495 | 399 |
| APT from Solution Systems | 65 | CALL |
| Arity Combination Package | 1225 | 1119 |
| Expert System Development Pkg | 295 | 259 |
| File Interchange Toolkit | 50 | 45 |
| PROLOG Compiler & Interpreter | 795 | 699 |
| Screen Design Toolkit | 50 | 45 |
| SQL Development Package | 295 | 259 |
| Arity PROLOG Interpreter | 350 | 309 |
| Arity Standard Prolog | 95 | 79 |
| AutoIntelligence by IntelligenceWare | 990 | CALL |
| ExpertEDGE Advanced by Human Edge | 2500 | CALL |
| ExpertEDGE Professional by Human Edge | 5000 | CALL |
| Expertech II by IntelligenceWare | 475 | 359 |
| EXSYS Development Software by EXSYS | 395 | 319 |
| EXSYS Runtime System | 600 | 479 |
| GCLISP Golden Common LISP by Gold Hill | 495 | CALL |
| GCLISP 286 Developer by Gold Hill | 1190 | CALL |
| Insight I by Level Five Research | 95 | 75 |
| Insight 2+ by Level Five Research | 485 | 379 |
| Intelligence/Compiler IntelligenceWare | 990 | 749 |
| Logic-Line Series 1 by Thunderstone | 90 | 85 |
| Logic-Line Series 2 by Thunderstone | 125 | 115 |
| Logic-Line Series 3 by Thunderstone | 150 | 139 |
| LPA microPROLOG All Varieties | CALL | CALL |
| Microsoft LISP Common LISP | 250 | 163 |
| MPROLOG Language Primer LOGICWARE | 50 | 45 |
| MPROLOG P500 by LOGICWARE | 495 | 395 |
| MPROLOG P550 by LOGICWARE | 220 | 175 |
| PC Scheme by Texas Instruments | 95 | 84 |
| Personal Consultant Easy by TI | 495 | 435 |
| Personal Consultant Plus by TI | 2950 | 2589 |
| Personal Consultant Runtime | 95 | 85 |
| QNIAL by NIAL Systems | 375 | 349 |
| TransLISP from Solution Systems | 95 | CALL |
| TransLISP PLUS from Solution Systems | 195 | CALL |
| Turbo PROLOG by Borland Intl | 100 | 65 |

assembly language

| | | |
|---|------|------|
| 386 ASM/LINK Cross Asm by Phar Lap | 495 | 389 |
| 8088 Assembler w/2-80 Trans by 2500 AD | 100 | 89 |
| ASMLIB Function Library by BC Assoc | 149 | 129 |
| asmTREE B-Tree Dev System by BC Assoc | 395 | 339 |
| Cross Assemblers Various by 2500 AD | CALL | CALL |
| Microsoft Macro Assembler | 150 | 95 |
| Norton Utilities by Peter Norton | 100 | 59 |
| Turbo EDITASM by Speedware | 99 | 84 |
| Uniware Cross Assemblers Various by SDS | 295 | 249 |
| Visible Computer: 8088 Software Masters | 80 | 65 |

basic language

| | | |
|--------------------------------|------|------|
| BetterBASIC by Summit Software | 200 | 119 |
| EXIM Services Toolkit by EXIM | CALL | CALL |
| Finally by Komputerwerks | 99 | 85 |
| Inside Track from Micro Help | 65 | 51 |
| MACH 2 by Micro Help | 75 | 59 |
| Microsoft QuickBASIC | 99 | 65 |
| 87 QB Pak by Hauppauge | 69 | 59 |
| Peeks 'n Pokes from MicroHelp | 45 | 37 |
| Professional BASIC by Morgan | 99 | 75 |
| 8087 Math Support | 50 | 42 |
| Stay-Res by MicroHelp | 95 | 74 |
| True Basic | 150 | 99 |
| True Basic w/Run-time | 245 | 179 |
| BASICA Converter | 50 | 45 |
| Run-time Module | 150 | 99 |
| Various Other Utilities | 50 | 45 |
| Turbo BASIC by Borland Intl | 100 | 69 |

blaise products

| | | |
|------------------------------------|-----|-----|
| ASYNCH MANAGER Specify C or Pascal | 175 | 124 |
| C TOOLS PLUS | 175 | 124 |
| EXEC Program Chainer | 95 | 75 |
| LIGHT TOOLS for Datatight C | 100 | 89 |
| PASCAL TOOLS | 125 | 99 |
| PASCAL TOOLS 2 | 100 | 79 |
| PASCAL TOOLS & PASCAL TOOLS 2 | 175 | 124 |
| RUNOFF Text Formatter | 50 | 45 |
| TURBO ASYNCH PLUS | 100 | 79 |
| TURBO POWER TOOLS PLUS | 100 | 79 |
| VIEW MANAGER Specify C or Pascal | 275 | 189 |

borland products

| | | |
|---------------------------------|-----|-----|
| EUREKA Equation Solver | 100 | 69 |
| REFLEX & REFLEX Workshop | 200 | 129 |
| REFLEX Data Base System | 150 | 89 |
| REFLEX Workshop | 70 | 45 |
| Turbo BASIC | 100 | 69 |
| Turbo DATABASE TOOLBOX | 70 | 47 |
| Turbo EDITOR TOOLBOX | 70 | 47 |
| Turbo GAMEWORKS TOOLBOX | 70 | 47 |
| Turbo GRAPHIX TOOLBOX | 70 | 47 |
| Turbo LIGHTNING | 100 | 64 |
| Turbo Numerical Methods Library | 100 | 69 |

| | | |
|---------------------------------|-----|----|
| Turbo PASCAL and TUTOR | 125 | 85 |
| Turbo PASCAL with 8087 and BCD | 100 | 64 |
| Turbo TUTOR | 40 | 28 |
| Turbo Prolog Compiler | 100 | 64 |
| Turbo Prolog Toolbox | 100 | 64 |
| Word Wizard | 70 | 47 |
| Word Wizard and Turbo Lightning | 150 | 94 |

c++

| | | |
|------------------------------------|-----|-----|
| C++ by Guidelines w/kernel 1.1 | 195 | 179 |
| PforC++ Library for C++ by Phoenix | 395 | 229 |

c compilers

| | | |
|-------------------------------------|-----|------|
| 68000/10/20 Cross Compiler by SDS | 595 | CALL |
| C86PLUS by Computer Innovations | 497 | CALL |
| Dataltight C Compiler Small Model | 60 | 49 |
| Dataltight Developer Kit | 99 | 79 |
| Dataltight Optimizer-C | 139 | 119 |
| DeSmet C w/Debugger | 159 | 138 |
| DeSmet C w/Debugger & Large Case | 209 | 184 |
| Eco-C Development System by EcoSoft | 125 | 83 |
| Lattice C Compiler from Lattice | 500 | 275 |
| Mark Williams Let's C Combo Pack | 125 | 99 |
| Let's C Compiler | 75 | 57 |
| csd Source Level Debugger | 75 | 57 |
| Mark Williams MWC-86 | 495 | 289 |
| Microsoft C with CodeView | 450 | 275 |
| Wizard C Combo by Wizard Systems | 750 | 529 |
| Wizard C Compiler | 450 | 299 |
| ROM Development Pkg | 350 | 259 |

c interpreters

| | | |
|---------------------------------------|-----|------|
| C-terp by Gimpel, Specify compiler | 300 | 235 |
| C Trainer with Book by Catalytic | 122 | 87 |
| Instant C by Rational Systems | 500 | 379 |
| Introducing C by Computer Innovations | 125 | CALL |
| Run/C from Lifeboat | 150 | 88 |
| Run/C Professional from Lifeboat | 250 | 159 |

c utilities

| | | |
|--|------|------|
| C Essentials by Essential Software | 100 | 75 |
| C-ISAM by Informix | 225 | 195 |
| C to dBase by Computer Innovations | 150 | CALL |
| c-tree & r-tree Combo by FairCom | 650 | 529 |
| c-tree ISAM File Manager | 395 | 329 |
| r-tree Report Generator | 295 | 249 |
| C Utility Library by Essential | 185 | 135 |
| C Windows by Syscom | 100 | 85 |
| C Wings by Syscom | 50 | 43 |
| CI ROMPac by Computer Innovations | 195 | CALL |
| dbQUERY All Varieties by Raima | CALL | CALL |
| dbVISTA Single-User DBMS by Raima | 195 | 155 |
| with Source Code | 495 | 425 |
| dbVISTA Multi-User DBMS by Raima | 495 | 425 |
| with Source Code | 990 | 845 |
| dBx dBase/C Translator by Desktop AI | 350 | 314 |
| with Library Source Code | 550 | 493 |
| Entelekon Combo Package | 200 | 169 |
| C Function Library | 130 | 109 |
| C Windows | 130 | 109 |
| Superforms for C | 50 | 43 |
| Essential Comm Library w/Debugger | 250 | 195 |
| Breakout Debugger Any language | 125 | 99 |
| Essential Comm Library | 185 | 135 |
| Essential Graphics by Essential Software | 250 | 195 |
| Flash-up Windows by Software Bottling | 90 | 79 |
| Graphic Mono v2.2 by Sci Endeavors | 280 | 209 |
| Graphic Color v3.0 by Sci Endeavors | 350 | 284 |
| GRAFLIB by The Librarian | 175 | CALL |
| Greenleaf Comm Library by Greenleaf | 185 | 127 |
| Greenleaf Data Windows by Greenleaf | 225 | 157 |
| with Source Code | 450 | 295 |
| Greenleaf Functions by Greenleaf | 185 | 127 |
| HALO by Media Cybernetics | 300 | 209 |
| HALO Development Pkg for Microsoft | 595 | 395 |
| The HAMMER by DES Systems | 195 | 139 |
| HELP/Control by MOS | 125 | 109 |
| METAWINDOWS No Royalties | 185 | 115 |
| MetaFONTS | 80 | 58 |
| MetaWINDOWS/Plus by Metagraphics | 235 | 189 |
| MetaFONTS/Plus | 235 | 189 |
| PANEL by Roundhill Computer Systems | 295 | 215 |
| PC Lint by Gimpel Software | 139 | 99 |
| PLOTHI by The Librarian | 175 | CALL |
| PLOTHP by The Librarian | 175 | CALL |
| Scientific Subroutine Lib by Peerless | 175 | 134 |
| screenplay by Flexus | 175 | 129 |
| Vector87 by Vectorplex Data Systems | 150 | 135 |
| Vitamin C by Creative Programming | 225 | CALL |
| VC Screen Forms Designer | 100 | 82 |
| Zview by Data Management Consultants | 245 | 189 |

cobol language

| | | |
|---------------------------------------|------|------|
| Micro Focus COBOL Workbench | 4000 | CALL |
| Micro Focus Level II COBOL | 1500 | CALL |
| COGRAPHICS | 250 | CALL |
| COMATH | 200 | CALL |
| FORMS-2 | 300 | CALL |
| Level II Animator | 900 | CALL |
| Level II SOURCEWRITER | 2000 | CALL |
| Micro Focus Level II COBOL for Novell | 2000 | CALL |
| Micro Focus Professional COBOL | 3000 | CALL |
| Multi-user Runtime for PC Network | 500 | CALL |

| | | |
|---------------------------------------|------|------|
| Microsoft COBOL See Microsoft Section | CALL | CALL |
| Realia COBOL | 995 | 785 |
| Realia CICS | 995 | 785 |
| RM/COBOL by Ryan-McFarland | 950 | 639 |
| RM/COBOL 85 by Ryan-McFarland | 1250 | 895 |
| screenplay by Flexus | 175 | 129 |

debuggers & profilers

| | | |
|---------------------------------------|-----|------|
| 386 DEBUG Cross Debugger by Phar Lap | 195 | 129 |
| Advanced Trace-86 by Morgan Computing | 175 | 125 |
| CI Probe by Computer Innovations | 225 | CALL |
| Codesifter Profiler by David Smith | 119 | 94 |
| Codesmith-86 by Visual Age | 145 | 99 |
| DSDB6 by Soft Advances | 70 | 61 |
| DSDB7 by Soft Advances | 100 | 79 |
| MiniProbe by Atron | 395 | CALL |
| Periscope I by The Periscope Company | 345 | CALL |
| Periscope II w/IMI Breakout Switch | 175 | CALL |
| Periscope II-X Software only | 145 | CALL |
| The PROFILER with Source Code by DWB | 125 | 89 |
| The WATCHER Profiler by Stony Brook | 60 | 51 |

forth language

| | | |
|---------------------------------------|------|------|
| CFORTH Native Code Compiler by LMI | 300 | 229 |
| Forth/83 Metacompiler Specify Target | 750 | 599 |
| PC/Forth by Laboratory Microsystems | 150 | 109 |
| PC/Forth+ by Laboratory Microsystems | 250 | 199 |
| Advanced Color Graphics Support | 100 | 74 |
| Enhanced Graphics Support | 200 | 148 |
| Intel 8087 Support | 100 | 74 |
| Interactive Symbolic Debugger | 100 | 74 |
| Native Code Optimizer | 200 | 148 |
| Software Floating Point | 100 | 74 |
| UR/Forth and support utilities by LMI | CALL | CALL |

fortran language

| | | |
|--|-----|------|
| 50 MORE: FORTRAN by Peerless Engr | 125 | 95 |
| ACS Time Series Alpha Computer Service | 495 | 399 |
| Btrieve ISAM File Mgr by SoftCraft | 245 | 194 |
| Essential Graphics by Essential Software | 250 | 195 |
| For-Winds Alpha Computer Service | 90 | 69 |
| Fortlib-Plus Alpha Computer Service | 70 | 49 |
| FORTLIB by Sutrast | 95 | CALL |
| FORTRAN Addenda by Impulse Engr | 95 | 85 |
| FORTRAN Addendum by Impulse Engr | 165 | 139 |
| GRAFLIB by Sutrast | 175 | CALL |
| HALO by Media Cybernetics | 300 | 209 |
| I/O PRO by MEF Environmental | 149 | 129 |
| Microcompatibles Combo Package | 240 | 219 |
| Grafmatic | 135 | 119 |
| Plotmatic | 135 | 119 |
| Microsoft FORTRAN w/CodeView - New Version | 450 | CALL |
| No Limit by MEF Environmental | 129 | 115 |
| PANEL Screen Designer by Roundhill | 295 | 215 |
| PLOTHI by Sutrast | 175 | CALL |
| PLOTHP by Sutrast | 175 | CALL |
| RM/FORTRAN Ryan-McFarland | 595 | CALL |
| Scientific Subroutine Lib by Peerless | 175 | 134 |
| Statistician Alpha Computer Service | 295 | 245 |
| Strings & Things Alpha Computer Service | 70 | 51 |
| Vector87 by Vectorplex Data Systems | 150 | 135 |

lattice products

| | | |
|-------------------------------------|------|-----|
| Lattice C Compiler from Lattice | 500 | 275 |
| with Library Source Code | 900 | 495 |
| C Cross Reference Generator | 50 | 37 |
| with Source Code | 200 | 145 |
| C-Food Smorgasbord Function Library | 150 | 95 |
| with Source Code | 300 | 184 |
| C-Sprite Source Level Debugger | 175 | 129 |
| Curses Screen Manager | 125 | 89 |
| with Source Code | 250 | 178 |
| dBC dBase File Manager for C | 250 | 178 |
| with Source Code | 500 | 356 |
| LMK Make Facility | 195 | 139 |
| RPG II Compiler No Royalties | 750 | 626 |
| RPG II Combo with SEU & Sort/Merge | 1100 | 939 |
| RPG II Screen Design Aid Utility | 350 | 309 |
| SecretDisk File Encryption Utility | 120 | 89 |
| SideTalk Resident Communications | 120 | 89 |
| SSP/PC Scientific Library | 350 | 269 |
| Text Management Utilities | 120 | 89 |
| TopView Toolbasket Function Library | 250 | 178 |
| with Source Code | 500 | 356 |

logitech products

| | | |
|-------------------------------------|-----|-----|
| LOGIMOUSE C7 Specify Connector Type | 99 | 83 |
| with PLUS Pkg | 119 | 98 |
| with PLUS & PC Paintbrush | 169 | 134 |
| with PLUS & CAD Software | 189 | 153 |
| with PLUS & Reflex | 199 | 162 |
| with PLUS & CAD & Paint | 219 | 179 |
| with PLUS & CAD & Paint & Reflex | 299 | 245 |
| LOGIMOUSE BUS with PLUS Pkg | 139 | 115 |
| with PLUS & PC Paintbrush | 189 | 149 |
| with PLUS & CAD Software | 209 | 175 |
| with PLUS & Reflex | 219 | 179 |
| with PLUS & CAD & Paint | 239 | 195 |
| with PLUS & CAD & Paint & Reflex | 319 | 259 |
| MODULA-2/86 Holiday Package | 199 | 159 |
| MODULA-2/86 Compiler | 89 | 62 |
| MODULA-2/86 with 8087 Support | 129 | 98 |

| | | |
|----------------------------------|-----|-----|
| MODULA-2/86 with PLUS Pkg | 189 | 138 |
| Library Sources | 99 | 88 |
| Make Utility | 29 | 25 |
| ROM Package | 199 | 172 |
| Run Time Debugger | 69 | 56 |
| Turbo to Modula Translator | 49 | 42 |
| Utilities Package | 49 | 42 |
| Window Package | 49 | 42 |
| REPETOIRE for MODULA-2/86 by PMI | 89 | 79 |
| Object Code Only | 19 | 15 |

microport products

| | | |
|-----------------------------------|-----|-----|
| System V/AT by Microport Systems | 440 | 395 |
| Runtime System (Operating System) | 159 | 145 |
| Software Development System | 169 | 155 |
| Text Preparation System | 169 | 155 |
| User Upgrade 3 to Unlimited Users | 169 | 155 |

microsoft products

| | | |
|--|-----|------|
| Microsoft BASIC Interpreter for XENIX | 350 | 239 |
| Microsoft C with CodeView | 450 | 275 |
| Microsoft COBOL Compiler | 700 | 439 |
| for XENIX | 995 | 635 |
| Microsoft COBOL Tools with Debugger | 350 | CALL |
| for XENIX | 450 | 289 |
| Microsoft FORTRAN w/CodeView - New Version | 450 | CALL |
| for XENIX | 695 | 439 |
| Microsoft Learning DOS | 50 | 36 |
| Microsoft LISP Common LISP | 250 | 163 |
| Microsoft MACH 10 w/Mouse & Windows | 549 | 385 |
| Microsoft MACH 10 Board only | 399 | 285 |
| Microsoft Macro Assembler | 150 | 95 |
| Microsoft Mouse Bus Version | 175 | 114 |
| Microsoft Mouse Serial Version | 195 | 124 |
| Microsoft muMath Includes muSIMP | 300 | 184 |
| Microsoft Pascal Compiler | 300 | 184 |
| for XENIX | 695 | 439 |
| Microsoft QuickBASIC | 99 | 65 |
| Microsoft Sort | 195 | 129 |
| Microsoft Windows | 99 | 65 |
| Microsoft Windows Development Kit | 500 | 309 |

other languages

| | | |
|-------------------------------------|-----|-----|
| CCS MUMPS Single-User by MGlobal | 60 | 51 |
| CCS MUMPS Single-User/Multi-Tasking | 150 | 129 |
| CCS MUMPS Multi-User | 450 | 369 |
| Janus/ADA C Pack by R&R Software | 95 | 89 |
| Janus/ADA D Pack by R&R Software | 900 | 769 |
| Personal REXX by Mansfield Software | 125 | 99 |
| Smalltalk/V by Digital | 99 | 84 |
| EGA Color Option | 49 | 45 |
| Goodies Diskette | 49 | 45 |
| Smalltalk/Comm | 49 | 45 |
| SNOBOL4+ by Catspaw | 95 | 80 |

other products

| | | |
|---|------|------|
| Compact Source Print by Aldebaran | CALL | CALL |
| Dan Bricklin's Demo Pgm Software Garden | 75 | 59 |
| FANSI-CONSOLE by Hersey Micro | 75 | 65 |
| FASTBACK by 5th Generation Systems | 179 | 135 |
| Informix for DOS by Informix | 795 | 639 |
| Informix4GL for DOS by Informix | 995 | 789 |
| InformixSQL for DOS by Informix | 795 | 639 |
| Instant Replay by Nostradamus | 90 | 79 |
| Interactive EASYFLOW by Haventree | 150 | 129 |
| MKS Toolkit with vi by MKS | 139 | 119 |
| Norton Commander by Peter Norton | 75 | 55 |
| On-line Help from Opt-Tech Data Proc | 149 | 109 |
| OPT-Tech Sort by Opt-Tech Data Proc | 149 | 115 |
| PrintQ by Software Directions | 89 | 84 |
| Quit Computing Combo Package | 199 | 159 |
| QMake Program Rebuild Utility | 99 | 84 |
| SRMS Software Revision Mgmt Sys | 125 | 109 |
| SoftScreen/HELP by Dialectic Systems | 195 | 149 |
| Source Print by Aldebaran Labs | CALL | CALL |
| Taskview by Sunny Hill Software | 80 | 56 |
| TLIB by Burton Systems Software | 100 | 89 |
| Tree Diagrammer by Aldebaran Labs | CALL | CALL |
| VTEK Term Emulator by Sci Endeavors | 150 | 129 |

phoenix products

| | | |
|------------------------------------|------|-----|
| Pasm86 Macro Assembler Version 2.0 | 195 | 115 |
| Pdisk Hard Disk & Backup Utility | 195 | 125 |
| Plintasy Pac Phoenix Combo | 1295 | 849 |
| Plintasy Performance Analyzer | 395 | 229 |
| Plix-86 Plus Symbolic Debugger | 395 | 229 |
| PforCe Comprehensive C Library | 395 | 229 |
| Plink-86 Plus Overlay Linker | 495 | 319 |
| Pmaker Make Utility | 125 | 78 |
| Pmate Macro Text Editor | 195 | 115 |
| Pre-C Lint Utility | 295 | 155 |
| Ptel Binary File Transfer Program | 195 | 115 |

polytron products

| | | |
|-------------------------------------|------|------|
| PolyBoost The Software Accelerator | 80 | 69 |
| Polytron C Beautifier | 49 | 45 |
| Polytron C Library I | 99 | 78 |
| Polytron PowerCom Communications | 179 | 139 |
| PolyLibrarian Library Manager | 99 | 78 |
| PolyLibrarian II Library Manager | 149 | 115 |
| PolyMake UNIX-like Make Facility | 99 | 78 |
| PolyShell | 149 | 119 |
| PolyWindows Products All Varieties | CALL | CALL |
| PolyXREF Complete Cross Ref Utility | 219 | 169 |
| PolyXREF One language only | 129 | 99 |
| PVCS Version Control System | 395 | 309 |

softcraft products

| | | |
|------------------------------------|-----|-----|
| Btrieve ISAM Mgr with No Royalties | 245 | 194 |
| Xtrieve Query Utility | 245 | 194 |
| Report Option | 145 | 114 |
| Btrieve/N for Networks | 595 | 464 |
| Xtrieve/N | 595 | 464 |
| Report Option/N | 345 | 274 |

text editors

| | | |
|-----------------------------------|-----|------|
| Brief from Solution Systems | 195 | CALL |
| Epsilon Emacs-like editor by Lugu | 195 | 154 |
| KEDIT by Mansfield Software | 125 | 99 |
| Micro/SPF by Phaser Systems | 175 | 139 |
| PC/VI by Custom Software Systems | 149 | 119 |
| SPF/PC by Command Technology Corp | 195 | 139 |
| Vedit by CompuView | 150 | 107 |
| Vedit Plus by CompuView | 185 | 139 |

turbo pascal utilities

| | | |
|--|-----|------|
| ALICE Interpreter by Software Channels | 95 | 66 |
| Flash-up Windows by Software Bottling | 90 | 79 |
| HELP/Control by MDS | 125 | 99 |
| screenplay all varieties by Flexus | 100 | 79 |
| Screen Sculptor by Software Bottling | 125 | 91 |
| Speed Screen by Software Bottling | 125 | 91 |
| System Builder by Royal American | 100 | CALL |
| IMPEX Query Utility | 75 | CALL |
| Report Builder | 75 | CALL |
| TDebugPLUS by TurboPower Software | 60 | 49 |
| Turbo EXTENDER by TurboPower Software | 85 | 64 |
| Turbo Professional by Sunny Hill | 70 | 48 |
| TurboHALO from IMSI | 129 | 98 |
| TurboPower Utilities by TurboPower | 95 | 78 |
| TurboRef by Gracon Services | 50 | 45 |
| TURBOsmith Debugger by Visual Age | 58 | 45 |
| TurboWINDOW by MetaGraphics | 80 | 58 |

wendin products

| | | |
|------------------------------------|----|----|
| Operating System Toolbox | 99 | 79 |
| PCNX Operating system | 99 | 79 |
| PCVMS Similar to VAX/VMS | 99 | 79 |
| XTC Text editor with Pascal source | 99 | 79 |

xenix system v

| | | |
|---|------|-----|
| See also Microport System V/AT section. | | |
| XENIX System V Complete by SCO | 1295 | 999 |
| XENIX Development System | 595 | 499 |
| XENIX Operating Sys Specify XT/AT | 595 | 499 |
| XENIX Text Processing Package | 195 | 144 |

xenix products

| | | |
|---------------------------------------|------|------|
| Btrieve ISAM File Mgr by SoftCraft | 595 | 464 |
| C-ISAM by Informix | 319 | 285 |
| C-terp by Gimpel, Specify compiler | 498 | 379 |
| c-tree ISAM Mgr by FairCom | 395 | 329 |
| dbVISTA All Varieties by Raima | CALL | CALL |
| dBx with Library Source by Desktop AI | 550 | 499 |
| DOSIX User Version by Data Basics | 199 | CALL |
| DOSIX Console Version by Data Basics | 399 | CALL |
| Informix by Informix | 995 | 795 |
| Informix4GL by Informix | 1500 | 1239 |
| InformixSQL by Informix | 995 | 795 |
| Lyrix by Informix | 595 | 449 |
| Micro Focus Level II Compact COBOL | 1000 | 795 |
| Forms-2 | 400 | 319 |
| Level II ANIMATOR | 600 | 479 |
| Microsoft See Microsoft Section | CALL | CALL |
| Networks for XENIX by SCO | 595 | 495 |
| PANEL Screen Designer by Roundhill | 625 | 535 |
| REAL-TOOLS Binary Version by PCT | 149 | 89 |
| Library Source Version | 399 | 289 |
| Complete Source Version | 499 | 369 |
| RM/COBOL by Ryan-McFarland | 1250 | 949 |
| RM/FORTRAN by Ryan-McFarland | 750 | 549 |
| SCO Professional Lotus clone by SCO | 795 | 595 |

LOWEST PRICES

Since this ad is prepared in advance of publication, some of our current prices may be lower than what's advertised here. Call for latest pricing.

FREE SHIPPING

Orders within the USA (including Alaska & Hawaii) are shipped FREE via UPS. Express shipping is available at the shipping carrier's standard rate with no rush fees or handling charges. To avoid delays when ordering by mail, please call first to determine the exact cost of express shipping.

CREDIT CARDS

VISA and MasterCard are accepted at no extra cost. Your card is charged when your order is shipped. Mail orders please include credit card expiration date and telephone number.

CODs AND POs

CODs and Purchase Orders are accepted at no extra cost. POs with net 30-day terms are available to qualified US accounts only.

FOREIGN ORDERS

Shipping charges for foreign and Canadian orders are based on the shipping carrier's standard rate. Since rates vary between carriers, please call or write for the exact cost. Foreign orders (except Canada), please include an additional \$10 for customs form preparation. All payments must be made with US funds drawn on a US bank. Please include your telephone number when ordering by mail. Due to government regulations, we cannot ship to all countries.

VOLUME ORDERS

Call for special pricing.

SOUND ADVICE

Our knowledgeable technical staff can assist in comparing products, answer technical questions and send you detailed product information tailored to your needs.

30-DAY GUARANTEE

Most of our products come with a 30-day documentation evaluation period or 30-day return guarantee. Please note that some manufacturers restrict us from offering guarantees on their products. Call for more information.

CALL TOLL-FREE

| | |
|----------------|--------------|
| U S | 800-336-1166 |
| CANADA | 800-225-1166 |
| OHIO & ALASKA | |
| (Call Collect) | 216-877-3781 |

| | |
|------------------|--------------|
| FOREIGN | 216-877-3781 |
| CUSTOMER SERVICE | 216-877-1110 |

Hours: Weekdays 8:30 AM to 8:00 PM EST.

Ohio customers please add 6% state sales tax

Prices are subject to change without notice.

Call or write for our FREE comprehensive price guide.

136 SUNNYSIDE STREET

HARTVILLE, OHIO 44632

programmer's connection

C & PASCAL PROGRAMMERS

Blaise Computing provides a broad range of programming tools for Pascal and C programmers, with libraries designed for serious software development. You get carefully crafted code that can be easily modified to grow with your changing needs. Our packages are shipped complete with comprehensive manuals, sample programs and source code.

C TOOLS PLUS

\$175.00

NEW! Full spectrum of general-purpose utility functions; windows that can be stacked, removed, and accept user input; interrupt service routines for resident applications; screen handling including EGA 43-line text mode support and direct screen access; string functions; and DOS file handling.

PASCAL TOOLS/TOOLS 2

\$175.00

Expanded string and screen handling; graphics routines; easy creation of program interfaces; memory management; general program control; and DOS file support.

VIEW MANAGER

\$275.00

Complete screen management; paint data entry screens; screens can be managed by your application program; block mode data entry or field-by-field control. Specify C or IBM/MS-Pascal.

ASYNCH MANAGER

\$175.00

Full featured asynchronous communications library providing interrupt driven support for the COM ports; I/O buffers up to 64K; XON/XOFF protocol; baud rates up to 9600; modem control and XMODEM file transfer. Specify C or IBM/MS-Pascal.

Turbo POWER TOOLS PLUS

\$99.95

NEW! Expanded string support; extended screen and window management including EGA support; pop-up menus; memory management; execute any program from within Turbo Pascal; interrupt service routine support allowing you to write memory resident programs; schedulable intervention code.

Turbo ASYNCH PLUS

\$99.95

Complete asynchronous communications library providing interrupt driven support for the COM ports; I/O buffers up to 64K; XON/XOFF protocol; and baud rates up to 9600.

RUNOFF

\$49.95

NEW! Text formatter written especially for programmers; flexible printer control; user-defined variables; index generation; and general macro facility. Crafted in Turbo Pascal.

EXEC

\$95.00

Program chaining executive. Chain one program from another even if the programs are in different languages. Shared data areas can be defined.

ORDER TOLL-FREE 800-227-8087!

LAISE COMPUTING INC.

9 Ninth Street, Suite 316 Berkeley, CA 94710 (415) 540-5441

Circle no. 217 on reader service card.

16 BIT

Listing One (Listing continued, text begins on page 110.)

```
-----
* paste -- a program to attach to the lines of a file the correspond-
*         ing lines of another file, with an optional string between
*         them.
*
* Written January, 1984 by John M. Gamble
* Updated for UNIX April, 1986
*
* usage:
*
* paste [-paste] [-b <string>] [-<n>] [file1] [file2]
*
* options:
*
* -p <file1> does not exist (<string> is prepended to each
*     line.)
*
* -a <file2> does not exist (<string> is appended to each
*     line.)
*
* -s Do not print <string> with lines from only one file.
*
* -t An option to resolve the ambiguous command
*     "paste <file>". The -t flag forces <file> to trail
*     standard input. I.e.,
*
*     "paste <file>"
*         is equivalent to "paste <file> <stdin>"
*
*     "paste -t <file>"
*         is equivalent to "paste <stdin> <file>".
*
* -e Do not print <string> if both input lines are empty
*     (i.e., that consist of no characters but '\n'.)
*
* -b <string> A string of characters to be inserted between the lines
*             of <file1> and <file2>. The string may contain all
*             the standard escape codes with the exception of '\0'.
*             The string may also indicate blanks with the escape
*             sequence '\s'.
*
* -<n> Print <n> lines of <file1> before appending lines of
*       <file2>. If <n> is negative (e.g., "paste --3") then
*       <n> lines of <file2> will be printed first.
*
*-----
#include <stdio.h>
#include <ctype.h>

/* On systems such as UNIX, if a string with blanks in it is
 * surrounded by quote marks, it is considered to be one string.
 * On other systems, the blank ends the string and the quote
 * marks are passed along with the other characters. So, while
 * on UNIX, the command
 *
 *     'paste -b " "; do " list1 list2'
 *
 * would set
 *
 *     argv[2] to "; do ",
 *     argv[3] to list1,
 *     argv[4] to list2.
 *
 * a system like MSDOS would set
 *
 *     argv[2] to "\"",
 *     argv[3] to "do",
 *     argv[4] to "\"",
 *     argv[5] to list1,
 *     argv[6] to list2.
 *
 * This is easily taken care of, but it does mean that conditional
 * compilation is required by setting the switch below to either
 * zero or one, depending on your particular operating system.
 */
#define BLANK_ENDS_STR 0

#define STRINGLEN 128
#define TRUE 1
#define FALSE 0

#define isoctal(x) ((x) >= '0' && (x) < '8')

typedef unsigned int Boolean;

char bstr[STRINGLEN] = {'\0'};

char *nullstr = "";
char *strf = "%s";
char *program_name = "paste";
char *error_msg[] =

{
    "usage: %s [-aptse] [-b \"string\"] [-<n>] [file1] [file2] %s\n",
    "%s: unknown flag %s\n",
    "%s: at least one file must exist%s\n",
    "%s: -t flag is only valid with one file on the command line%s\n",
    "%s: both files can't be standard input%s\n",
    "%s: contradictory options%s\n",
    "%s: can't open %s\n",
    "%s: -a or -p flags are invalid with two files%s\n",
    "%s: too many files%s\n",
    "%s: string argument lacks closing \" or \"%s\n",
    "%s: string character in string argument%s\n",
    "%s: null character in string argument too long%s\n"
};

main(argc, argv)
int
char **argv;
```



```

FILE          *fp1, *fp2, *fopen();
Booleanprepend = FALSE, append = FALSE, trailing = FALSE;
Booleanprintempty = TRUE, printsingle = TRUE;
int           slip = 0;
char          *subarg;

if (argc == 1)
    exit_error(0, nullstr);

/* Get the flags.
 */
while (--argc > 0 && **++argv == '-')
{
    switch (*(*argv + 1))
    {
        case '0': /* Because default: won't catch this.*/
            exit_error(1, *argv);
            break;

        case 'b':
            if (argc == 1)
                exit_error(0, nullstr);

            argc--;
            argv++;

        #if BLANK_ENDS_STR
            strget(&argc, &argv, bstring);
        #else
            strload(&argv, bstring);
        #endif
            break;

        case '-':
        case '0':
        case '1':
        case '2':
        case '3':
        case '4':
        case '5':
        case '6':
        case '7':
        case '8':
        case '9':
            slip = atoi(*argv + 1);
            break;

        default:
            subarg = *argv;
            while (**++subarg)
            {
                switch (*subarg)
                {
                    case 'a':
                        append = TRUE;
                        break;

                    case 'e':
                        printempty = FALSE;
                        break;

                    case 'p':
                        prepend = TRUE;
                        break;

                    case 's':
                        printsingle = FALSE;
                        break;

                    case 't':
                        trailing = TRUE;
                        break;

                    default:
                        exit_error(1, *argv);
                        break;
                }
            }
            break;
    }
}

if (prepend && append) /* Contradictory options.*/
    exit_error(2, nullstr);

switch (argc) /* The number of file names on the command line.*/
{
    case 0:
        if (trailing)
            exit_error(3, nullstr);

        if (!(prepend || append)) /* Both files can't be stdin.*/
            exit_error(4, nullstr);

        if (append)
            attachf(stdin, NULL, slip, printsingle, printempty);
        else
            attachf(NULL, stdin, slip, printsingle, printempty);
        break;

    case 1:
        /* Contradictory options?
        */
        if (trailing && (prepend || append))
            exit_error(5, nullstr);

        if ((fp1 = fopen(*argv, "r")) == NULL)
            exit_error(6, *argv);

```

(continued on page 82)

ANNOUNCING . . . High performance APL Interpreter using MC68000 32 bit coprocessors and NS32081 floating point processors totally integrated with DOS and Novell Netware hardware and software environment. MultiAPL coprocessors offer 1MB or 4MB RAM for large APL workspaces and the fastest processing facilities available under DOS or Netware.


MULTIAPL

EXPLORE

- 640K + 1MB or 4MB
- Full component multi-user file system
- Btrieve file interface
- No restrictions on object size
- Shared variable interface
- Uses standard DOS files
- Overlays (functions/variables)
- 10 & 12 MHZ coprocessors available
- Extended superset of IBM's VSAPL
- APL*PLUS conversion utilities
- Full screen facilities included
- Enhanced version of APL.68000
- Run time versions available

COMPARE

BYTE Magazine
Calculations Benchmark
Double Precision Numbers
(All systems with one user)



INTRODUCTORY OFFER

\$995

GOOD THRU 4/30/87

INCLUDES: APL INTERPRETER
AND REFERENCE MANUAL, 10 MHZ
COPROCESSOR WITH 1 MB RAM
(No Wait State)

Optional Math Processor \$295

Order direct for \$995 + Shipping/handling
(\$18 US, \$20 Canada) VISA/MC/AMEX add 4%.
Certified check, MO, COD. OFFER GOOD IN
U.S. AND CANADA ONLY.


30 DAY MONEY BACK GUARANTEE

SPENCER
ORGANIZATION, INC.

P.O. BOX 248 WESTWOOD, N.J. 07675

(201) 666-6011

Btrieve is a trademark of Softcraft, Inc.
APL*PLUS is a trademark and service
mark of STSC, Inc.




POWER TOOLS for SYSTEM BUILDERS™

800-543-6277

Ask for Operator 2053
California: 800-368-7600

TSF is owned and operated by programmers, so we understand your needs. We believe *and practice* integrity in all business dealings. We advertise real prices and offer our best price to all customers. We provide prompt delivery of current product versions.

We accept checks, Visa, MasterCard, American Express and COD. We charge your card only when we ship and do **not** add a surcharge. We provide free UPS delivery on orders over \$100 (\$3 delivery charge for small orders). Our COD fee is \$4. We allow return privileges on most products. **Give us a try!**



The Software Family

649 Mission Street
San Francisco, CA 94105

See us at the Computer Faire,
Moscone Center, San Francisco,
March 26 through 29, 1987!

Winter Specials

Basic Language

| | |
|-----------------------------------|------|
| Microsoft Quick Basic (List \$99) | \$65 |
| MicroHelp Inside Track (\$65) | \$55 |
| MicroHelp Mach 2 (List \$75) | \$60 |
| MicroHelp Stay-Res (List \$95) | \$75 |
| Sterling Castle Tools (List \$99) | \$80 |

C Language

| | |
|----------------------------------|-------|
| Datalight C (List \$99) | \$75 |
| Microsoft C w/Codeview (\$450) | \$270 |
| Guidelines C++ (List \$195) | \$175 |
| Lattice C (List \$500) | \$270 |
| Mark Williams C (List \$500) | \$290 |
| Rational Instant C | \$375 |
| Gimple C-Terp (List \$300) | \$224 |
| Run/C Professional (List \$250) | \$160 |
| Run/C Interpreter (List \$120) | \$85 |
| Gimpel PC Lint (List \$139) | \$103 |
| Softcraft Btrieve (List \$245) | \$190 |
| Lattice dBase III Intfc (\$250) | \$175 |
| Blaise View Manager (List \$275) | \$197 |
| Vermont Window for Data (\$295) | \$259 |
| Lattice Curses (List \$125) | \$90 |
| Essentials C Essentials (\$100) | \$80 |
| Essentials Graphics (List \$250) | \$200 |
| Blaise C Tools+ (List \$175) | \$125 |
| Essentials Utility (List \$185) | \$130 |
| Greenleaf Functions (List \$185) | \$130 |
| Greenleaf Comm (List \$185) | \$130 |
| Blaise Async Manager (\$175) | \$125 |

Pascal Language

| | |
|-----------------------------------|-------|
| Microsoft Pascal (List \$300) | \$180 |
| Blaise View Manager (List \$275) | \$197 |
| Blaise Async Manager (\$175) | \$125 |
| Blaise Pascal Tools+ (List \$175) | \$125 |

Turbo Pascal

| | |
|----------------------------------|------|
| Turbo Pascal BCD & 8087 (\$100) | \$65 |
| Software Channels Alice (\$95) | \$70 |
| Kydror Symbolic Debugger (\$49) | \$40 |
| Blaise Turbo Async (\$100) | \$80 |
| Blaise Power Tools (\$100) | \$80 |
| Borland Turbo Editor (List \$70) | \$48 |

Other Tools

| | |
|----------------------------------|-------|
| Custom Software PC/VI (\$149) | \$119 |
| MKS Toolkit (\$List \$139) | \$115 |
| Periscope I (List \$295) | \$235 |
| Periscope II (List \$145) | \$108 |
| Phoenix Plink+ (List \$495) | \$315 |
| Phoenix Pfinish (List \$395) | \$230 |
| Phoenix Pfix86+ (List \$395) | \$225 |
| Polytron Make (List \$99) | \$80 |
| Quilt SRMS + Qmake (List \$199) | \$165 |
| Seidl SVM + SMK (List \$379) | \$330 |
| Dan Bricklin's Demo (List \$75) | \$68 |
| Opt-Tech Sort (List \$149) | \$126 |
| Borland Turbo Prolog (List \$99) | \$65 |
| Microsoft MASM (List \$150) | \$98 |
| Microsoft Fortran (List \$350) | \$200 |

... and many more

... call for price list

Basic: Mach2 from MicroHelp expands Basic's horizons with window management, input editing, array sorting and print formatting. It also provides MSDOS/BIOS function calls and allows you to break the 64K data barrier. Written in assembler for high performance. For Bascom, Quick Basic, BASICA and GWBASIC. (List \$75) **Only \$60 from TSF. 30 day money back guarantee!**

C: Gimpel's PC-Lint evaluates your source code to locate insidious C bugs like "=" instead of "==" and mismatched function parameters. Evaluates multiple source files to validate use of all public functions and variables. Compatible with all popular compilers. 30 day trial period (15% restock fee). (List \$139) **Only \$103 from TSF.**

All Languages: Periscope II speeds debugging with multiple windows, symbolic memory addressing, and sophisticated trace and breakpoints. Includes an NMI break switch so you can interrupt programs at any time without pre-setting break points -- ends guesswork for hard-to-locate crashes. (List \$145) **Only \$108 from TSF. 30 day money back guarantee!**

Turbo: Kydror's Symbolic Debugger provides symbolic debugging for Turbo Pascal programs. Includes trace, breakpoint, memory display and memory modification. Runs from within Turbo's environment, so you don't lose any Turbo features. Written in assembler for speedy operation and low memory overhead. (List \$49) **Only \$40 from TSF.**

Communications: RamNet from System Design provides background file transfers and e-mail for your PC. Incoming and outgoing calls are processed automatically while you continue with your normal work. Outgoing calls can be scheduled to take advantage of late night phone rates and to concentrate messages in a multi-node **RamNet** network. (List \$149) **Only \$129 from TSF. A two node starter kit is only \$248. 30 day money back guarantee!**

COMPUTING

MICROSOFT

BORLAND
INTERNATIONAL

Lattice

Phoenix

BLAISE COMPUTING

Do You Feel Lucky???



Good programming isn't a matter of luck. It requires skill, perseverance and good programming tools. You already have the skill and perseverance; **Janus/Ada** provides the programming tools. Tools you can rely on in any project, in almost any MS DOS environment, with full portability to any other Ada system. With **Janus/Ada**, you get lucky in all the right ways:

- SYSTEM REQUIREMENTS:** Any Intel 86 family processor with 512K RAM, two floppy disk drives or a hard disk and DOS 2.0 or higher.
- COMPILE SPEEDS:** 8086/6MHZ: 300 lines per minute; 80186/8MHZ: 500 lines per minute; 80286/8MHZ: 900 lines per minute (DOS 3.0)
- PRODUCT SUPPORT:** Quarterly newsletters, 24 hour Bulletin Board, and a staff with over 20 man years of actual Ada programming experience.
- APPLICATIONS AND TOOLS:** Assemblers, disassemblers, Ada source code, a Pascal to Ada translator, 8087 support, tutorials and more!
- AFFORDABILITY:** Our **Janus/Ada "C"** Pak is available for \$99.95 and contains the **Janus/Ada** Compiler and Linker, designed specifically for microcomputers and consumer tested since 1981. Our customers can upgrade to our development and embedded systems "paks" with 100% credit for this starter package. Our **Janus/Ada** Extended Tutorial is available for the same low price. We feature commercial and educational "site" licensing for all of our packages.
- ADA STANDARDIZATION:** **Janus/Ada** source code can be ported to any validated Ada system and compiled. We offer a variety of tools and consultations to assist you in this process, if needed.
- JANUS/ADA USERS:** Over 5,000 separate sites use the **Janus/Ada** compiler for training, embedded systems and applications each day. We supply our tools to the U.S. Armed Forces, Fortune 500 companies and over 400 educational institutions, as well as to individuals like you.

We've been making programmers lucky with our tools for over 5 years; isn't it about time you changed your luck? We'll even pay for the call! To place an order or receive our informative brochure, **please call 1-800-722-3248**. It'll make your day!!!



SOFTWARE, INC.

P.O. Box 1512 Madison, Wisconsin 53701
(608) 244-6436 TELEX 4998168

CP/M, CP/M-86, CCP/M-86 are trademarks of Digital Research, Inc.
ADA is a trademark of the U.S. Department of Defense
MS-DOS is a trademark of Microsoft

© Copyright 1986 RR Software

specialists in state of the art programming

1-800-722-3248

Circle no. 365 on reader service card.

2 Programmers & Developers New Products!

Distribute Your Demos with No Royalties

Screen Machine creates interactive demos, tutorials, menu systems and DOS shells. Includes a text screen editor that optionally generates source code* and binary or text files. Never write code for screen display again. Capture any program's text screens for editing and your own use. Capture CGA compatible graphics screens for BLOAD or direct display. SAVE hundreds of HOURS of work.

Now there's no need for separate screen and demo software packages and no need to pay outrageous royalties. Priced at only \$79.00.

*Turbo Pascal, Mach 2 for Turbo, Assembler, dBASE II & III, BASIC (including The Inside Track and Mach 2).

Supercharge Turbo Pascal

Mach 2 for Turbo Pascal adds assembler speed to your programs. 90+ subroutines, most in assembler, give you speed and functionality you never knew was possible. No knowledge of assembler language required.

INSTANT displays. INSTANT windows (incl. exploding and boxed). FASTEST sort you've seen. Read/write files FAST as DOS. INSTANT menus, 1-2-3 horizontal and vertical bar.

Trap ^C/^Break & DOS critical errors so no more A)bort, R)etry or I)gnore. Emulate BASIC PRINT USING for FAST formatted numbers. Execute any prog, batch or DOS command without ending program.

Read environment. Read file directory. Get/set file attributes. Plus too many string functions to describe here. No royalties when you distribute COM programs. All source code included. A true bargain at \$69.00.

NOT COPY PROTECTED. 30 Day Money-Back Performance Guarantee. Requires IBM/compatible & DOS 2+.

Order Now 800-922-3383

We welcome VISA/MC. COD US only \$3. S/H US \$3, Canada \$5, Elsewhere \$18. GA res. add tax and call 404-973-9272. Demo available. Send \$5 check. Refunded on direct purchase.

We also publish Stay-Res, Mach 2 for BASIC, The Inside Track and Peaks 'n Pokes.

MicroHelp, Inc.
2220 Carlyle Drive
Marietta GA 30062

Circle no. 215 on reader service card.

16 BIT

Listing One (Listing continued, text begins on page 110.)

```

if (append)
    attachf(fp1, NULL, slip, printsingle, printempty);

else if (prepend)
    attachf(NULL, fp1, slip, printsingle, printempty);

else if (trailing)
    attachf(stdin, fp1, slip, printsingle, printempty);

else
    attachf(fp1, stdin, slip, printsingle, printempty);

fclose(fp1);
break;

case 2:
    if (trailing)
        exit_error(3, nullstr);

    if (prepend || append)
        exit_error(7, nullstr);

    if ((fp1 = fopen(*argv, "r")) == NULL)
        exit_error(6, *argv);

    if ((fp2 = fopen(++argv, "r")) == NULL)
        exit_error(6, *argv);

    attachf(fp1, fp2, slip, printsingle, printempty);
    fclose(fp1);
    fclose(fp2);
    break;

default:
    exit_error(8, nullstr);
    break;
}

exit(0);                                     /* End of main.*/
}

/*if BLANK_ENDS_STR
/*-----
 * strget -- retrieve the <string> argument from the command line.
 * If the string contains blanks, C assumes this is the end of the
 * string, and places a \0 at its end. Since WE know that it's
 * just a blank, we put one in, update the position of argv, and
 * decrement argc. Escape sequences are treated just as defined
 * in C (except \0, which is an error). One extra escape sequence
 * ('\s') exists to handle multiple blanks on a line, for even if
 * the string is enclosed in quotes the extra blanks will not be
 * passed from the command line.
 *-----*/
strget(pargc, pargv, bstr)
int
char
char
char
{
    register int j;
    char *subarg;
    Booleanst_quote = FALSE;
    Booleanst_apost = FALSE;

    subarg = **pargv;

    /* If the string is begun with a quote or an apostrophe, remember
     * so that we know when to end the string.
     */
    if ((st_quote = (*subarg == '"')) || (st_apost = (*subarg == '\'')))
        subarg++;

    for (j = 0; j < STRINGLEN; bstr++, subarg++, j++)
    {
        /* A " or ' encountered could mean the end of a string -
         * check against st_quote or st_apost.
         */
        if ((st_quote && *subarg == '"') ||
            (st_apost && *subarg == '\''))
            break;

        else if (*subarg == '\0')
        {
            /* If we began with a quote, we are not finished.
             */
            if (st_quote || st_apost)
            {
                /* If nothing is left on the command line,
                 * a quote mark is missing.
                 */
                if (--(*pargc) == 0)
                    exit_error(9, nullstr);

                /* Put the blank in, and point subarg
                 * to the next argv string.
                 */
                *bstr = ' ';
                subarg = *++(*pargv) - 1;
            }

            /* Otherwise we didn't start with a quote mark - end.
             */
            else
                break;
        }

        else if (*subarg == '\\')
            switch(++subarg)

```

/* Escape sequences.*/
(continued on page 84)

Why Are So Many People Switching to Smalltalk/V?

Why are scientists, engineers, and professionals switching to Smalltalk/V? Because it lets them do amazing things on their PCs, with a Mac-like interface and an easy-to-use object-oriented language. And with Smalltalk/V you get an unsurpassed array of problem-solving tools. You can even personalize the entire system to suit your needs.

Smalltalk/V is the programmable environment that gives you total control of your computer and makes it what it was meant to be, a truly personal tool for your mind.

"This is the real thing, folks. A super Smalltalk like this turns your PC into a hot workstation. It's fantastic . . . Highly recommended."

*John C. Dvorak,
Contributing Editor, PC Magazine*

"My background is in physical chemistry, not in programming. I like Smalltalk/V because I can use objects in the computer to represent objects in the physical world."

*Dr. Paul Soper, Senior Specialist
E. I. du Pont de Nemours & Co.*

"Smalltalk/V is a productive programming environment that allows us to quickly develop sophisticated medical applications."

*Dr. Mike McCoy,
Dean for Instructional Computing
UCLA School of Medicine*



"Smalltalk/V is the highest performance object-oriented programming system available for PCs."

*Dr. Piero Scaruffi,
Chief Scientist, Olivetti
Artificial Intelligence Center*

"Smalltalk/V is an excellent buy and makes a good alternative to other programming languages for the development of complex applications."

*Bill Wong, Director, PC Labs
PC Magazine*

\$99.00

Other Smalltalk/V Features

- Object-oriented Prolog integrated with the Smalltalk environment
- Supports exploratory programming and prototyping
- Class hierarchy with inheritance creates highly re-useable source code
- Smalltalk source code included, with browser windows for easy access and modification
- Object-swapping creates a virtual memory on hard or RAM disk
- Bit-mapped graphics with bit and form editors
- A sophisticated source-level debugger
- Automatic change log for easy recovery from errors
- Powerful directory/file browser system for organizing DOS files
- Access to other languages and DOS functions
- 500 page manual with comprehensive tutorial and reference sections
- Optional add-on modules
 - RS-232 communications interface with UNIX™ and TTY windows
 - EGA color graphics
 - "Goodies" diskette, including multiprocessing, music, zoom, object loader, and more

Smalltalk/V The Programmable Environment

"Smalltalk/V, with its visual interface and class structure, is a perfect way to simulate the complex interactions of natural systems."

*Lee A. Graham, Research Assistant
Institute of Ecology, University of Georgia*

"I solve problems quickly using Smalltalk/V because its classes and objects help me organize my thinking. And besides, it's fun to use."

*Dr. Barry Fishman, Sr. Project Engineer
Hughes Aircraft Company*

BYTE and BIX are trademarks of McGraw-Hill, Inc. IBM, IBM-PC, and IBM PC-AT are trademarks of International Business Machines Corporation. Unix is a trademark of Bell Laboratories.

Yes! I want to turn my PC into a hot workstation! Send me . . .

☐ Smalltalk/V-The Programmable Environment \$99
☐ Communications Option \$49
☐ EGA Color Option \$49
☐ "Goodies" diskette \$49
 Shipping and Handling \$
 CA residents add applicable sales tax \$
TOTAL \$
Shipping and Handling
 U.S., Canada, Mexico \$ 5.00
 Elsewhere \$15.00

I enclose ☐ Check ☐ Money Order
☐ Credit card information ☐ MC ☐ VISA
 Number: _____
 Expiration: _____
 Signature: _____
 Name: _____
 Street Address: _____
 City/State/Zip: _____
 Phone: _____

**NOT COPY PROTECTED, 60-DAY MONEY-BACK GUARANTEE
ON-LINE USER-SUPPORT CONFERENCE ON BYTE'S BIX™**

Smalltalk/V requires DOS and 512K RAM on IBM PCs (including AT) or "compatibles," and a CGA, EGA, Toshiba T3100, Hercules, or AT&T 6300 graphic controller. A Microsoft or compatible mouse is recommended.

digitaltalk inc.

5200 West Century Boulevard
Los Angeles, CA 90045 (213) 645-1082

Circle no. 127 on reader service card.

SAPIENS V8

A VIRTUAL MEMORY MANAGER FOR THE PC

**C PROGRAMMERS!
LINK IN**

**EXPAND YOUR C COMPILER
8 MEGABYTES
ON A PC**

- ★ VIRTUAL MEMORY MANAGER FOR C PROGRAMMERS ON THE IBM PC.
- ★ PROVIDES 8 MGS. VIRTUAL MEMORY WORKSPACE.
- ★ Link V8 libraries to C compilers — MICROSOFT, LATTICE AND AZTEC.
- ★ FAST: LESS THAN 10 % SPEED OVERHEAD
- ★ ADVANCED SOFTWARE EMULATION OF 64-BIT ARCHITECTURE

\$300⁰⁰

Sapiens V8 is for C programmers who want to develop PC applications that go beyond current memory restrictions of the PC and a 16 bit architecture.

- V8 is not dependent on add-on boards.
- Virtual stack library supports stack frame management and multiple return values.
- Virtual heap (vmalloc()) allows allocation of very large data structures.
- System requirements: Huge model C compiler, V8 uses 22-128 Kb core.



Sapiens Software Corporation
236 Mora St. Santa Cruz, CA 95060
408/458-1990

Circle no. 168 on reader service card.

16 BIT

Listing One (Listing continued, text begins on page 110.)

```

{
    /* Nothing after the '\ ' - let the 'blank'
     * section handle it.
     */
    case '\0':
        bstr--;
        subarg--;
        j--;
        break;

    case ' ':
        *bstr = ' ';
        break;

    case '0':
    case '1':
    case '2':
    case '3':
    case '4':
    case '5':
    case '6':
    case '7':
        *bstr = (char) bit_pattern(&subarg);
        break;

    case '\\':
        *bstr = '\\';
        break;

    case 'b':
        *bstr = '\b';
        break;

    case 'f':
        *bstr = '\f';
        break;

    case 'n':
        *bstr = '\n';
        break;

    case 'r':
        *bstr = '\r';
        break;

    case 't':
        *bstr = '\t';
        break;

    case 's':
        *bstr = ' ';
        break;

    default:
        *bstr = *subarg;
        break;
}

else
    *bstr = *subarg; /* No special character handling.*/
}

if (j == STRINGLEN)
    exit_error(11, nullstr);

*bstr = '\0'; /* End of strget.*/
}
#else
/*-----
 * strload -- retrieve the <string> argument from the command line.
 * Escape sequences are treated just as defined in C (except \0,
 * which is an error). One extra escape sequence ('\s') exists in
 * order to handle multiple blanks on a line without bothering to
 * enclose the string in quotes.
 *-----*/
strload(subarg, bstr)
char *subarg;
char *bstr;
{
    extern char *nullstr;
    register int j;

    for (j = 0; *subarg && j < STRINGLEN; bstr++, subarg++, j++)
        if (*subarg == '\\') /* Escape sequences.*/
            switch(++subarg)
            {
                case '0':
                case '1':
                case '2':
                case '3':
                case '4':
                case '5':
                case '6':
                case '7':
                    *bstr = (char) bit_pattern(&subarg);
                    break;

                case '\\':
                    *bstr = '\\';
                    break;

                case 'b':
                    *bstr = '\b';
                    break;
            }
        else
            *bstr++ = *subarg++;
    *bstr = '\0';
}

```


**New
Release!**

SEIDL MAKE UTILITY

Version 2.0

The BEST just got BETTER!

If you're serious about software development, consider the **SEIDL MAKE UTILITY (SMK)**. SMK is not just another copy of the Unix Make. It was specifically designed to deliver features and performance not found in other makes.

✓ **Structured Language** to describe dependencies in a clear, concise and portable manner.

✓ **Rich Command Set** includes parameterized macros, variables, if-then-else, iteration, wild cards, exception cases, macro libraries, interactive statements, environment access, pattern matching and much more!

✓ **Intelligent Analysis** algorithm handles nested include files, library dependencies, and performs consistency tests to detect errors that other makes would blindly ignore.

✓ **Seidl Version Manager** compatibility lets you expand your system into the most comprehensive revision/version control system available.

"SMK is a very good Make indeed. Its major distinction is a truly simple Dependency Definition Language, easy to learn and easy to use... you'll probably bless SMK."

— Sextant, July '86

"SMK offers many unique features. [The error handling facility] is extremely useful if a large number of files must be recompiled."

— Computer Language, June '86

DOS \$99⁹⁵ \$3.50 p&h
Version Only Call for other
Only op systems.

Call Today

1-313-662-8086

Visa/MC/COD Accepted
Dealer Inquiries Invited

SEIDL COMPUTER ENGINEERING

3106 Hilltop Dr., Ann Arbor, MI 48103

```

    case 'f':
        *bstr = '\f';
        break;

    case 'n':
        *bstr = '\n';
        break;

    case 'r':
        *bstr = '\r';
        break;

    case 't':
        *bstr = '\t';
        break;

    case 's':
        *bstr = ' ';
        break;

    default:
        *bstr = *subarg;
        break;
    }

    else
        *bstr = *subarg; /* No special character handling.*/

    if (! -- STRINGLEN)
        exit_error(11, nullstr);

    *bstr = '\0';

}
#endif

/*-----
 * bit_pattern -- Change the \ddd format to a character symbol. It will
 * check to see if there are (at most two) other octal digits
 * present. It does not allow the return of the null character.
 * The pointer *ddd is only incremented by one for each extra
 * digit, because the pointer will be incremented again upon
 * returning from the function.
 *-----*/
bit_pattern(ddd)
char *ddd;
{
    extern char *nullstr;
    int num;

    num = *ddd - '0'; /* Num is octal, otherwise we wouldn't be here.*/

    if (isoctal(*(ddd + 1))) /* Is the next character an octal digit?*/
    {
        num = 8 * num + **ddd - '0';

        if (isoctal(*(ddd + 2))) /* How about this character?*/
            num = 8 * num + ***ddd - '0';
    }

    if (!num)
        exit_error(10, nullstr); /* No \0 allowed.*/

    return(num);
}

/*-----
 * attachf -- Take the lines of <file2>, if any, and attach them
 * to the lines of <file1>, if any. Slip determines how many
 * lines of <file1> (<file2> if negative) are printed before
 * printing the lines from both files together. It is possible to
 * specify some slippage even if the -a or -p flags are present.
 * This is not an error. Attachf is smart enough to skip slip
 * in that case.
 *-----*/
attachf(fp1, fp2, slip, printsingle, printempty)
FILE *fp1, *fp2;
int slip;
Boolean printsingle, printempty;
{
    Boolean notempty;
    register int nxc;

    /* Handle slippage, if any, up to the end of the file.
    */
    for (; slip > 0 && fp1 != NULL; slip--)
    {
        notempty = (nxc = nextc(fp1)) != '\n';

        if (nxc == EOF)
        {
            fp1 = NULL;
            break;
        }

        put_line(fp1);

        if (printsingle && (printempty || notempty))
            printf(strf, bstrng);

        putchar('\n');
    }

    if (slip < 0)
        slip = -slip;

    for (; slip > 0 && fp2 != NULL; slip--)

```

(continued on next page)



SQL Compatible Query System adaptable to any operating environment.

CQL Query System. A subset of the Structured English Query Language (SEQUEL, or SQL) developed by IBM. Linked files, stored views, and nested queries result in a complete query capability. File system interaction isolated in an interface module. Extensive documentation guides user development of interfaces to other record oriented file handlers.

Portable Application Support System

Portable Windowing System. Hardware independent windowing system with borders, attributes, horizontal and vertical scrolling. User can construct interface file for any hardware. Interfaces provided for PC/XT/AT (screen memory interface and BIOS only interface), MS-DOS generic (using ANSI.SYS), Xenix (both with and without using the curses interface), and C-library (no attributes).

Screen I/O, Report, and Form Generation Systems. Field level interface between application programs, the Query System, and the file system. Complete input/output formatting and control, automatic scrolling on screens and automatic pagination on forms, process intervention points. Seven field types: 8-bit unsigned binary, 16 bit signed binary, 16 bit unsigned binary, 32 bit signed binary, monetary (based on 32 bit binary), string, and date.

\$395.00

C Interpreter. Run the interpreter on any hardware and on any operating system. Develops true intermediate code, allowing full C features in an interpreter. User configurable interface to compiler library allows linkage with compiled routines.

**HARDWARE AND FILE SYSTEM
INDEPENDENT**

**KURTZBERG
COMPUTER SYSTEMS**

**41-19 BELL BLVD.
BAYSIDE, N.Y. 11361**

VISA/Master Charge accepted
(718) 229-4540

*C-tree is a trademark of FairCom

IBM, SEQUEL, PC, XT, AT are trademarks of IBM Corp
MS-DOS and Xenix are trademarks of Microsoft Corp
CQL and the CQL Logo are trademarks of Kurtzberg Computer Systems

Circle no. 294 on reader service card.

16 BIT

Listing One (Listing continued, text begins on page 110.)

```

{
    if ((nxtc = nextc(fp2)) == EOF)
    {
        fp2 = NULL;
        break;
    }

    if (printsingl && (printempty || nxtc != '\n'))
        printf(strf, bstring);

    put_line(fp2);
    putchar('\n');
}

/* Paste the lines of each file together.
*/
while (fp1 != NULL && fp2 != NULL)
{
    notempty = (nxtc = nextc(fp1)) != '\n';

    if (nxtc == EOF)
    {
        fp1 = NULL;
        break;
    }

    put_line(fp1);

    if (printempty || notempty || nextc(fp2) != '\n')
        printf(strf, bstring);

    put_line(fp2);

    if (nextc(fp2) == EOF)
    {
        fp2 = NULL;
    }

    putchar('\n');
}

while (fp1 != NULL)
{
    notempty = (nxtc = nextc(fp1)) != '\n';
    put_line(fp1);

    if (nextc(fp1) == EOF)
        fp1 = NULL;

    if (printsingl && (printempty || notempty))
        printf(strf, bstring);

    putchar('\n');
}

while (fp2 != NULL)
{
    if (printsingl && (printempty || nextc(fp2) != '\n'))
        printf(strf, bstring);

    put_line(fp2);

    if (nextc(fp2) == EOF)
        fp2 = NULL;

    putchar('\n');
}

} /* End of attachf.*/

/*-----*
 * put_line -- Get a line, print a line.
 *-----*/
put_line(fp)
FILE *fp;
{
    register int c;

    while((c = getc(fp)) != '\n' && c != EOF)
        putchar(c);

} /* End of put_line.*/

/*-----*
 * nextc -- What is the next character? I realize that there are
 * some routines in some stdio.h files that do this for you, but
 * this is not true of all of them. Hence this function.
 *-----*/
nextc(fp)
FILE *fp;
{
    register int c;

    c = getc(fp);
    ungetc(c, fp);

    return(c);

} /* End of nextc.*/

/*-----*
 * exit_error -- Print out the appropriate error message for the
 * appropriate error, then exit.
 *-----*/
exit_error(errcode, details)
int errcode;
char *details;
{
    extern char *error_msg[];

    fprintf(stderr, error_msg[errcode], program_name, details);
    exit(1);

} /* End of exit_error.*/

```

End Listing

CLEAN SCREEN MACHINE

Data Entry

Menus

Windows

Prototyping

Toolkit

C-scape

■ Total Screen Control

C-scape is a combination screen generator and library of screen I/O functions. Written for C programmers, C-scape brings a fresh approach to the need for an easy-to-learn and use, but truly powerful and flexible screen management tool.

C-scape's kernel is your most powerful ally. Without requiring parameters you'll never use, it allows you to create tailored functions with ease and simplicity. Each key is individually definable. If you know `printf()`, you can use C-scape. C-scape's kernel provides a veritable screen design and construction toolkit to rewrite our functions or to write your own.

■ Most Powerful Prototyping Available

C-scape offers a unique approach to prototyping your software. You may use **Dan Bricklin's Demo Program** to create, edit, and view your screens (you can even capture existing screens from other programs), and then use C-scape's **demo2c** utility to convert each screen to code. You can design each screen with attributes such as colors, menu selections, data entry fields (including type, validation, and field naming), masking, and text, and then automatically convert the entire screen to code.

■ Powerful Function Library

Use C-scape's functions for Lotus-like, pull-down, or your own menu designs, automatic scrolling, pop-up windows (number limited only by RAM), logical colors, help, time and date, yes/no, tickertape fields, secure and protected fields, and many others, to turn your demo into a fully functioning and complete program in a fraction of the time spent coding screens from scratch.

C-scape's extensive library includes just about all the data entry and display functions you'll ever need, including money functions, fully definable borders, and orthogonal field movement (get the latest list by calling for more information). And modifying our functions or writing your own is easy. C-scape adjusts automatically for CGA, EGA, monochrome, and the Hercules Graphics Card Plus in RamFont mode, and optionally writes directly to video memory, so it's flexible and fast.

■ Bridges to Power

C-scape includes examples of how to bridge to other powerful tools such as **c-tree** and **db_VISTA**. You'll be integrating demos to dictionaries to file handlers and database managers in no time. You can even use C-scape to provide the screen design for AI applications, using TransLisp Plus and other packages that support calls to C.

■ Clean, Complete Documentation

C-scape's documentation is a clear example of how to write for programmers in a hurry. A short introduction uses helpful examples to explain the C-scape design. Each function is documented separately. An index makes reference easy, and a quick-reference card provides a synopsis of each function.

■ Source Code Included/Portable/No Royalties/No Runtime License

Providing source code at no additional cost gives you the freedom to modify existing functions without raising cost as a barrier. The source code includes all the low level routines you might need to port C-scape to an unsupported machine or compiler. Speaking of barriers, you pay *no royalties or runtime license fees*, either.

■ Toll Free Support and Bulletin Board

To make your job even easier, we provide technical support (toll free), and access to our 24-hour Bulletin Board.

■ Easy Prices/Risk-Free Terms

Try C-scape for 30 days. If you are not satisfied, return it for a refund. When you register, we send you source code. Order C-scape today, or call toll free for more information. See why some very major groups are standardizing on C-scape.

C-scape (Lattice/Microsoft/others)

Only \$179

C-scape with Dan Bricklin's Demo Program

\$249

Please add \$3 for shipping; Massachusetts orders add 5% sales tax.

Circle no. 342 on reader service card.



CALL TODAY!

617-491-7311

800-233-3733

Oakland Group, Inc. 

675 Massachusetts Avenue, Cambridge, MA 02139-3309

Get a Grip on Assembly Language.

The award winning
Visible Computer:
8088.



The Visible Computer is a book and software combination for mastering the elusive skills of assembly language. PC Tech Journal took one look and made it their September '85 "Program of the Month."

It's an animated simulation of the PC's microprocessor that lets you see with your own eyes how assembly language works. You'll be using it as a debugging tool for years to come.

It's a tutorial. A lot of people think the 350 page manual is the best book on assembly language ever written.

It's 45 demonstration programs you'll execute with the simulator, from simple register loads to advanced programs that manipulate interrupts and perform file I/O. And what you'll learn applies to all 86 family processors, including the 80186 and 80286. **\$79.95** not copy protected

The Visible Computer for IBM PC/XT/AT and true compatibles. If your dealer doesn't have it, order direct: Software Masters, 2714 Finfeather, Bryan, TX, 77801. (409) 822-9490. Please include \$3.00 shipping. Bank cards accepted.

Circle no. 347 on reader service card.



TVC takes you inside the
processor as it executes programs.

Software Masters™

STRUCTURED PROGRAMMING

Listing One (Text begins on page 120.)

Listing 1. CHANGE.BAS Utility to search/replace text in a number of files.

```

1000 ' Batch Find/Replace Utility Version 1.0 10/29/86
1005 ' IBM PC BASICA version 2 or later
1010 ' Copyright (c) 1987 Namir Clement Shammas
1020 DEFINT A-Z
1030 DIM FILENAMES$(20),STRNG$(30),REPLACE$(30),REPLACES$(30),L$(500)
1040 TRUE = 1
1050 FALSE = 0
1060 MAX.LINES = 500 ' Current maximum number of lines read from a file
1900 CLS
1910 TS = "BATCH FILE FIND/REPLACE PROGRAM" : GOSUB 8000
1920 PRINT
1930 TS = "VERSION 1.0" : GOSUB 8000
1940 PRINT : PRINT
2000 GOSUB 5000 ' Get filenames
2010 GOSUB 6000 ' Get strings
2030 FOR IFILE = 1 TO NUM.FILES
2060 GOSUB 7000 ' Read text lines from file
2070 FOR I = 1 TO NUM.STRINGS
2080 FOUND = FALSE
2090 FOR J = 1 TO NUM.LINES
2100 PTR = INSTR(L$(J),STRNG$(I))
2110 WHILE PTR > 0
2120 IF (FOUND = TRUE) THEN 2150
2130 FOUND = TRUE
2140 LPRINT "KEYWORD : ";STRNG$(I)
2150 BS = STR$(J) + ":"
2155 OFFSET = LEN(BS)
2160 LPRINT J;"":L$(J)
2170 LPRINT SPC(PTR+OFFSET);""
2180 IF (REPLACE(I) = FALSE) THEN 2240
2190 FIRST$ = ""
2200 IF PTR > 1 THEN FIRST$ = MID$(L$(J),1,(PTR-1))
2210 LAST$ = ""
2220 IF (PTR+LEN(STRNG$(I))) => LEN(L$(J)) THEN 2230
2230 LAST$ = MID$(L$(J),(PTR+LEN(STRNG$(I))))
2240 L$(J) = FIRST$ + REPLACE$(I) + LAST$
2250 LPRINT "BECOMES" : LPRINT
2260 LPRINT J;"":L$(J) : LPRINT : LPRINT
2270 PTR = INSTR(PTR+1,L$(J),STRNG$(I))
2280 WEND
2290 NEXT J
2300 NEXT I
2310 GOSUB 9000 ' Write file back
2320 LPRINT : LPRINT
2330 NEXT IFILE
2340 LPRINT CHR$(140) ' FORM FEED
3000 END '-----
5000 ' Subroutine to input filenames from the keyboard
5010 NUM.FILES = 0
5020 WHILE NUM.FILES <= 0
5030 INPUT "Enter number of files ";NUM.FILES
5040 PRINT
5050 WEND
5060 FOR I = 1 TO NUM.FILES
5070 PRINT "Enter filename # ";I;" ";
5080 INPUT FILENAMES(I) : PRINT
5090 IF FILENAMES(I) = "" THEN 5070
5100 NEXT I
5110 RETURN
6000 ' Subroutines to input search/replace strings
6010 NUM.STRINGS = 0
6020 WHILE NUM.STRINGS <= 0
6030 INPUT "Enter number of search/replace strings ";NUM.STRINGS
6040 PRINT
6050 WEND
6060 FOR I = 1 TO NUM.STRINGS
6065 REPLACES$(I) = ""
6070 PRINT : PRINT "For string # ";I
6080 INPUT "Enter string ";STRNG$(I)
6090 INPUT "Replace Find ";AS
6100 IF (INSTR("Rr",MID$(AS,1,1)) = 0) THEN REPLACE(I) =
FALSE ELSE REPLACE(I) = TRUE
6110 IF REPLACE(I) = FALSE THEN 6125
6120 INPUT "Enter replacement string ";REPLACES$(I)
6125 PRINT
6130 NEXT I
6140 RETURN
7000 ' Subroutines to read text lines
7003 LPRINT "PROCESSING FILE : ";FILENAMES(IFILE)

```



```

7006 OPEN "I",1,FILENAME$(IFILE)
7010 NUM.LINES = 0
7020 WHILE (NOT EOF(1)) AND (NUM.LINES <= MAX.LINES)
7030     NUM.LINES = NUM.LINES + 1
7040     LINE INPUT#1,L$(NUM.LINES)
7050 WEND
7060 CLOSE #1
7070 RETURN
8000 ' Subroutine to center a message
8010 PRINT SPC(40 - LEN(T$)/2);T$
8020 RETURN
9000 'Subroutine to write the updated file
9010 OPEN "O",1,FILENAME$(IFILE)
9020 FOR I = 1 TO NUM.LINES
9030     PRINT#1,L$(I)
9040 NEXT I
9050 CLOSE#1
9060 RETURN

```

End Listing One

Listing Two

Listing 2. CHNG1.TRU the version of True BASIC CHANGE.BAS produced by the BASIC-Converter.

```

10 ! This program converted from the Microsoft Advanced Basic
11 ! language on the IBM PC to the True BASIC language.
12 !
13 ! Converter copyright (c) 1985 by:
14 !     True BASIC, Inc.
15 !     Hanover, NH 03755
16 !     All rights reserved.
17 !
18 ! True BASIC makes no warranty, expressed or implied, that
19 ! this converted program is a precise and accurate equivalent
20 ! of the original BasicA program. This conversion is provided
21 ! only as an aid to a complete conversion by the owner of the
22 ! program being converted.
23 !
24 LIBRARY "deflib"
25 DECLARE DEF csrlin, oef, fre, hex$, inkey$, loc, lof
26 DECLARE DEF mki$, mks$, cvi, cvs, oct$, csr_pos, val_a, err, erl
27
28 DEF Eof (f)
29     IF end #f then LET eof = -1 else LET eof = 0
30 END DEF
31
32 DEF Loc (f)
33     ASK #f: record T_ARG1
34     LET t_arg1 = -int(-(t_arg1-1)/128)
35     IF t_arg1 = 0 then let loc = 1 else let loc = t_arg1
36 END DEF
37
38 DEF Lof (f)
39     ASK #f: filesize T_ARG1
40     LET lof = t_arg1
41 END DEF
42
43 OPTION BASE 0
44
1000 ! Batch Find/Replace Utility Version 1.0 10/29/86
1005 ! IBM PC             BASICA version 2 or later
1010 ! Copyright (c) 1987  Namir Clement Shammas
1020 !  defint A-Z
1030 dim filename$(20), strng$(30), replace(30), replace$(30), l$(500)
1040 let true = 1
1050 let false = 0
1060 let max_lines = 500    ! Current maximum number of lines read from a file
1900 clear
1910 let t$ = "BATCH FILE FIND/REPLACE PROGRAM"
1911 gosub 8000
1920 print
1930 let t$ = "VERSION 1.0"
1931 gosub 8000
1940 print
1941 print
1945 OPEN #9 : PRINTER
2000 gosub 5000    ! Get filenames
2010 gosub 6000    ! Get strings
2030 for ifile = 1 to num_files
2060 gosub 7000    ! Read text lines from file
2070 for i = 1 to num_strings

```

(continued on next page)

**MAKE YOUR PC
SEEM LIKE AN AT!**

**MAKE YOUR AT
SEEM LIKE A
DREAM MACHINE!**

**ANSI-tm
CONSOLE**

The Integrated Console Utility™
**FAST, POWERFUL
ANSI.SYS REPLACEMENT**

For the IBM-PC, AT, and clones

**New Version 2.00 is MUCH FASTER!
Now blink free scrolling on CGA!**

Now uses EMS/EEMS for Scroll Recall
New Menu Program for Changing Options

**GET A BOX FULL OF UTILITIES!
MAKE LIFE EASIER FOR ONLY \$75!**

- Speed up your screenwriting 2-6x
- Extend your ANSI.SYS to full VT100
- Add many more escape sequences
- Scroll lines back onto screen
- Save scrolled lines into a file
- Add zip to your cursor keys
- Free your eyes from scroll blinking
- Easy installation
- Get a 43 line screen w/EGA
- Get a 50 line screen w/CGA
- No more annoying typeahead beep
- Prevent screen phosphor burnin
- Control many programs' use of color
- Generate breakpts from keyboard
- Shorten that annoying bell
- Over 50 other useful options

*"The psychological difference is
astounding"*
—Lotus June 85 pg 8.

*"So many handy functions rolled into
one unobtrusive package"*
—PC-World Feb 86 pg 282.

*"The support provided by the
publishers is extraordinary"*
—Capital PC Monitor May 86 pg 25.

*"... the best choice for improving your
console..."*
—Capital PC Monitor June 86 pg 26.

460p Manual (w/slip case) & disks \$75.

**Satisfaction Guaranteed!
Order Yours Today!**

HERSEY MICRO CONSULTING
Box 8276, Ann Arbor, MI 48107
(313) 994-3259 VISA/MC/Amex

DEALER INQUIRIES INVITED



Circle no. 280 on reader service card.

function libraries
disassemblers
compilers
text editors
text filters
communications support
text formatters
interpreters
bulletin boards
CO routines
compiler compilers
window packages
mailers
games
routines
math packages
link editors
languages
cross compilers
pre-processors
function libraries
disassemblers
compilers
text editors

The
C Users' Group
Library

A Directory
of Public Domain
C Source Code

Send \$10
for Directory. Write
or call for more details
on over 100 volumes of
Public Domain C Source
Code.

The C Users' Group
PO Box 97
McPherson, KS 67460
(316) 241-1065

Circle no. 181 on reader service card.

**DISK FORMAT
CONVERSION**

PC-DOS program
lets your PC
Read/Write/Format
over 300 formats

XENOCOPY-PC™

by Fred Cisin

\$79.95 + \$5.00 S/H Sales Tax if CA.



Upgrades available from previous versions

Ask about FREE CP/M emulator! ➡

To Order Contact:

XENOSOFT™

1454 Sixth Street, Berkeley, CA 94710

 (415) 525-3113 

Circle no. 225 on reader service card.

**Enhance Your Turbo
Pascal™ Programming
with
TURBO-JET**

- Ultra Fast Screen Read and Display
- Advanced String and Numeric Formatting
- Advanced File and Keyboard Handling
- Subdirectory Utilities
- Over 100 Files Included!

Pascal Source Code included with all Routines
Routines Crafted in Assembly Language
No Royalties for Program Use
Give Programs a Professional Look
Don't Pay More For Less!
Dealer Inquiries Invited

TURBO-JET, Only \$39.95

Add \$3.00 for Postage & Handling

NY Residents add sales tax

TOC Business Solutions, Inc.

P.O. Box 129

Old Westbury, N.Y. 11568

MC/VISA (516) 795-2800

Circle no. 345 on reader service card.

STRUCTURED PROGRAMMING

Listing Two (Listing continued, text begins on page 120.)

```

2080 let found = false
2090 for j = 1 to num_lines
2100 let ptr = pos(l$(j),strng$(i))
2110 do while ptr > 0
2120 if (found = true) then goto 2150
2130 let found = true
2140 print #9 : "KEYWORD : ";STRNG$(I)
2150 let b$ = str$(j) & ":"
2153 let offset = round(len(b$))
2155 print #9 : J;"":L$(J)
2160 print #9 : REPEAT$( " ", (PTR-OFFSET+1));"^" ! Manual fix on this line
2170 if (replace(i) = false) then goto 2240
2180 let first$ = ""
2190 if ptr > 1 then let first$ = (l$(j))[1:1+(ptr-1)-1]
2200 let last$ = ""
2210 if (ptr+len(strng$(i))) => len(l$(j)) then goto 2230
2220 let last$ = (l$(j))[(ptr+len(strng$(i))):maxnum]
2230 let l$(j) = first$ & replace$(i) & last$
2231 print #9 : "BECOMES"
2232 print #9 :
2233 print #9 : J;"":L$(J)
2234 print #9 :
2235 print #9 :
2240 let ptr = pos(l$(j),strng$(i),ptr+1)
2250 loop
2260 next j
2270 next i
2275 gosub 9000 ! Write file back
2277 print #9 :
2278 print #9 :
2280 next ifile
2290 print #9 : CHR$(140) ! FORM FEED
3000 stop !-----
5000 ! Subroutine to input filenames from the keyboard
5010 let num_files = 0
5020 do while num_files <= 0
5030 input prompt "Enter number of files ": num_files
5040 print
5050 loop
5060 for i = 1 to num_files
5070 print "Enter filename # "; i; " "
5080 input filename$(i)
5081 print
5090 if filename$(i) = "" then goto 5070
5100 next i
5110 return
6000 ! Subroutines to input search/replace strings
6010 let num_strings = 0
6020 do while num_strings <= 0
6030 input prompt "Enter number of search/replace strings ": num_strings
6040 print
6050 loop
6060 for i = 1 to num_strings
6065 let replace$(i) = ""
6070 print
6071 print "For string # "; i
6080 input prompt " Enter string ": strng$(i)
6090 input prompt " R)eplace F)ind ": a$
6100 if (pos("Rr", (a$)[1:1]) = 0) then let replace(i) =
        false else let replace(i) = true
6110 if replace(i) = false then goto 6125
6120 input prompt " Enter replacement string ": replace$(i)
6125 print
6130 next i
6140 return
7000 ! Subroutines to read text lines
7003 print #9 : "PROCESSING FILE : ";FILENAME$(IFILE)
7006 open #1: name filename$(ifile), access input, create old
7010 let num_lines = 0
7020 do while ((not eof(1) <> 0)) and (num_lines <= max_lines)
7030 let num_lines = num_lines+1
7040 line input #1:l$(num_lines) ! Manual fix here
7050 loop
7060 close #1
7070 return
8000 ! Subroutine to center a message
8010 print tab(csr_pos+40-len(t$)/2); t$
8020 return
9000 !Subroutine to write the updated file
9010 open #1: name filename$(ifile), access output, create old
9015 erase #1 ! this line is added

```


CLEAN SCREEN MACHINE

Data Entry

Menus

Windows

Prototyping

Toolkit

C-scape

■ Total Screen Control

C-scape is a combination screen generator and library of screen I/O functions. Written for C programmers, C-scape brings a fresh approach to the need for an easy-to-learn and use, but truly powerful and flexible screen management tool.

C-scape's kernel is your most powerful ally. Without requiring parameters you'll never use, it allows you to create tailored functions with ease and simplicity. Each key is individually definable. If you know `printf()`, you can use C-scape. C-scape's kernel provides a veritable screen design and construction toolkit to rewrite our functions or to write your own.

■ Most Powerful Prototyping Available

C-scape offers a unique approach to prototyping your software. You may use **Dan Bricklin's Demo Program** to create, edit, and view your screens (you can even capture existing screens from other programs), and then use C-scape's **demo2c** utility to convert each screen to code.

You can design each screen with attributes such as colors, menu selections, data entry fields (including type, validation, and field naming), masking, and text, and then automatically convert the entire screen to code.

■ Powerful Function Library

Use C-scape's functions for Lotus-like, pull-down, or your own menu designs, automatic scrolling, pop-up windows (number limited only by RAM), logical colors, help, time and date, yes/no, tickertape fields, secure and protected fields, and many others, to turn your demo into a fully functioning and complete program in a fraction of the time spent coding screens from scratch.

C-scape's extensive library includes just about all the data entry and display functions you'll ever need, including money functions, fully definable borders, and orthogonal field movement (get the latest list by calling for more information). And modifying our functions or writing your own is easy. C-scape adjusts automatically for CGA, EGA, monochrome, and the Hercules Graphics Card Plus in RamFont mode, and optionally writes directly to video memory, so it's flexible and fast.

■ Bridges to Power

C-scape includes examples of how to bridge to other powerful tools such as **c-tree** and **db_VISTA**. You'll be integrating demos to dictionaries to file handlers and database managers in no time. You can even use C-scape to provide the screen design for AI applications, using TransLisp Plus and other packages that support calls to C.

■ Clean, Complete Documentation

C-scape's documentation is a clear example of how to write for programmers in a hurry. A short introduction uses helpful examples to explain the C-scape design. Each function is documented separately. An index makes reference easy, and a quick-reference card provides a synopsis of each function.

■ Source Code Included/Portable/No Royalties/No Runtime License

Providing source code at no additional cost gives you the freedom to modify existing functions without raising cost as a barrier. The source code includes all the low level routines you might need to port C-scape to an unsupported machine or compiler. Speaking of barriers, you pay *no royalties or runtime license fees*, either.

■ Toll Free Support and Bulletin Board

To make your job even easier, we provide technical support (toll free), and access to our 24-hour Bulletin Board.

■ Easy Prices/Risk-Free Terms

Try C-scape for 30 days. If you are not satisfied, return it for a refund. When you register, we send you source code. Order C-scape today, or call toll free for more information. See why some very major groups are standardizing on C-scape.

C-scape (Lattice/Microsoft/others)

Only \$179

C-scape with Dan Bricklin's Demo Program

\$249

Please add \$3 for shipping; Massachusetts orders add 5% sales tax.

Circle no. 342 on reader service card.

Oakland Group, Inc. 

675 Massachusetts Avenue, Cambridge, MA 02139-3309



CALL TODAY!

617-491-7311

800-233-3733

Get a Grip on Assembly Language.

The award winning
Visible Computer:
8088.



The Visible Computer is a book and software combination for mastering the elusive skills of assembly language. PC Tech Journal took one look and made it their September '85 "Program of the Month."


It's an animated simulation of the PC's microprocessor that lets you see with your own eyes how assembly language works. You'll be using it as a debugging tool for years to come.

It's a tutorial. A lot of people think the 350 page manual is the best book on assembly language ever written.

It's 45 demonstration programs you'll execute with the simulator, from simple register loads to advanced programs that manipulate interrupts and perform file I/O. And what you'll learn applies to all 86 family processors, including the 80186 and 80286. **\$79.95** not copy protected

The Visible Computer for IBM PC/XT/AT and true compatibles. If your dealer doesn't have it, order direct: Software Masters, 2714 Finfeather, Bryan, TX, 77801. (409) 822-9490. Please include \$3.00 shipping. Bank cards accepted.

Circle no. 347 on reader service card.



TVC takes you inside the processor as it executes programs.

Software Masters™

STRUCTURED PROGRAMMING

Listing One (Text begins on page 120.)

Listing 1. CHANGE.BAS Utility to search/replace text in a number of files.

```

1000 ' Batch Find/Replace Utility Version 1.0 10/29/86
1005 ' IBM PC          BASICA version 2 or later
1010 ' Copyright (c) 1987  Namir Clement Shammass
1020 DEFINT A-Z
1030 DIM FILENAME$(20),STRNG$(30),REPLACE(30),REPLACES$(30),L$(500)
1040 TRUE  = 1
1050 FALSE = 0
1060 MAX.LINES = 500 ' Current maximum number of lines read from a file
1900 CLS
1910 TS = "BATCH FILE FIND/REPLACE PROGRAM" : GOSUB 8000
1920 PRINT
1930 TS = "VERSION 1.0" : GOSUB 8000
1940 PRINT : PRINT
2000 GOSUB 5000 ' Get filenames
2010 GOSUB 6000 ' Get strings
2030 FOR IFILE = 1 TO NUM.FILES
2060     GOSUB 7000 ' Read text lines from file
2070     FOR I = 1 TO NUM.STRINGS
2080         FOUND = FALSE
2090         FOR J = 1 TO NUM.LINES
2100             PTR = INSTR(L$(J),STRNG$(I))
2110             WHILE PTR > 0
2120                 IF (FOUND = TRUE) THEN 2150
2130                 FOUND = TRUE
2140                 LPRINT "KEYWORD : ";STRNG$(I)
2150                 B$ = STR$(J) + ":"
2153                 OFFSET = LEN(B$)
2155                 LPRINT J;"":L$(J)
2160                 LPRINT SPC(PTR+OFFSET);""
2170                 IF (REPLACE(I) = FALSE) THEN 2240
2180                 FIRST$ = ""
2190                 IF PTR > 1 THEN FIRST$ = MID$(L$(J),1,(PTR-1))
2200                 LAST$ = ""
2210                 IF (PTR+LEN(STRNG$(I))) => LEN(L$(J)) THEN 2230
2220                 LAST$ = MID$(L$(J),(PTR+LEN(STRNG$(I))))
2230                 L$(J) = FIRST$ + REPLACES(I) + LAST$
2231                 LPRINT "BECOMES" : LPRINT
2233                 LPRINT J;"":L$(J) : LPRINT : LPRINT
2240                 PTR = INSTR(PTR+1,L$(J),STRNG$(I))
2250             WEND
2260         NEXT J
2270     NEXT I
2275     GOSUB 9000 ' Write file back
2277     LPRINT : LPRINT
2280 NEXT IFILE
2290 LPRINT CHR$(140) ' FORM FEED
3000 END '-----
5000 ' Subroutine to input filenames from the keyboard
5010 NUM.FILES = 0
5020 WHILE NUM.FILES <= 0
5030     INPUT "Enter number of files ";NUM.FILES
5040     PRINT
5050 WEND
5060 FOR I = 1 TO NUM.FILES
5070     PRINT "Enter filename # ";I;" ";
5080     INPUT FILENAME$(I) : PRINT
5090     IF FILENAME$(I) = "" THEN 5070
5100 NEXT I
5110 RETURN
6000 ' Subroutines to input search/replace strings
6010 NUM.STRINGS = 0
6020 WHILE NUM.STRINGS <= 0
6030     INPUT "Enter number of search/replace strings ";NUM.STRINGS
6040     PRINT
6050 WEND
6060 FOR I = 1 TO NUM.STRINGS
6065     REPLACES$(I) = ""
6070     PRINT : PRINT "For string # ";I
6080     INPUT "    Enter string ";STRNG$(I)
6090     INPUT "    Replace Find ";AS
6100     IF (INSTR("Rr",MID$(AS,1,1)) = 0) THEN REPLACE(I) =
        FALSE ELSE REPLACE(I) = TRUE
6110     IF REPLACE(I) = FALSE THEN 6125
6120     INPUT "    Enter replacement string ";REPLACES$(I)
6125 PRINT
6130 NEXT I
6140 RETURN
7000 ' Subroutines to read text lines
7003 LPRINT "PROCESSING FILE : ";FILENAME$(IFILE)

```



```

7006 OPEN "I",1,FILENAME$(IFILE)
7010 NUM.LINES = 0
7020 WHILE (NOT EOF(1)) AND (NUM.LINES <= MAX.LINES)
7030     NUM.LINES = NUM.LINES + 1
7040     LINE INPUT#1,LS(NUM.LINES)
7050 WEND
7060 CLOSE #1
7070 RETURN
8000 ' Subroutine to center a message
8010 PRINT SPC(40 - LEN(T$)/2);T$
8020 RETURN
9000 'Subroutine to write the updated file
9010 OPEN "O",1,FILENAME$(IFILE)
9020 FOR I = 1 TO NUM.LINES
9030     PRINT#1,LS(I)
9040 NEXT I
9050 CLOSE#1
9060 RETURN

```

End Listing One

Listing Two

Listing 2. CHNG1.TRU the version of True BASIC CHANGE.BAS produced by the BASIC-Converter.

```

10 ! This program converted from the Microsoft Advanced Basic
11 ! language on the IBM PC to the True BASIC language.
12 !
13 ! Converter copyright (c) 1985 by:
14 !     True BASIC, Inc.
15 !     Hanover, NH 03755
16 !     All rights reserved.
17 !
18 ! True BASIC makes no warranty, expressed or implied, that
19 ! this converted program is a precise and accurate equivalent
20 ! of the original BasicA program. This conversion is provided
21 ! only as an aid to a complete conversion by the owner of the
22 ! program being converted.
23 !
24 LIBRARY "deflib"
25 DECLARE DEF csrlin, oef, fre, hex$, inkey$, loc, lof
26 DECLARE DEF mki$, mkss$, cvi, cvs, oct$, csr_pos, val_a, err, erl
27
28 DEF Eof (f)
29     IF end #f then LET eof = -1 else LET eof = 0
30 END DEF
31
32 DEF Loc (f)
33     ASK #f: record T_ARG1
34     LET t_arg1 = -int(-(t_arg1-1)/128)
35     IF t_arg1 = 0 then let loc = 1 else let loc = t_arg1
36 END DEF
37
38 DEF Lof (f)
39     ASK #f: filesize T_ARG1
40     LET lof = t_arg1
41 END DEF
42
43 OPTION BASE 0
44
1000 ! Batch Find/Replace Utility Version 1.0 10/29/86
1005 ! IBM PC BASICA version 2 or later
1010 ! Copyright (c) 1987 Namir Clement Shammass
1020 ! defint A-Z
1030 dim filenames$(20), strng$(30), replace(30), replace$(30), l$(500)
1040 let true = 1
1050 let false = 0
1060 let max_lines = 500 ! Current maximum number of lines read from a file
1900 clear
1910 let t$ = "BATCH FILE FIND/REPLACE PROGRAM"
1911 gosub 8000
1920 print
1930 let t$ = "VERSION 1.0"
1931 gosub 8000
1940 print
1941 print
1945 OPEN #9 : PRINTER
2000 gosub 5000 ! Get filenames
2010 gosub 6000 ! Get strings
2030 for ifile = 1 to num_files
2060 gosub 7000 ! Read text lines from file
2070 for i = 1 to num_strings

```

(continued on next page)

**MAKE YOUR PC
SEEM LIKE AN AT!**

**MAKE YOUR AT
SEEM LIKE A
DREAM MACHINE!**

**ANSI-tm
CONSOLE**

The Integrated Console Utility™
**FAST, POWERFUL
ANSI.SYS REPLACEMENT**

For the IBM-PC, AT, and clones

New Version 2.00 is MUCH FASTER!
Now blink free scrolling on CGA!

Now uses EMS/EEMS for Scroll Recall
New Menu Program for Changing Options

GET A BOX FULL OF UTILITIES!
MAKE LIFE EASIER FOR ONLY \$75!

- Speed up your screenwriting 2-6x
- Extend your ANSI.SYS to full VT100
- Add many more escape sequences
- Scroll lines back onto screen
- Save scrolled lines into a file
- Add zip to your cursor keys
- Free your eyes from scroll blinking
- Easy installation
- Get a 43 line screen w/EGA
- Get a 50 line screen w/CGA
- No more annoying typeahead beep
- Prevent screen phosphor burnin
- Control many programs' use of color
- Generate breakpaks from keyboard
- Shorten that annoying bell
- Over 50 other useful options

*"The psychological difference is
astonishing"*
—Lotus June 85 pg 8.

*"So many handy functions rolled into
one unobtrusive package"*
—PC-World Feb 86 pg 282.

*"The support provided by the
publishers is extraordinary"*
—Capital PC Monitor May 86 pg 25.

*"... the best choice for improving your
console..."*
—Capital PC Monitor June 86 pg 26.

460p Manual (w/slip case) & disks \$75.

Satisfaction Guaranteed!
Order Yours Today!

HERSEY MICRO CONSULTING
Box 8276, Ann Arbor, MI 48107
(313) 994-3259 VISA/MC/Amex

DEALER INQUIRIES INVITED



Circle no. 280 on reader service card.

function libraries
disassemblers
compilers
text editors
text filters
communications support
text formatters
interpreters
bulletin boards
on-routines
compiler compilers
window packages
assemblers
games
tutorials
main packages
link editors
languages
cross compilers
dfe-processors
function libraries
disassemblers
compilers
text editors

The Users' Group Library

A Directory
of Public Domain
C Source Code

Send \$10
for Directory. Write
or call for more details
on over 100 volumes of
Public Domain C Source
Code.

The C Users' Group
PO Box 97
McPherson, KS 67460
(316) 241-1065

Circle no. 181 on reader service card.

**DISK FORMAT
CONVERSION**

PC-DOS program
lets your PC
Read/Write/Format
over 300 formats

XENOCOPY-PC™

by Fred Oslin

\$79.95 + \$5.00 S/H Sales Tax if CA.

Upgrades available from previous versions

Ask about **FREE** CP/M emulator! ➔

To Order Contact:

XENOSOFT™

1454 Sixth Street, Berkeley, CA 94710



(415) 525-3113



Circle no. 225 on reader service card.

**Enhance Your Turbo
Pascal™ Programming
with
TURBO-JET**

- Ultra Fast Screen Read and Display
- Advanced String and Numeric Formatting
- Advanced File and Keyboard Handling
- Subdirectory Utilities
- Over 100 Files Included!

Pascal Source Code included with all Routines
Routines Crafted in Assembly Language
No Royalties for Program Use
Give Programs a Professional Look
Don't Pay More For Less!
Dealer Inquiries Invited

TURBO-JET, Only \$39.95

Add \$3.00 for Postage & Handling

NY Residents add sales tax

TOC Business Solutions, Inc.

P.O. Box 129

Old Westbury, N.Y. 11568

MC/VISA (516) 795-2800

Circle no. 345 on reader service card.

STRUCTURED PROGRAMMING

Listing Two (Listing continued, text begins on page 120.)

```

2080 let found = false
2090 for j = 1 to num_lines
2100 let ptr = pos(l$(j), string$(i))
2110 do while ptr > 0
2120 if (found = true) then goto 2150
2130 let found = true
2140 print #9 : "KEYWORD : "; string$(i)
2150 let b$ = str$(j) & ":"
2153 let offset = round(len(b$))
2155 print #9 : J; ":"; string$(i)
2160 print #9 : REPEAT$( " ", (PTR+OFFSET+1)); "^" ! Manual fix on this line
2170 if (replace(i) = false) then goto 2240
2180 let first$ = ""
2190 if ptr > 1 then let first$ = (l$(j))[1:1+(ptr-1)-1]
2200 let last$ = ""
2210 if (ptr+len(string$(i))) => len(l$(j)) then goto 2230
2220 let last$ = (l$(j))[ptr+len(string$(i));maxnum]
2230 let l$(j) = first$ & replace$(i) & last$
2231 print #9 : "BECOMES"
2232 print #9 :
2233 print #9 : J; ":"; string$(i)
2234 print #9 :
2235 print #9 :
2240 let ptr = pos(l$(j), string$(i), ptr+1)
2250 loop
2260 next j
2270 next i
2275 gosub 9000 ! Write file back
2277 print #9 :
2278 print #9 :
2280 next ifile
2290 print #9 : CHR$(140) ! FORM FEED
3000 stop !-----
5000 ! Subroutine to input filenames from the keyboard
5010 let num_files = 0
5020 do while num_files <= 0
5030 input prompt "Enter number of files ": num_files
5040 print
5050 loop
5060 for i = 1 to num_files
5070 print "Enter filename # "; i; " ";
5080 input filename$(i)
5081 print
5090 if filename$(i) = "" then goto 5070
5100 next i
5110 return
6000 ! Subroutines to input search/replace strings
6010 let num_strings = 0
6020 do while num_strings <= 0
6030 input prompt "Enter number of search/replace strings ": num_strings
6040 print
6050 loop
6060 for i = 1 to num_strings
6065 let replace$(i) = ""
6070 print
6071 print "For string # "; i
6080 input prompt " Enter string ": string$(i)
6090 input prompt " Replace Find ": a$
6100 if (pos("Rr", (a$)[1:1]) = 0) then let replace(i) =
        false else let replace(i) = true
6110 if replace(i) = false then goto 6125
6120 input prompt " Enter replacement string ": replace$(i)
6125 print
6130 next i
6140 return
7000 ! Subroutines to read text lines
7003 print #9 : "PROCESSING FILE : "; filename$(ifile)
7006 open #1: name filename$(ifile), access input, create old
7010 let num_lines = 0
7020 do while ((not eof(1) <> 0)) and (num_lines <= max_lines)
7030 let num_lines = num_lines+1
7040 line input #1:l$(num_lines) ! Manual fix here
7050 loop
7060 close #1
7070 return
8000 ! Subroutine to center a message
8010 print tab(csr_pos+40-len(t$)/2); t$
8020 return
9000 ! Subroutine to write the updated file
9010 open #1: name filename$(ifile), access output, create old
9015 erase #1 ! this line is added

```



```

9020 for i = 1 to num_lines
9030 print #1:1$(i)
9040 next i
9050 close #1
9060 return
9061 end

```

End Listing Two

Listing Three

Listing 3. CHNG2.TRU the True BASIC version of CHANGE.BAS that is translated manually.

```

! Batch Find/Replace Utility Version 1.0 10/29/86
! IBM PC True BASIC version 1
! Copyright (c) 1987 Namir Clement Shammass
DIM FILENAMES$(20), STRNG$(30), REPLACE$(30), L$(500)
LET TRUE = 1
LET FALSE = 0
LET MAX_LINES = 500 ! Current maximum number of lines read from a file
CLEAR ! Clear screen
CALL CenterText("BATCH FILE FIND/REPLACE PROGRAM")
PRINT
CALL CenterText("VERSION 1.0")
PRINT
PRINT
OPEN #9 : PRINTER
CALL GetFile(FILENAMES$, NUM_FILES) ! Get filenames
CALL GetStrings(STRNG$, REPLACE$, REPLACE, NUM_STRINGS) ! Get strings
FOR IFILE = 1 TO NUM_FILES
    CALL ReadLines(L$, FILENAMES$, IFILE, NUM_LINES) ! Read text lines from file
    FOR I = 1 TO NUM_STRINGS
        LET FOUND = FALSE
        FOR J = 1 TO NUM_LINES
            LET PTR = POS(L$(J), STRNG$(I))
            DO WHILE PTR > 0
                IF (FOUND = FALSE) THEN
                    LET FOUND = TRUE
                    PRINT #9 : "KEYWORD : "; STRNG$(I)
                END IF
                LET B$ = STR$(J) & ":" ! Use & to concatenate strings
                LET OFFSET = LEN(B$)
                PRINT #9 : J; ":"; L$(J)
                PRINT #9 : REPEATS(" ", (PTR-OFFSET+1)); "^"
                IF (REPLACE(I) = TRUE) THEN
                    LET FIRST$ = ""
                    IF PTR > 1 THEN LET FIRST$ = L$(J)[1:(PTR-1)]
                    LET LAST$ = ""
                    IF (PTR+LEN(STRNG$(I))) < LEN(L$(J)) THEN
                        LET LAST$ = L$(J)[(PTR+LEN(STRNG$(I))):LEN(L$(J))]
                    END IF
                    LET L$(J) = FIRST$ & REPLACE$(I) & LAST$
                    PRINT #9 : "BECOMES"
                    PRINT #9 :
                    PRINT #9 : J; ":"; L$(J)
                    PRINT #9 :
                    PRINT #9 :
                END IF
                LET PTR = POS(L$(J), STRNG$(I), (PTR+1))
            LOOP
        NEXT J
    NEXT I
    CALL WriteLines(L$, FILENAMES$, REPLACE, IFILE, NUM_LINES)
    ! Write file back
    PRINT #9 :
    PRINT #9 :
NEXT IFILE
PRINT #9 : CHR$(140) ! FORM FEED

SUB GetFile(FILENAMES$, NUM_FILES)
! Subroutine to input filenames from the keyboard
LET NUM_FILES = 0
DO WHILE NUM_FILES <= 0
    INPUT PROMPT "Enter number of files ": NUM_FILES
    PRINT
LOOP
FOR I = 1 TO NUM_FILES
    LET FILENAMES$(I) = ""
    DO WHILE FILENAMES$(I) = ""
        PRINT "Enter filename # "; I; " ";
        INPUT FILENAMES$(I)
    LOOP

```

(continued on next page)

Quelo® 68000 Software Development Tools

Quelo Assembler Packages are **Motorola compatible**. Each package includes a macro assembler, linker/locator, object librarian, utilities for producing **ROMable code**, extensive indexed typeset manuals and produces **S-records**, Intel hex, **extended TEK hex**, **UNIX COFF** and symbol cross references. **Portable source** written in "C" is available. It has been ported to a variety of mainframes and minis including **VAX**.

68020 Assembler Package

For CP/M-86, -68K and MS/PC-DOS\$ 750

68000/68010 Assembler Package

For CP/M-80, -86, -68K and MS/PC-DOS\$ 595

68000 "C" Cross Compiler

For MS/PC-DOS by Lattice, Inc.

With Quelo 68000/68010 Assembler Package \$1095

With Quelo 68020 Assembler Package\$1250

Call Patrick Adams today:

Quelo, Inc.
2464 33rd W. Suite #173
Seattle, WA USA 98199
Phone 206/285-2528
Telex 910-333-8171

COD, Visa, MasterCard

Trademarks: CP/M, Digital Research; MS, Microsoft Corporation; Quelo, Quelo, Inc.

Circle no. 377 on reader service card.

SOURCE CODE LIBRARIAN & REVISION CONTROL SYSTEM

TLIB™ keeps ALL versions of your program in ONE compact library file, *even with hundreds of revisions!*

- **Super Fast!** Updates (deltas) average **5-7 times faster** than PC/IX (Unix) SCCS. TLIB updates libraries faster than many editors load and save files!
- **LAN-compatible!** Shared libraries with PC Network!
- Synchronized control of multiple related source files.
- Use with floppies or hard disk. TLIB doesn't need big temporary files, so you can maintain a 300K library on one 360K diskette, with room to spare, even with TLIB itself on the same disk. And libraries are more compact than with most other revision management systems.
- Perfect for backup. Date and comments kept with each version. High data integrity because library data, once written, is never modified. Libraries are only appended, to minimize the chance of data loss due to a power glitch or hardware crash. And TLIB isn't copy-protected, either.
- Free copy of Landon Dyer's excellent public domain **MAKE** utility. With macros, full source code. For DOS & VAX/VMS.

PC/MS-DOS 2.x & 3.x **Just \$99.95 + \$3 s/h** Visa/MC

BURTON SYSTEMS SOFTWARE

P. O. Box 4156, Cary, NC 27511-4156
(919) 469-3068

Circle no. 212 on reader service card.

DATA CONVERSION

TRANSFER DATA BETWEEN OVER
600 DIFFERENT COMPUTER SYSTEMS

| |
|---------------------------------|
| WORD PROCESSORS TOO |
| QUICK TURN-AROUND |
| PRICES FROM \$9 PER DISK |
| CALL OR WRITE FOR YOUR |
| FREE CATALOG |

PORT-A-SOFT

555 S. STATE ST., SUITE #12
P.O. BOX 1685, OREM, UT 84057
(801) 226-6704

Circle no. 229 on reader service card.

COMBINE THE
RAW POWER OF FORTH
WITH THE CONVENIENCE
OF CONVENTIONAL LANGUAGES

HS/ FORTH

Why HS/FORTH? Not for speed alone, although it is twice as fast as other full memory Forths, with near assembly language performance when optimized. Not even because it gives MANY more functions per byte than any other Forth. Not because you can run all DOS commands plus COM and EXE programs from within HS/FORTH. Not because you can single step, trace, decompile & disassemble. Not for the complete syntax checking 8086/8087/80186 assembler & optimizer. Nor for the fast 9 digit software floating point or lightning 18 digit 8087 math pack. Not for the half megabyte LINEAR address space for quick access arrays. Not for complete music, sound effects & graphics support. Nor the efficient string functions. Not for unrivaled disk flexibility — including traditional Forth screens (sectored or in files) or free format files, all with full screen editors. Not even because I/O is as easy, but far more powerful, than even Basic. Just redirect the character input and/or output stream anywhere — display, keyboard, printer or com port, file, or even a memory buffer. You could even transfer control of your entire computer to a terminal thousands of miles away with a simple >COM <COM pair. Even though a few of these reasons might be sufficient, the real reason is that we don't avoid the objections to Forth — WE ELIMINATE THEM!

Public domain products may be cheap; but your time isn't. Don't shortchange yourself. Use the best. Use it now!

HS/FORTH, complete system: \$395. with "FORTH: A Text & Reference" by Kelly and Spies, Prentice-Hall and "The HS/FORTH Supplement" by Kelly and Callahan



Visa

Mastercard



**HARVARD
SOFTWARES**

PO BOX 69
SPRINGBORO, OH 45066
(513) 748-0390

Circle no. 132 on reader service card.

STRUCTURED PROGRAMMING

Listing Three (Listing continued, text begins on page 120.)

```

PRINT
LOOP
NEXT I
END SUB

SUB GetStrings (STRNG$( ), REPLACES( ), REPLACE( ), NUM_STRINGS)
! Subroutines to input search/replace strings
LET NUM_STRINGS = 0
DO WHILE NUM_STRINGS <= 0
  INPUT PROMPT "Enter number of search/replace strings ":NUM_STRINGS
  PRINT
LOOP
FOR I = 1 TO NUM_STRINGS
  LET REPLACES(I) = ""
  PRINT
  PRINT "For string # ";I
  INPUT PROMPT "  Enter string ":STRNG$(I)
  INPUT PROMPT "  Replace Find ":AS
  IF (POS("Rr",AS[1:1]) = 0) THEN
    LET REPLACE(I) = FALSE
  ELSE
    LET REPLACE(I) = TRUE
    INPUT PROMPT "    Enter replacement string ":REPLACES(I)
  END IF
  PRINT
NEXT I
END SUB

SUB ReadLines (L$( ), FILENAMES( ), INDEX, NUM_LINES)
! Subroutines to read text lines
PRINT #9 : "PROCESSING FILE : ";FILENAMES(INDEX)
OPEN #1 : NAME FILENAMES(INDEX), ORGANIZATION TEXT, ACCESS INPUT, CREATE OLD
LET NUM_LINES = 0
DO WHILE MORE #1
  LET NUM_LINES = NUM_LINES + 1
  LINE INPUT#1 : L$(NUM_LINES)
LOOP
CLOSE #1
END SUB

SUB CenterText (T$)
! Subroutine to center a message
PRINT REPEAT$( " ", (40 - LEN(T$)/2));T$
END SUB

SUB WriteLines (L$( ), FILENAMES( ), INDEX, NUM_LINES)
! Subroutine to write the updated file
OPEN #1 : NAME FILENAMES(INDEX), ORGANIZATION TEXT, ACCESS OUTPUT, CREATE OLD
ERASE #1
FOR I = 1 TO NUM_LINES
  PRINT#1 : L$(I)
NEXT I
CLOSE#1
END SUB

END
```

End Listing Three

Listing Four

Listing 4. CHNG1.BAS the first QuickBASIC version of CHANGE.BAS that is translated manually.

```

' Batch Find/Replace Utility Version 1.0 10/29/86
' IBM PC QuickBASIC version 2
' Copyright (c) 1987 Namir Clement Shammass
DEFINT A-Z
DIM FILENAMES(20), STRNG$(30), REPLACE(30), REPLACES(30), L$(500)
TRUE = 1
FALSE = 0
MAX_LINES = 500 ' Current maximum number of lines read from a file
CLS
TS = "BATCH FILE FIND/REPLACE PROGRAM" : GOSUB Center
PRINT
TS = "VERSION 1.0" : GOSUB Center
PRINT : PRINT
GOSUB GetFile ' Get filenames
GOSUB GetStrings ' Get strings
FOR IFILE = 1 TO NUM.FILES
```



```

GOSUB ReadLines ' Read text lines from file
FOR I = 1 TO NUM.STRINGS
  FOUND = FALSE
  FOR J = 1 TO NUM.LINES
    PTR = INSTR(L$(J),STRNG$(I))
    WHILE PTR > 0
      IF (FOUND = FALSE) THEN
        FOUND = TRUE
        LPRINT "KEYWORD : ";STRNG$(I)
      END IF
      BS = STR$(J) + ":"
      OFFSET = LEN(BS)
      LPRINT J;"":L$(J)
      LPRINT SPC(PTR-OFFSET);""
      IF (REPLACE(I) = TRUE) THEN
        FIRST$ = ""
        IF PTR > 1 THEN FIRST$ = MID$(L$(J),1,(PTR-1))
        LAST$ = ""
        IF (PTR+LEN(STRNG$(I))) < LEN(L$(J)) THEN
          LAST$ = MID$(L$(J),(PTR+LEN(STRNG$(I))))
        END IF
        L$(J) = FIRST$ + REPLACE$(I) + LAST$
        LPRINT "BECOMES" : LPRINT
        LPRINT J;"":L$(J) : LPRINT : LPRINT
      END IF
      PTR = INSTR(PTR+1,L$(J),STRNG$(I))
    WEND
  NEXT J
NEXT I
GOSUB WriteLines ' Write file back
LPRINT : LPRINT
NEXT IFILE
LPRINT CHR$(140) ' FORM FEED
END '-----
GetFile: ' Subroutine to input filenames from the keyboard
NUM.FILES = 0
WHILE NUM.FILES <= 0
  INPUT "Enter number of files ";NUM.FILES
  PRINT
WEND
FOR I = 1 TO NUM.FILES
  FILENAMES(I) = ""
  WHILE FILENAMES(I) = ""
    PRINT "Enter filename # ";I;" ";
    INPUT FILENAMES(I) : PRINT
  WEND
NEXT I
RETURN
GetStrings: ' Subroutines to input search/replace strings
NUM.STRINGS = 0
WHILE NUM.STRINGS <= 0
  INPUT "Enter number of search/replace strings ";NUM.STRINGS
  PRINT
WEND
FOR I = 1 TO NUM.STRINGS
  REPLACE$(I) = ""
  PRINT : PRINT "For string # ";I
  INPUT "  Enter string ";STRNG$(I)
  INPUT "  Replace Find ";AS
  IF (INSTR("Rr",MID$(AS,1,1)) = 0) THEN REPLACE(I) =
  FALSE ELSE REPLACE(I) = TRUE
  IF REPLACE(I) = TRUE THEN
    INPUT "  Enter replacement string ";REPLACE$(I)
  END IF
  PRINT
NEXT I
RETURN
ReadLines: ' Subroutines to read text lines
LPRINT "PROCESSING FILE : ";FILENAMES$(IFILE)
OPEN "I",1,FILENAMES$(IFILE)
NUM.LINES = 0
WHILE (NOT EOF(1)) AND (NUM.LINES <= MAX.LINES)
  NUM.LINES = NUM.LINES + 1
  LINE INPUT#1,L$(NUM.LINES)
WEND
CLOSE #1
RETURN
Center: ' Subroutine to center a message
PRINT SPC(40 - LEN(T$)/2);T$
RETURN
WriteLines: 'Subroutine to write the updated file
OPEN "O",1,FILENAMES$(IFILE)

```

(continued on next page)

FLASH UP YOUR PROGRAMS WITH

POPSCREEN™

THE SCREEN GENERATOR FOR PROGRAMMERS

Create instantaneous, full color, pop-up displays and windows for your programs. Design your displays onscreen, in view, with easy, automated routines.

PopScreen automatically compiles your displays to compact .obj modules which link easily and integrally into your programs at link time. Will write displays as .asm or inline code for Assembler and Turbo Pascal.

Requires NO SATELITE DISPLAY FILES or resident loaders to accompany your C, Pascal, or Assembly programs. Your final program looks professional and is completely self-contained, in one integral file.

Dbase III and batch file programs require only one external display file for all your program's displays.

Simple to use, includes manual & tutorial. A single procedure call pops your display to screen in .015 seconds. Average display size is only 500 bytes.

POPSCREEN SUPPORTS:
 MONOCHROME, CGA, EGA, PGC;
ASSEMBLERS: (ALL);
C: (IBM, LATTICE, MICROSOFT);
PASCAL: (IBM, MICROSOFT,
TURBO PASCAL);
BASIC WITH BLOAD; DBASE III;
WILL CREATE .COM DISPLAYS FOR
BATCH FILES & APPLICATIONS.

POPSCREEN
ONLY \$39.95

Circle no. 383 on reader service card.

BAYSOFT
 BOX 6562-D, ALBANY, CA. 94706
 415-527-3300

30 DAY
SATISFACTION GUARANTEE

Circle no. 383 on reader service card.

Jou Laboratories
presents

EditingTools

new version 2.1

A Superb
Text Editor
with an Intelligent
DOS Shell

Don't use your PC
without it

EditingTools Editor

Fast, powerful, simple to use.
Edit multiple files, limited only
by available memory. Move text
among files. Deleted lines are
recoverable from the trash file.

EditingTools DOS Shell

An intelligent interface between
DOS and the Editor. Load
multiple directories as menus in
easy to read table format - names
of files with the same extension
are sorted into a column, labeled
by their common extension.
Select a file to edit, or a program
to execute without worrying
about paths.

Shell Commands

Execute DOS Command, Change
Color/ Drive, ChDir, Copy,
Delete, Edit, Execute, Move,
Rename, Load/Erase Directory,
Previous/ Next Directory, Print,
MkDir, Store/Recall Command,
List Commands, Return To
Editor, and more.

Editor Commands

Auto Insert/ Indent, Indent
Block, Previous/ Next File, Edit
Trash File, Verify Key, Restore
Line, Find/Replace, Goto Line,
Repeat/ Reverse Goto, Tab
Right/ Left, List Commands,
Blank Screen, Return To Shell,
and much more.

System Requirements

EditingTools is only 40K in size,
and runs efficiently on IBM PC,
XT, AT and true compatibles.
No installation program. All
editor command keys can be
changed effortlessly during
editing. It is not copy protected.

Incredible Value

Add EditingTools to your PC
toolbox for only \$35 + \$4 s/h.
Optimized Turbo Pascal source
code optional. 60 day money
back guarantee. To order, send
check or money order to:

Jou Laboratories
P.O. Box 460969
Garland, TX 75046
(214) 495-8862

Circle no. 355 on reader service card.

STRUCTURED PROGRAMMING

Listing Four (Listing continued, text begins on page 120.)

```
FOR I = 1 TO NUM.LINES
  PRINT#1, L$(I)
NEXT I
CLOSE#1
RETURN
```

End Listing Four

Listing Five

Listing 5. CHNG2.BAS the second QuickBASIC version of CHANGE.BAS that is translated manually.

```
' Batch Find/Replace Utility Version 1.0 10/29/86
' IBM PC QuickBASIC version 2
' Copyright (c) 1987 Namir Clement Shammass
DEFINT A-Z
DIM FILENAMES(20), STRNG$(30), REPLACE(30), REPLACES$(30), L$(500)
TRUE = 1
FALSE = 0
MAX.LINES = 500 ' Current maximum number of lines read from a file
CLS
CALL CenterText("BATCH FILE FIND/REPLACE PROGRAM")
PRINT
CALL CenterText("VERSION 1.0")
PRINT : PRINT
CALL GetFile(FILENAMES(), NUM.FILES) ' Get filenames
CALL GetString(STRNG$(1), REPLACES$(1), REPLACE(1), NUM.STRING$) ' Get strings
FOR IFILE = 1 TO NUM.FILES
  ' Read text lines from file
  CALL ReadLines(L$(1), FILENAMES(1), IFILE, NUM.LINES)
  FOR I = 1 TO NUM.STRING$
    FOUND = FALSE
    FOR J = 1 TO NUM.LINES
      PTR = INSTR(L$(J), STRNG$(I))
      WHILE PTR > 0
        IF (FOUND = FALSE) THEN
          FOUND = TRUE
          LPRINT "KEYWORD : "; STRNG$(I)
        END IF
        BS = STR$(J) + ":"
        OFFSET = LEN(BS)
        LPRINT J; ":"; L$(J)
        LPRINT SPC(PTR+OFFSET); ""
        IF (REPLACE(I) = TRUE) THEN
          FIRST$ = ""
          IF PTR > 1 THEN FIRST$ = MID$(L$(J), 1, (PTR-1))
          LAST$ = ""
          IF (PTR+LEN(STRNG$(I))) < LEN(L$(J)) THEN
            LAST$ = MID$(L$(J), (PTR+LEN(STRNG$(I))))
          END IF
          L$(J) = FIRST$ + REPLACES$(I) + LAST$
          LPRINT "BECOMES" : LPRINT
          LPRINT J; ":"; L$(J) : LPRINT : LPRINT
        END IF
        PTR = INSTR(PTR+1, L$(J), STRNG$(I))
      WEND
    NEXT J
  NEXT I
  ' Write file back
  CALL WriteLines(L$(1), FILENAMES(1), REPLACE(1), IFILE, NUM.LINES)
  LPRINT : LPRINT
NEXT IFILE
LPRINT CHR$(140) ' FORM FEED
END '-----

SUB GetFile(FILENAMES(1), NUM.FILES) STATIC
' Subroutine to input filenames from the keyboard
NUM.FILES = 0
WHILE NUM.FILES <= 0
  INPUT "Enter number of files "; NUM.FILES
  PRINT
WEND
FOR I = 1 TO NUM.FILES
  FILENAMES(I) = ""
  WHILE FILENAMES(I) = ""
    PRINT "Enter filename # "; I; " "
    INPUT FILENAMES(I) : PRINT
  WEND
NEXT I
END SUB
```



```

SUB GetStrings(STRNG$(1),REPLACES(1),REPLACE(1),NUM.STRING$) STATIC
' Subroutines to input search/replace strings
  NUM.STRING$ = 0
  WHILE NUM.STRING$ <= 0
    INPUT "Enter number of search/replace strings ";NUM.STRING$
    PRINT
  WEND
  FOR I = 1 TO NUM.STRING$
    REPLACES(I) = ""
    PRINT : PRINT "For string # ";I
    INPUT "  Enter string ";STRNG$(I)
    INPUT "  Replace Find ";A$
    IF (INSTR("Rr",MID$(A$,1,1)) = 0) THEN
      REPLACE(I) = FALSE
    ELSE
      REPLACE(I) = TRUE
      INPUT "  Enter replacement string ";REPLACES(I)
    END IF
    PRINT
  NEXT I
END SUB

SUB ReadLines(L$(1),FILENAME$(1),INDEX,NUM.LINES) STATIC
' Subroutines to read text lines
  LPRINT "PROCESSING FILE : ";FILENAME$(INDEX)
  OPEN "I",1,FILENAME$(INDEX)
  NUM.LINES = 0
  WHILE (NOT EOF(1)) ' AND (NUM.LINES <= MAX.LINES)
    NUM.LINES = NUM.LINES + 1
    LINE INPUT#1,L$(NUM.LINES)
  WEND
  CLOSE #1
END SUB

SUB CenterText(T$) STATIC
' Subroutine to center a message
  PRINT SPC(40 - LEN(T$)/2);T$
END SUB

SUB WriteLines(L$(1),FILENAME$(1),INDEX,NUM.LINES) STATIC
' Subroutine to write the updated file
  OPEN "O",1,FILENAME$(INDEX)
  FOR I = 1 TO NUM.LINES
    PRINT#1,L$(I)
  NEXT I
  CLOSE#1
END SUB

```

End Listings

ATTENTION DATABASE DEVELOPERS

If you have the need for relational database management within your application programs

TURBO-DB™

is the programmer's tool you have been waiting for!

TURBO-DB offers a number of features for the software developer:

SMALL AND LARGE DATABASE MANAGEMENT

A UNIQUE PROGRAMMATIC INTERFACE FOR CUSTOM APPLICATION DEVELOPMENT

IN ASM, 'C', FORTRAN AND PASCAL

QUEL-TYPE QUERY LANGUAGE

INTEGRATED DATABASE ADMINISTRATION

DATABASE RECOVERY AND BACKUP UTILITIES

WRITTEN ENTIRELY IN 'C'— UNIX COMPATIBLE

For the IBM PC/XT/AT
or compatible computers
(256K RAM, DOS 2.0+, diskette or hard disk)

Software Developer Package I

- Interactive Query Writer
- Database Administration
- Database Backup and Recovery Utilities
- User Tutorial
- User Reference Manual

\$145

Software Developer Package II

- Software Developer Package I
- 'C' Object Code Interface
- Programming Interface Reference Manual

\$395

UPLAND SOFTWARE CO.

P.O. BOX 3136 • REDWOOD CITY, CA 94064
(415) 876-7636

MasterCard, Visa, Checks Accepted

Nr: A C Implementation of Nroff, Part 2


This month I'll continue discussing the nr text formatter that I introduced last month. I'll present the first part of a complete users' guide and continue it in the next column. The source-code disk contains a complete implementation of the ms macro package. (See the end of this column for information about the source code disk.) Nr is as much a programming language as it is a text formatter, and a look at a complex macro package such as ms can show you how to program in that language.

I should preface this article by saying that I've implemented the Unix nroff as closely as I can. Over the course of several years, I've learned more things about nroff than I actually care to know. I do not claim, however, to know everything there is to know about the real nroff. As a consequence, there may be a few differences between nr and the real nroff, introduced because I can't figure out how the real nroff works. Sorry. I should also say that, though I've used the program presented here for several years now and don't know about any bugs, I'm a creature of habit and probably haven't exercised those parts of the program that have bugs in them. In particular, when you get into the realm of fancy laser printers and proportional spacing, nr may not work without your having to modify the program somewhat. It works fine on the various printers I own (HP Thinkjet, Brother HR-15, and HP-Laserjet+), but these are the only print-

by Allen Holub

ers on which the program has been used. I've added the proportional-spacing features very recently, so I don't have as much confidence in that part of the program as I do in the older parts.

As I write this article, I'm looking at the code more closely than I have for



a while. As a consequence I'm noticing (and fixing) a few nroff incompatibilities I hadn't noticed before. Two such fixes affect one of the subroutines I discussed last month—the expression parser in `parse.c`. This parser treats the `'str1'str2'` expression as if it were using the C `strcmp()` function. Nroff, on the other hand, evaluates this expression to true if the two strings are equal and to false if they are not—the opposite of `strcmp()`. A second problem with the parser is actually a bug. It shouldn't recognize a quote as white space. To modify `parse.c` to fix these problems, replace line 293 of `parse.c` with:

```
rval = !strcmp(s1, s2);
```

and change line 137 to:

```
while( isspace(*Str) )
```

Nr Users' Guide

It's almost impossible to describe a program as complex as nr in an orderly fashion because there's no way to organize the material to avoid forward references. Consequently,

you'll probably have to read this guide (and its conclusion in my next column) twice—once to get a general idea of how the program works and a second time to fill in the details.

Nr is an almost complete implementation of the Unix nroff text formatter. It incorporates several of troff's functions as well, and it can generate output for most printers without any modifications to the source code.

Nr is a compiler-like text formatter. You create the input text with a normal editor and then submit it to nr just like you'd submit a program to a compiler. Nr formats the input and sends the resultant text to standard output (so you have to redirect it if you don't want to display it on the screen). You invoke nr with:

```
nr [-switches] files... [ >stream ]
```

You can list several files—they are just concatenated as the program runs. The command-line switches are optional, and several of them are position sensitive. Table 1, below, summarizes supported switches. They are:

-- print a list of legal command-line switches.

-c—map all control characters, if present, to visible characters before they're printed. This option is partic-

| | |
|----------|--|
| -c | don't print (c)ontrol characters |
| -d | print only (d)d pages |
| -e | print only (e)ven pages |
| -m<str> | append (m)acro: /lib/tmac/<str>.mac |
| -n<num> | (n)umber first page <num> |
| -o<list> | print (o)nly pages in list <list> |
| -p | suppress bold, underline, overstrike |
| -r<str> | set number (r)eg: -rx<num> -r(xx<num>) |
| -s<num> | (s)top every <num> pages |
| -t<str> | set s(t)ring: -tx<str> -t(xx<str>) |
| -v | (v)erbose mode, echo input commands |

Table 1: Summary of command-line arguments



EVERYTHING THE C PROGRAMMER NEEDS

■ Eco-C88 C Compiler:

A full, professional C compiler with many ANSI enhancements at an unbelievably low price.

* Prototyping, enum, void data types, plus structure passing & assignment * All operators and data types * Over 200 library functions * cc and mini-make for easy use * 8087 support * ASM or OBJ output * Lint-like tiered error messages * Fast code * CED editor (edit-compile-link from within the editor) * Expanded user's manual * Not copy protected * All for only \$59.95!

■ Eco-C88 Flexi-Graph Graphics Package

Everything you need to write dramatic graphics effects into your Eco-C88 C programs.

* EGA, CGA, and Z100 support * Over 100 graphics functions (many are PLOT-10 compatible) * Most assembler support routines are outside small model code-data * Write thru BIOS (for compatibility) or to memory (for speed) * Graphics function help from CED editor * World, pixel or turtle color graphics modes * 47 standard fill patterns, 17 line dashing patterns, Hershey fonts, plus user definable fill, dash, and fonts * Supports view areas, rotatable fonts, clipping, arbitrary fill areas, extensive error checking, examples, and user's manual * Only \$39.95

■ Eco-C88 Windowing Library

Use this library to build pop-up windows, help windows, selection menus, special effects—anywhere you need an attention getter.

* CGA and EGA support * Control any program that goes through the BIOS * Use up to 255 windows * No special window commands — use plain old printf() to write to a window * Resize and move windows * Custom window titles and borders * Can be used with ANSI device driver * Most window code-data are outside small model * User's manual and examples for only \$29.95

■ Ecosoft Librarian

Combine your modules, functions, and subroutines into your own library for easy link commands. Compatible with any standard MSDOS OBJ files * Add, delete, and extract from a library * Get table of contents or index of a library * Combine libraries, control library page size, use switches for combinations, process complex library requests, use wildcards, and do library directives from command files * Complete with user's manual for only \$29.95

■ Developer's Library


Contains the source code for for all library functions, including the transcendental, memfiles, and those written in assembler. \$25.00 with order, \$50.00 if ordered later. (Sold only to Eco-C88 owners.)



Ecosoft Inc.
6413 N. College Ave.
Indianapolis, IN 46220




Eco-C88 C compiler requires an IBM PC, XT, or AT (or compatible) with 256K of memory, 2 disk drives and MSDOS 2.1 or later.



C Programming Guide

(Purdum, Que Corp.)

The second edition of the B. Dalton bestseller. Perfect for those just getting started with C. Includes discussion of many X3J11 ANSI Standards Committee recommendations. Many error messages from Eco-C88 give page references to this book. Price is \$20.00 plus \$2.00 shipping.



C Self-Study Guide

(Purdum, Que Corp.)

Using a question-answer approach, this book is filled with shortcuts, tips, techniques, and traps to avoid when learning C. Price is \$17.00 plus \$2.00 for shipping.



C Programmer's Library

(Purdum, Leslie, Stegemoller, Que Corp.)

Another B. Dalton bestseller. An intermediate C text for the programmer that wants to get the most from the language. Contains source code for many functions including an ISAM file handler. Price is \$22.00 plus \$2.00 for shipping.

To order, call or write:

1-800-952-0472
(for orders)

or

1-317-255-6476
(tech. info.)

ORDER FORM CLIP & MAIL TO:

Ecosoft Inc., 6413 N. College Ave., Indianapolis, IN 46220

- ☐ Eco-C88 C Compiler \$59.95 _____
- ☐ Eco-C88 Flexi-Graph Graphics Package \$39.95 _____
- ☐ Eco-C88 Windowing Library \$29.95 _____
- ☐ Ecosoft Librarian \$29.95 _____
- ☐ Developer's Library \$25.00 (\$50.00 if not with order) _____
- ☐ C Programming Guide \$20.00 _____
- ☐ C Self-Study Guide \$17.00 _____
- ☐ C Programmer's Library \$22.00 _____

SHIPPING \$4.00

TOTAL (IND. RES. ADD 5% TAX) _____

PAYMENT: ☐ VISA ☐ MC ☐ AE ☐ CHECK

CARD# _____ EXPIR. DATE _____

NAME _____

ADDRESS _____

CITY _____ STATE _____

ZIP _____ PHONE _____

ECOSOFT

ularly useful for debugging escape sequences that are sent directly to the printer. Nonprinting characters are output as `<DD>`, where `DD` is two hex digits.

`-d`—print only odd-numbered pages. This option is useful if you're sending output to a laser printer and want two-sided output. This command interacts with the `-o` and `-n` switches described later (for example `nr -d -o10-20 file.nr >prn` prints only odd-numbered pages in the range 11 to 19).

`-e`—print only even-numbered pages.

`-m <name>`—cause the contents of a macro file to be processed before any of the normal input files are processed. You can think of `-m` as short for `/lib/tmac/name.mac`. For example, the switch `-ms` causes `nr` to process the file `/lib/tmac/s.mac`. If you specify several `-m` options, the files are processed in order from left to right, and all macro files are processed before any normal files are processed.

`-n <num>`—cause the first page to be numbered `N`—for example, `-n10` causes page numbering to start at 10.

`-o <list>`—print only those pages in `<list>`. The list can take several forms. The simplest is `-o1,3,5`, which prints only pages 1, 3, and 5. You can specify ranges of pages, as in `-o5-10`, which prints pages 5 to 10 inclusive. The notation `-o-10` means print all pages from the beginning of the document up to and including page 10. Similarly, `-o10-` means print from page 10 to the end of the document. You can combine all these forms, as in `-o-10,12,15-20,30-`, which prints pages 1 to 10, page 12, pages 15 to 20, and from page 30 to the end of the document. Note that the `-n` option interacts with the `-o` and `-e` options—that is, if you say `-n5`, then saying `-o2` won't work because there is no page 2.

`-p`—generate plain output (suppress

all boldface, underline, and overstrike).

`-r <str>`—initialize a number register (described later). This option can have two forms:

`-rx123`
`-r(xx123)`

The first form initializes the single-character number register `x` to 123; the second initializes the two-character register `xx`. These numbers can be used in the document with `\nx` and `\n(xx` (see later).

`-s <num>`—stop output every `num` pages. This option is useful if you have to hand-feed paper into your printer one page at a time (use `-s1` for this purpose).

`-t <str>`—initialize a text string macro (works just like `-n` does). The text is available inside the document using the `*x` and `*(xx` mechanisms, described later. Note that you have to quote the string to get blanks into the text:

`nr " -t\text with spaces" file`

`-v` (verbose mode)—cause commands to be echoed to standard output just before they're executed but after all the escape sequences (described later) have been expanded. Commands that are part of macro definitions aren't echoed. The name of the input source (a file or macro name) is printed as well. This is a debugging option.

Input to Nr

The command structure and command names `nr` uses are almost identical to those that `nroff` uses. There are a few minor differences that I will discuss later. Because I didn't want to create a binary intermediate file, such as the one used by `ditroff` (device-independent `troff`), I've added several nonstandard commands to support configuration to various printers. Nonstandard commands are identified as such in the following command descriptions.

One of my original intentions in writing `nr` was to be able to write documents at home and then upload these to the `nroff` system at school for

final typesetting. Consequently, I tried to make the move as painless as possible. At the macro level, `nr` is identical to `nroff`. I've written an implementation of the `ms` macro package that's in use at UC Berkeley. If your documents are formatted with `ms`, as are the overwhelming majority of `nroff` and `troff` documents, porting to a real Unix system is trivial. The few minor differences between the `nr` internal commands and the real `nroff` are well documented and easily translated. I just recently transferred a complete book from `nr` to the VAX at school and for the most part experienced no difficulties. The main problem I had was with translating macros not in the `ms` package to the real `nroff`/`troff`. `Nr` is better documented than `nroff` itself. As a consequence, writing real `nroff` macros can be difficult. Once you have created the equivalent macros, translation is no problem, of course. The other problems I had were typesetter-related. A typesetter is not a daisy-wheel printer, and the differences took a few days to figure out.

`Nr` takes as input a normal ASCII text file that contains intermingled text and formatting commands. Note that `nr` won't automatically map ASCII to a funny daisywheel—you have to do it yourself. `Nr`, unlike `troff`, understands the entire ASCII character set. Some of the characters (such as `\`) have a special meaning to `nr`, however, and have to be entered in a special way, discussed later. There's also a provision for printing special non-ASCII characters.

`Nr` commands take two forms: dot commands and escape sequences. Dot commands all start with a dot in the leftmost column. The dot is followed by a one- or two-letter command name. All of the built-in commands have two-letter names. You can create new commands using `nr`'s macro capability, however, and these can have either one- or two-letter names. There can be any amount of white space (spaces or tabs) between the dot and the first character of the name, which is useful inside a macro if you want to indent the body of an `.if` statement. Because `.if` and `.ie` (`.if . . . else`) statements nest, indenting can help a great deal.

Escape sequences, the other sort of command, are text strings that are

embedded in the text itself. They all begin with a backslash (\) but are otherwise dissimilar. You use escape sequences for such tasks as changing fonts on the fly or expanding certain macros. The `\fI` escape sequence, for example, changes the current font to italics and `\fP` puts it back to the previous state. You can put a word into italics with `\fIword\fP`.

Expressions

All the `nr` commands that take numeric arguments can also take expressions (which are computed as the document is processed) instead of absolute numbers. Several operators are available, shown in Table 2, right. All these operators work just like their C equivalents do except that expression evaluation doesn't terminate when the truth or falsity of an `&&` or `!!` expression is determined. Note that this is a more powerful expression syntax than is supported by the real `nr`off.

Be careful of strings that follow expressions on the command line. Because white space is legal in an expression, the analyzer just scans the input line until it finds an illegal character. If you say something such as:

```
.vd <up> 1 <down>
```

the `<` that precedes `down` will be absorbed by the expression parser because `<` is a legal character in an expression. The problem can be fixed by putting quote marks around the strings:

```
.vd "<up>" 1 "<down>"
```

Most commands treat leading plus or minus signs specially. These signs cause the current value associated with a command to be incremented or decremented by the indicated amount.

For example:

```
.in 10 \" Set indent level to 10
.in +5 \" Increase it to 15
.in -5 \" Decrease it back to 10
```

The `\` is a comment; all text that follows it is ignored.

The real `nr`off supports several unit-of-measurement operators that can be appended onto numbers (inches, picas, points, and so forth). `nr` does not support these.

Dot Commands

`nr` supports a rich set of dot commands (90 or so). As I mentioned earlier, all commands that take numeric arguments can be passed expressions

| Operator | Precedence Level | Meaning |
|----------|------------------|--|
| () | 5 | used for grouping |
| - | 5 | unary minus (as in -5) |
| ! | 5 | logical NOT |
| 's1's2' | 5 | compares two strings—evaluates to true (1) if they are equal, to false (0) if they are not |
| * | 4 | multiply |
| / | 4 | divide |
| % | 4 | modulus (MOD) |
| + | 3 | addition |
| - | 3 | subtraction |
| < | 2 | less than |
| <= | 2 | less than or equal |
| > | 2 | greater than |
| >= | 2 | greater than or equal |
| = | 2 | equal |
| != | 2 | not equal |
| && | 1 | logical AND |
| !! | 1 | logical OR |

Table 2: Operators. All operators associate left to right. Higher numbers have higher precedence.

Here's why you should choose Periscope as your debugger...

You'll get your programs running fast. "It works great! A problem we had for three weeks was solved in three hours," writes Wade Clark of MPPI, Ltd.

You'll make your programs solid. David Nanian says, "I can't live without it!! BRIEF, a text editor my company wrote, would not be as stable as it is today without Periscope."

You'll protect your investment. We won't forget you after the sale. You'll get regular software updates, including a FREE first update and notice of later updates. You'll get technical help from Periscope's author. And you'll be able to upgrade to more powerful models of Periscope if you need to. One Periscope user writes, "...

your support has won over even the heart of this hardened programmer!"

You deserve the best. Thousands of programmers rely on the only debugger that PC Tech Journal has ever selected as **Product of the Month** (1/86). You owe it to yourself to find out why, first hand.

You can try it at no risk. You get an unconditional 30-Day, Money-Back Guarantee, so you can't lose.

Start saving time and money now — order toll-free, 800/722-7006. Use MasterCard, Visa, COD, or a qualified company purchase order. As one user puts it, Periscope is "one of the rare products, worth every penny!"

New Version 3 is better than ever!

Periscope I, software, manual,
protected memory board and
breakout switch \$345
Periscope II, software, manual, and
breakout switch \$175
Periscope II-X,
software and manual \$145

Add shipping - \$3 US; \$8 Canada; \$24 elsewhere.

The
PERISCOPE
Company, Inc.

14 Bonnie Lane • Atlanta, GA 30328 • 404/256-3860

instead of explicit numbers. The escape sequences on the line are expanded before the expression is evaluated, so you can use number registers and the like in expressions (I'll discuss these in depth in a moment). If a command argument contains any space characters, you must enclose it in double quotes, as in the following:

```
.ds x "several words in a string"
```

Unlike the various Unix shells, the quotes are just for grouping—they do not protect any internal escape sequences (introduced with a `\`) from expansion. For example:

```
.sp "(\\nx + 15) * \\ny"
```

is treated identically to:

```
.sp \\nx + 15 * \\ny
```

but is a little easier to read.

All supported dot commands are discussed later. The commands are grouped functionally. Don't be dismayed by their number and complexity. As I mentioned earlier, `nr` is really a programming language that generates formatted text as output rather than a compiled program. Consequently, you hardly ever have to use the primitive commands themselves; rather, you use subroutines (macros) that are written in terms of the primitive commands. The advantage of a system such as this is that you can redefine the way your text formatter works to suit your convenience.

In all the following descriptions, brackets delimit an optional argument (*arg*); in nonliteral arguments, *on* is a string that turns something on and *N* is a number; and angle brackets are used when more than one word is needed to describe an argument (*<left str>*).

Configuration

`Nr` has several commands that configure it to work with specific printers. Typically these are concentrated in a macro file that is read using the `-m` command-line switch—for example, the switch `-mlaser` tells `nr` to read

the file `/lib/tmac/laser.mac` before processing other files. The `ms` macro package I use is configured so that text is displayed properly on the screen, provided that `ANSI.SYS` is installed—that is, boldface is shown in high intensity, italic is underlined, and so forth.

The configuration commands are:

.bd on off—takes as its argument two strings—one to turn boldface on, the

Nr is a compiler-like text formatter that can generate output for most printers.

other to turn it off. The maximum length of either string is 80 characters. Use `\x` to send control characters. For example:

```
.bd \\x1b[1m \\x1b[0m
```

configures `nr` for `ANSI.SYS`. It outputs `ESC[1m` (`0x1b` is an `ESC`) to enable boldface printing. `ESC[0m` turns it off again. If a *.bd* command is never specified, or if a *.bd* is executed with no arguments, then boldface is done by printing every character twice with an intervening backspace (`C<bs>C`). This command is a little different from the one in `nroff`.

.cm [on]—enable `nroff`-style copy mode during macro definitions. If an argument is present, `nroff` copy mode is enabled; otherwise, it's turned off. In normal copy mode only `\` and `<CR>` are recognized. In `nroff` mode the following are recognized:

```
\ " \<cr> \n \* \$ \\ \. \t \a
```

Both modes are discussed in greater detail later.

.hd <left str> N <right str>—define horizontal motion. The two strings send the printer cursor left or right by $1/N$ spaces. The width of a space is taken from the currently active character-width table (it is 1 in

the default monospaced font) and can be changed with a *.ss* command. *N* determines the minimum resolution for the space between characters in proportional-spacing mode. All the widths in the character-width table must be in terms of *N* as well.

As an example, if a space character occupies 12 units of horizontal resolution in a specific font, *N* is 12 and the two strings, when sent to the printer, move the cursor $1/12$ of a space width. The character-width tables loaded with the *.df* command (discussed later) contain widths that will all be in terms of these minimum, $1/12$ space units. For example, if the character-width table entry for *i* is 6, the character *i* occupies $6/12$ of the space occupied by a space. If the entry for *A* is 14, the character *A* takes up $14/12$ ($1\frac{1}{3}$) of the space required for a space character. The default *<left string>* is a single backspace character, the default *<right string>* is a single space character, and the default *N* is 1.

.id on off—send the string specified in *on* to the printer to put it into italics (underline) mode; *off* takes it out. The maximum length of either string is 80 characters. Use `\x<two hex digits>` to send a control character. If no arguments are present or if no *.id* is specified, then underlining is used—`nr` prints an underscore, a backspace, and then the character for each character.

.od on off—put the printer into overstrike mode (works like *.id* does). A dash is used instead of an underscore in the default situation.

.ss N—change the width of a space in the currently active font to *N*; the default *N* is 1.

.vd <up str> N <down str>—define vertical motion. The *<up str>* string moves the printer cursor up $1/N$ lines; the *<down str>* moves it down again.

Font Control and Character Attributes

Several commands are available to change the current font and to load new fonts. `Nr` handles fonts a little differently from the way `nroff` does, primarily because most printers han-

dle the various highlight modes somewhat differently from the way that phototypesetters do. All fonts have single-letter names. Five names are reserved by nr:

R—Roman, the default font
I—italics (or underline)
B—boldface
O—overstrike
P—previous

The *R* font is the default font. Initially it is a monospaced (nonproportional) font, but you can replace it with a proportional font by using a *.df* command. You can change the current font with either the *.ft* command or with an embedded *\f* escape sequence. For example, you can put the word into italics with *\fI*italics*\fP*. Here, *\fI* switches into the italics font (by sending out the string defined with the *.id* command, described earlier), prints the word *italics*, and then switches back to the previously active font with *\fP*.

The *I* (italics) attribute is a little weird in that it's used for both italics and underlining. Typically you can have only one or the other in a document, not both. If you want to have both, you should use nr's italics and then use the line-drawing characters to underline a word when necessary. Note that the real nroff doesn't support an *O* default font. Nr is also different from nroff in that nr treats the *I*, *B*, and *O* fonts as attributes rather than as actual fonts. That is, when you change to font *I*, the current font stays active but nr sends whatever string was defined with the *.id* command out to the printer. This way you can have a bold-italic character by using *\fI\bword\fP*. Changing to any font other than *I*, *B*, or *O* disables all three attributes.

Font commands are:

.bo [+ -]*N*—put all words on the next *N* input lines into boldface. The default *N* (used when *N* is missing) is 1. Note that this is not an nroff command, though it can be simulated with a macro in nroff. If you want to put an unspecified amount of text into boldface, use:

```
.bo 1000
<a bunch of text goes here>
```

.bo 0

.ul [*N*]—underline (or put into italics) words only on the next *N* input lines. Only alphanumeric characters are underlined; punctuation, spaces, and so on are not.

.cu [+ -]*N*—underline (or italicize) words continuously on the next *N* input lines. All characters are underlined, even spaces and punctuation. For example, This is continuous underlining and this is not.

.os [*N*]—overstrike the next *N* input lines (works like *.ul* does). If *N* is missing, 1 is used.

.df *F* <start> <end> <cwidths>—redefine the *R* font (but not the *I*, *O*, or *P* fonts) or add a new font. If no arguments are present, a list of existing fonts is printed to standard output along with the character-width tables.

F is a font name (one character), <start> is the name of a macro to invoke when the font is activated in the normal way (with a *\fF* or *.ft F* command), <end> is a macro to invoke when you switch out of the font, and <cwidths> is the name of a file that holds the character-width table associated with the font. This file must be composed of 256 numbers, with the numbers listed in ASCII order—that is, the first number is the character corresponding to an ASCII '\0', the second number is a Ctrl-B, the 32nd number is the width of the space character, and so on. Numbers must be separated from each other by either white space or new lines.

A sample font-width table is shown in Table 3, below. The 0s on the first line correspond to the characters having numeric values in the range 0 to 31 (all the control characters). A space (ASCII 32) is 12 units wide, an exclamation point (ASCII 33) uses 6 units, a double-quote mark (ASCII 34) uses 8 units, and so on. If numbers are missing from the end of the list, 1 is assumed. A *unit* here must also be defined in the *.hd* command described earlier. If no font-width file is specified to *.df*, a table is created and all entries in it are set to 1. (This is the default for a monospaced font.)

.ft F—change to font *F* at the beginning of the next input text line. You can also embed font changes with a *\fF* escape sequence. Note that, if font *F* doesn't exist, the error won't be flagged until the output routines try to process the font change request.

Text Filling, Adjusting, and Centering

Nr generally fills lines—that is, it collects words from input (a word is any space-delimited collection of characters) until it has collected an entire output line, and then it outputs all the words on a single line. For example:

This
is several
words.

will be collected and printed as:

This is several words.

If hyphenation is enabled, it will read one word too many and then try

| | | | | | | | | | | | | | | | |
|----|----|----|----|----|----|----|----|---|---|---|---|---|---|---|---|
| 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| 12 | 6 | 8 | 12 | 10 | 16 | 14 | 6 | | | | | | | | |
| 6 | 6 | 10 | 10 | 6 | 8 | 6 | 8 | | | | | | | | |
| 10 | 10 | 10 | 10 | 10 | 10 | 10 | 10 | | | | | | | | |
| 10 | 10 | 6 | 6 | 10 | 10 | 10 | 10 | | | | | | | | |
| 16 | 14 | 12 | 14 | 14 | 12 | 12 | 14 | | | | | | | | |
| 14 | 6 | 10 | 14 | 12 | 16 | 14 | 14 | | | | | | | | |
| 12 | 14 | 14 | 10 | 12 | 14 | 12 | 16 | | | | | | | | |
| 14 | 14 | 12 | 6 | 8 | 6 | 10 | 12 | | | | | | | | |
| 10 | 10 | 10 | 10 | 10 | 10 | 8 | 10 | | | | | | | | |
| 10 | 6 | 6 | 10 | 6 | 16 | 10 | 10 | | | | | | | | |
| 10 | 10 | 8 | 8 | 8 | 10 | 10 | 14 | | | | | | | | |
| 10 | 10 | 10 | 6 | 6 | 6 | 10 | 0 | | | | | | | | |

Table 3: A font-width file

C CHEST

(continued from page 101)

to hyphenate the last one. If `nr` can insert a hyphen to squeeze more characters onto the current line, it will do so. You can also adjust the text in several other ways. The most common is to insert white space between words in order to get the rightmost characters to line up (with the words spread as evenly as possible on the line).

You can force a line break (in which the contents of the fill buffer are printed even if there aren't enough words to fill the line) in several ways. The `.br` command always causes a break and leaves the cursor at the beginning of the next output line. In addition, several other commands—`.bp`, `.br`, `.ce`, `.fi`, `.in`, `.nf`, `.sp`, and `.ti`—cause breaks as a side effect of their operation. If you don't want a line to break when one of these is executed, replace the dot that's usually used to introduce a command with the `nobreak` command character (the default is a backquote [`]). For exam-

ple, the `.sp N` command usually causes a break and then prints `N` blank lines. The `'sp N` command, however, prints the blank lines without flushing the fill buffer first. You can change the default no-break character with a `.c2` command.

Commands for controlling filling and margins are:

`.ad [C]`—turn on margin adjusting. Adjustment modes (values of `C`) are:

`b`—adjust both margins.

`n`—same as `b`.

`l`—adjust only the left margin, leaving a ragged-right edge, as in a hand-typed document.

`r`—adjust only the right margin, leaving a ragged-left edge. God knows what this mode is good for, but `nroff` supports it.

`c`—center each output line on the page.

If `C` is missing then the most recently active adjustment mode is used.

`.br` (break)—print all the words in the current fill buffer even if there aren't enough words to fill the output line,

then go to the next output line.

`.ce [N]`—center the next `N` input lines without filling. Default `N` is 1. This command causes a break.

`.fi`—enable line filling. The default is filling off, so a `.fi` command must be specified at the top of the input. This is usually done automatically by a macro file such as `ms`. This command causes a break.

`.na`—turn off adjusting. Turn it back on with a `.ad`.

`.nf`—disable line filling, flushing the buffer first. This command causes a break.

Page Control

`Nr` has several commands for page control:

`.bp [+ -] N`—begin page `N`. If `N` is absent, use the current page number plus 1. Note that `N` is the number of the new page, not the current one, so a footer on the current page will reflect the old number. If `N` has a leading plus or minus sign, the current page number is modified by the indicated amount. This command causes a break.

`.ne N`—need `N` lines. If there aren't that many lines on the current page, then force a new page. The `.ne` command actually looks at the distance from the current position on the output page to the next output line trap, discussed later in the Macros, Strings, Diversions, and Traps section. If this distance is less than `N`, `nr` skips forward to the trap. The assumption here is that the trap will be an end-of-page trap.

`.pl [+ -] N`—set page length to `N` lines.

`.po [+ -] N`—set page offset to `N` spaces. The page offset is a specified number of space characters that are printed to the left of every output line—that is, `.po` defines the width of the left margin.

Changing Special Characters

Certain characters are special to `nr`. These are:

`.(` (command character)—introduces

The C Programmer's Assistant

C TOOLSET

UNIX-like Utilities for Managing C Source Code

No C programmer should be without their assistant — C ToolSet. All of the utility programs are tailored to support the C language, but you can modify them to work with other languages too.

Source code in standard K&R C is included; and you are welcome to use it with any compiler (UNIX compatible) and operating system you choose.

12 Time Savers

DIFF - Compares text files on a line-by-line basis; use **CMP** for byte-by-byte. Indispensable for showing changes among versions of a program under development.

GREP - Regular expression search. Ideal for finding a procedural call or a variable definition amid a large number of header and source files.

FCHART - Traces the flow of control between the large modules of a program.

PP (C Beautifier) - Formats C program files so they are easier to read.

CUTIL - A general purpose file filter.

Requires MSDOS and 12K RAM

CCREF - Cross references variables used within a program.

CBC (curly brace checker) - checks for pairing of curly braces, parens, quotes, and comments.

Other utilities include **DOCMAKE**, **ASCII**, **NOCOM**, and **PRNT**.

Source code to every program is included!

Thorough User Support Text and Online

C ToolSet documentation contains descriptions of each program, a listing of program options (if any), and a sample run of the program.

On-line help gives you information on the programs and how to run them. Most of the programs respond to `?` on the command line with a list of options.

Call 800-821-2492 to order C ToolSet risk-free for only \$95.

Solution Systems™

335-D Washington St.,
Norwell, MA 02061
(617) 659-1571

Full refund if not
satisfied in 30 days.

Circle no. 152 on reader service card.

C Programmers! High-Speed Database tames complex C applications

"db_VISTA™ lets you easily build complex databases with many interconnected record types..."

Dave Schmitt, President, Lattice, Inc.

High-Speed data retrieval and access... just two benefits of using RAIMA's network model DBMS, db_VISTA. Combine these design benefits with those of C—speed, portability, efficiency, and you begin to understand db_VISTA's real measure... performance.

Independent Benchmark proves High-Speed model 2.76 times faster

An independent developer benchmarked db_VISTA against a leading competitor. Eleven key retrieval tests were executed with sequentially and randomly created key files.

*Result of 11 Key Retrieval Tests

db_VISTA :671.24 seconds
Leading Competitor :1,856.43 seconds

db_VISTA's high-speed network database model lets you precisely define relationships to minimize redundant data. Only those functions necessary for operation are incorporated into the run time program.

Portable DBMS Applications with db_VISTA

For maximum application portability, every line of db_VISTA's code is written in C and complete source code is available. db_VISTA operates on most popular computers with several operating systems supported. So whether you write applications for micros, minis, or mainframes...db_VISTA is for you.

How db_VISTA works...

Design your database and compile your schema file with the database definition language processor. Develop application programs, making calls to db_VISTA's C functions. Edit and review your database using the Interactive Database Access utility. Compile and link your C program with the db_VISTA runtime library, and your application is ready to run.

Multi-user and LAN capability

Information often needs to be shared. db_VISTA has multi-user capability and supports simultaneous users in either multi-tasking or local area networking environments, allowing the same C applications to run under UNIX, MS-DOS, and VAX VMS.

db_QUERY™ lets you ask more of your database

db_QUERY is a linkable, royalty-free, SQL-based ad hoc query and report writing facility. It provides a user-friendly relational view of a network-model database. Use it directly or design an interface for the inexperienced to generate powerful queries and reports.

Royalty-Free Run-Time

Whether you're developing applications for a few customers, or for thousands, the price of db_VISTA or db_QUERY is the same. If you are currently paying royalties for a competitor's database, consider switching to db_VISTA and say goodbye to royalties.

FREE Technical Support For 60 days

Raima's software includes free telephone support and software updates for 60 days. Technical support personnel are available to answer questions about our software or yours.

30-Day Money-Back Guarantee

Try db_VISTA for 30 days and if not fully satisfied, return it for a full refund.

Order Schedule

| | db_VISTA | db_QUERY |
|--|----------|----------|
| <input type="checkbox"/> Single-user | \$ 195 | \$ 195 |
| <input type="checkbox"/> Single-user w/Source | \$ 495 | \$ 495 |
| <input type="checkbox"/> Multi-user | \$ 495 | \$ 495 |
| <input type="checkbox"/> Multi-user w/Source | \$ 990 | \$ 990 |
| <input type="checkbox"/> VAX Multi-user | \$ 990 | \$ 990 |
| <input type="checkbox"/> VAX Multi-user w/Source | \$1980 | \$1980 |

Not Copy Protected

Call Toll-Free Today!

Order Line 1-800-327-2462
Information Line . 1-206-828-4636



Read what others say...

"If you are looking for a sophisticated C programmer's database, db_VISTA is it. In either a single or multi-user environment, db_VISTA lets you easily build complex databases with many interconnected record types. The multi-user implementation handles data efficiently with a LAN, and Raima's customer support and documentation are excellent. Source code availability and a royalty-free run-time is a big plus."

Dave Schmitt, President
Lattice, Inc.

"My team has developed a sophisticated PC-based electronic mail application for resale to HP customers. db_VISTA has proved to be an all-round high performer in terms of fast execution, flexibility and portability, and has undoubtedly saved us much time and development effort."

John Adelus, Hewlett-Packard Ltd.
Office Productivity Division

"On the whole, I have found db_VISTA easy to use, very fast with a key find, and powerful enough for any DBMS use I can imagine on a microcomputer."

Michael Wilson, Computer Language

db_VISTA Version 2.2

Database Record and File Sizes

- Maximum record length limited only by accessible RAM
- Maximum records per file is 16,777,215
- No limit on number of records or set types
- Maximum file size limited only by available disk storage
- Maximum of 255 index and data files

Keys and Sets

- Key length maximum 246 bytes
- No limit on maximum number of key fields per record—any or all fields may be keys with the option of making each key unique or duplicate
- No limit on maximum number of fields per record, sets per database, or sort fields per set
- No limit on maximum number of member record types per set

Operating System & Compiler Support

- Operating systems MS-DOS, PC-DOS, UNIX, XENIX, SCO XENIX, UNOS, ULTRIX, VMS
- C compilers: Lattice, Microsoft, DeSmet, Aztec, Computer Innovations, XENIX and UNIX

Features

- Multi-user support allows flexibility to run on local area networks
- File structure is based on the B-tree indexing method and the network database model
- Run-time size, variable—will run in as little as 64K, recommended RAM size is 256K
- Transaction processing assures multi-user database consistency
- File locking support provides read and write locks on shared databases
- SQL-based db_QUERY is linkable
- File transfer utilities included for ASCII, dBASE optional

Utilities

- Database definition language processor
- Interactive database access utility
- Database consistency check utility
- Database initialization utility
- Multi-user file locks clear utility
- Key file build utility
- Data field alignment check utility
- Database dictionary print utility
- Key file dump utility
- ASCII file import and export utility

*The benchmark procedure was adapted from "Benchmarking Database Systems: A Systematic Approach" by Bitton, DeWitt and Turbyfill, December 1983.



High-Speed Programming Tools,
Designed for Portability

3055-112th Avenue N.E.
Bellevue, WA 98004 USA
(206) 828-4636 Telex: 9103330300

Circle no. 206 on reader service card.

Order Toll-Free
1 (800) 327-2462

dot commands.

(nobreak character)—also introduces commands, but a line break is not done if that command usually forces a break.

\ (escape character)—introduces an escape sequence.

You can change these characters with the following:

.c2 [C]—change no-break character to C. If C is missing, use a backquote (`).

.cc [C]—change command character to C. If C is missing, use a period (.).

.ec c—change escape character to C. If C is missing, use a backslash (\).

.eo—disable the escape mechanism entirely (change the escape character to nothing). You can restore it again with a **.ec** command.

Spacing, Line Length, and Indenting

You can use the commands listed in this section to change line spacing, the current indent level, and so forth. If you use a leading plus or minus sign in a numeric argument, the current value is modified by the indicated amount; otherwise, the current value is changed to the indicated value.

.in [+ -]—change the indent level to N. This indent is in addition to the left margin, which is set up with the **.po** command, described earlier. If you use both **.po** and **.in**, then the left margin is the sum of the values given to the two commands. Generally the page offset remains constant throughout a document, and the indent is changed with **.in**. This command causes a break.

.ll [+ -]N—change line length to N spaces. The line length determines how many words are collected when line filling is enabled.

.ls [+ -]N—change line spacing to N lines; 1 is single spacing, 2 is double spacing, and so on.

.ns—inhibit the printing of blank lines (no-space mode)—that is, no blank lines will be printed until some text is encountered, a **.bp N** is executed (the N is required), or a **.rs** is executed. This command is useful in the top-of-page macro.

.rs—restore blank line printing when it has been turned off with a previous **.ns** command.

.sp [N]—space down N lines (print N blank lines). N can be negative if your printer supports reverse line feeds and a previous **.vd** command was executed. This command causes a break. Note that a blank input line is treated identically to a **.sp 1** (it forces a break and prints a blank line under the flushed text).

.ti N—set the temporary indent to N spaces—that is, only the next output line will be indented by the indicated amount. This command is useful for the first line of a paragraph. The indent level for this line will be the sum of the indents specified in the **.po** and **.ti** commands—that is, the **.in** command isn't used in the calculation. To indent relative to the current indent level, use a leading plus or minus sign. For example, **.ti +5** causes the next line to be indented five spaces further than the current indent level, as specified with previous **.in** or **.po** commands. The **.ti** command causes a break.

Macros, Strings, Diversions, and Traps

Macros are the heart of nr. Without them the word processor would be so difficult to use that it wouldn't be worth the trouble. Macros are collections of text. When you define a macro, the text is saved by nr, and when you expand a macro, the text is used for input. The mechanism is identical to the **#define** mechanism in C. A macro name can be any length, though for nr off compatibility I'd suggest limiting yourself to one- or two-character names. Macros used in traps (discussed shortly) must have one- or two-character names, however. Macro names are case sensitive. You cannot define a macro that has the same name as a built-in dot command (if you do, the macro will just be ignored).

A macro is defined with a **.de** <name> command and is expanded as if it were a dot command whenever you precede its name with a dot in the first column. A macro can take up to nine arguments (accessible within the macro using **\\$1**, **\\$2**, and so forth). For example a macro defined with:

```
.de xx
arg 1 <\$1>
arg 2 <\$2>
arg 3 <\$3>
...
```

is invoked with:

```
.xx "this is one argument" doo wha
```

and will print:

```
arg 1 <this is one argument>
arg 2 <doo>
arg 3 <wha>
```

Macros can also call other macros (though recursion is not permitted). In practice they are used in the same way as subroutines are. They let you take the nr primitives described here and do something useful with them.

There are two flavors of macros: true macros and strings. A true macro is intended to hold a collection of commands and text; a string is intended to hold text that is expanded into a line. In practice, the only difference is that the last line in a macro is terminated with a carriage return whereas the last line of a string is not. Strings are defined with a **.ds** or **.as** command. They are expanded using the ***x** or ***(xx** escape sequences. The first syntax is for one-character names, and the second is for two-character names. Strings may contain escape sequences. Note that they are defined in normal mode, however (not in copy mode as the real nr off does it). This means that you need to use double backslashes to get an escape sequence into a string. For example, if you want to define a string called **#d** that prints the word **#define** in boldface, you could use:

```
.ds #d \\fB#define\\fP
```

The string could be used later by embedding a ***(#d** into the text where you wanted the word to appear.

A diversion is a macro that's used to

delay printing temporarily. This way you can collect footnotes or a table of contents in a diversion and then print the diversion out at the end of the document. The *.di xx* command causes output to be sent to the macro called *xx* rather than to the output stream. A *.di* without arguments will stop the redirection and restore the previous output stream. Diversion nesting is permitted—you can redirect to a diversion from within a diversion.

Macros and diversions are both created in copy mode, a crippled input mode in which only two escape sequences are recognized (`\` and `<CR>`). Copy mode is described in greater depth later. *Nr* supports two copy modes—the one just described and an *nroff*-compatible copy mode that is a little less restrictive. Small macros are stored internally, in RAM. If the macro gets too large (greater than 256 characters), it is stored on disk, however. The file names all take the form *xxxx.mac*, where *xxxx* is four hex digits. The string defined in the *TMP* environment (created by *COMMAND.COM* with a *set* command and by the shell with a *setenv* command) is appended to the front of the file name, so you can use something such as:

```
set TMP d:/tmp/
```

to put macro files onto a RAM disk. The trailing `/` is necessary here. Macro files are all deleted when *nr* terminates.

One of the more useful features of *nr* is a trap. A trap is a way to tell *nr* to expand a macro automatically when a specified event occurs. For example, you can set a trap to expand a macro at the top or bottom of every page. You can spring a trap after a specified number of input lines have been read or after a specified number of lines have been put into a diversion. There's also a special trap that's sprung once, after the entire document has been printed.

.de name [xx]—define a macro and give it the indicated *name*. All lines between the *.de* command and the first line that begins with *.* (or with *.xx*, where *xx* is the second argument to *.de*) are added to the macro. If a macro with the indicated name exists, it is destroyed. If both arguments

are missing, all currently defined macros are printed (like *.pm* in *real nroff* does, except the contents of the macro are printed, too).

.am name [xx]—append text to an existing macro. It works like *.de* does but doesn't overwrite the existing macro.

.ds name text—define a string called *name*, and put the indicated *text* into it. If the string already exists, it is deleted.

.as name—append text to the end of an existing string. It works like *.ds* does except that it doesn't overwrite the existing string.

.di [name]—divert output to the named macro. The diversion is terminated by a *.di* or *.da* command that has no argument. Diversions can be nested. Normal text processing occurs in a diversion except that the page offset isn't done. If a macro having the indicated name already exists, it is destroyed.

.da [name]—divert text to the named macro, appending to its end rather than overwriting it. Stop appending when a *.da* or *.di* without an argument is encountered.

.rm name—remove the named macro or string. If the macro is on the disk, the file is deleted.

.em name—use the named macro as the end macro. This macro will be executed once, after all output has been processed. You can't give arguments to the end macro.

.wh N [name]—set an output line trap. The named macro is executed automatically, immediately after printing line *N* on every page. If *N* is 0, the trap is sprung at the top of a page (above line 1). If the *name* is absent, the trap at line *N* is removed. If *N* is negative, then the trap is set relative to the bottom of the page. (The location is determined by looking at the page length [as set with *.pl*] that was in effect when the *.wh* was executed.) The macro replaces any previously installed macro for that trap position; macros do not shadow one another as in the *real nroff*.

.ch name [+ -]N—change output line trap position for the named macro to line *N*. Any existing trap at that position is destroyed (*nroff* will shadow the earlier trap, not destroy it). If *N* is absent, the trap is removed.

.dt [+ -]N name—set a diversion trap. The named macro is executed after *N* lines have been written into the current diversion. Only one diversion trap may be active.

.it [+ -]N name—set an input line trap. Execute the named macro after *N* lines of input have been read. Only one input line trap may be active. A *.it* destroys a previous trap if one exists.

Environments

In a real programming language you can copy things into local variables when you need to save them. *Nr*, however, only supports global variables, and this can present a problem. A solution of sorts is the environment mechanism. An environment is a stack. When you save an environment, various parameters that control how *nr* works are pushed onto the stack. You can then change those parameters at will. The old environment can be popped from the stack at a later date, overwriting any changes that were made after the previous push. The saved parameters are listed in Table 4, page 108.

The *.ev [N]* command pushes various commonly used variables onto an environment stack. *Nroff* supports several environments, and *nr* supports only one. If an argument is present, the current environment is pushed. If no argument is present, a previously saved environment is popped from the stack. The stack can hold up to five environments. An error message is printed if you try to push more than five.


Number Registers

Number registers are *nr*'s global variables. They are used to hold numeric quantities. You create number registers with a *.nr* command and expand them into the text with `\nx` or `\n(xx` escape sequences. The first syntax is for one-character names, and the second is for two-character names. The string `\nx`, when found in the input, is replaced by a string representing the

MICROWAY MEANS 8087 PERFORMANCE

FastCACHE-286™

Runs the 80286 at 8.5 or 11 MHz and the 80287 at 5, 6 or 11 MHz. Includes 8 kbytes of 55ns CACHE. Works with more PCs than any other accelerator, including Leading Edge Model D, Compaq, and Turbo motherboards. Includes 8088 Reboot Switch, DCache and Diagnostics. **From \$449**



LOTUS/INTEL EMS SPECIFICATION BOARDS

MegaPage™ The only EMS board which comes populated with two megabytes of cool-running, low power drain CMOS RAM installed. Includes RAM disk, print spooler, disk cache and EMS drivers. For the IBM PC, XT and compatibles...**\$549**


MegaPage with 0K. **\$149**

MegaPage AT/ECC™ EMS card for the PC AT and compatibles includes Error Correction Circuitry. With ECC, 11 RAM chips cover 256K so the user never encounters RAM errors. Sold populated with 1 megabyte CMOS ... **\$699** or with 3 megabytes CMOS cool running low power drain RAM ... **\$1295**. Optional serial/parallel daughterboard. **\$95**

NUMBER SMASHER/ECM™

Triples the speed of your PC, XT or compatible!

From \$599



12 MHz Accelerator Plus A Megabyte for DOS

PC Magazine "Editor's Choice"

DATA ACQUISITION and REAL TIME TOOLS

DAL™ - "Data Acquisition Language."

Unkelscope™ - A real time data acquisition, control and process software pkg.

87FFT and 87FFT-2


TransView Menu driven FFT Spectrum/transfer analyzer. **\$250**

RTOS - REAL TIME OPERATING SYSTEM

A multi-user, multi-tasking real time operating system. Includes a configured version of Intel's iRMX-86, LINK-86, LOC-86, LIB-86, OH-86 and the MicroWay 87DEBUG. Runs on the IBM-PC, XT, PC-AT and COMPAQ. **\$600**

INTEL COMPILERS Available for RTOS FORTRAN-86, PASCAL-86, PL/M-86.

287 Turbo™ -10/12



287 Turbo runs the 80287 at 10 or 12 MHz in the IBM PC AT, compatibles and the new Compaq 386 with 100% software compatibility.
10 MHz **\$450**
12 MHz **\$550**

PC Magazine "Editor's Choice"

8087 UPGRADES

All MicroWay 8087s include a one year warranty, complete MicroWay Test Program and installation instructions.

8087 5 MHz **\$114**
For the IBM PC, XT and compatibles

8087-2 8 MHz **\$149**
For Wang, AT&T, DeskPro, NEC, Leading Edge

80287-3 5 MHz **\$179**
For the IBM PC AT and 286 compatibles

80287-6 6 MHz **\$229**
For 8 MHz AT compatibles

80287-8 8 MHz **\$259**
For the 8 MHz 80286 accelerator cards


80287-10 10 MHz **\$395**
For the Compaq 386

Call for prices on V20, V30, 64K, 128K and 256K RAM

A2D-160™

The Fastest 12 bit A/D Converter

\$1295



160,000 Samples per second
Pseudo Random Noise Generator/DAC
Optional signal conditioners
AFM-50 Programmable Low Pass Filter Module. **\$225**


8087 SOFTWARE

IBM BASIC COMPILER **\$465**
MICROSOFT QUICK BASIC **\$79**
87BASIC COMPILER PATCH. **\$150**
IBM MACRO ASSEMBLER. **\$155**
MS MACRO ASSEMBLER. **\$99**
87MACRO/DEBUG. **\$200**
MICROSOFT FORTRAN. **\$209**
RM FORTRAN. **\$399**
LAHEY FORTRAN F77L. **\$477**
MS or LATTICE C. **CALL**
STSC APL★PLUS/PC. **\$450**
STSC STATGRAPHICS. **\$675**
SPSS/PC+. **\$675**
87SFL Scientific Functions. **\$250**
PHOENIX PRODUCTS. **CALL**
FASTBREAK for 1-2-3 V.1A. **\$79**
HOTLINK for 1-2-3 V.1A. **\$99**

287 TURBO-PLUS™

Speeds up your AT

Adjustable 80286 Clock 6-12 MHz
10 MHz 80287 Clock
Plus Full Hardware Reset. **\$149**
Optional 80286-10



287TURBO-PLUS
With 80287 10 MHz. **\$549**
With 80287 12 MHz. **\$629**


CALL (617) 746-7341 FOR OUR COMPLETE CATALOG

MicroWay

P.O. Box 79
Kingston, Mass.
02364 USA
(617) 746-7341

**The World Leader
in 8087 Support!**


MicroWay Europe
32 High Street
Kingston-Upon-Thames
Surrey England KT1 1HL
Telephone: 01-541-5466



Better BASIC™


NOW INTRODUCING VIRTUAL MEMORY SUPPORT

BetterBASIC with the optional Virtual Memory Manager can now address 400,000,000,000 bytes of memory!




BetterBASIC Application Development System \$199.00

The BetterBASIC Application Development System provides very close compatibility with PC-BASIC and GW-BASIC, yet provides numerous new and sophisticated language features such as: program Block Structures, recursive Procedures and Functions with local variables, structures, Records and Pointers and last but not least support of large memory.




BetterBASIC Application Development System \$199.00

The BetterBASIC Application Development System provides very close compatibility with PC-BASIC and GW-BASIC, yet provides numerous new and sophisticated language features such as: program Block Structures, recursive Procedures and Functions with local variables, structures, Records and Pointers and last but not least support of large memory.




Virtual Memory Manager \$99.00

The Virtual Memory Manager expands Better-BASIC's data space into the gigabyte range and finally breaks the 640k byte barrier for array sizes. Not only can you directly address all expanded memory supported by LIM/EMS memory boards, you can also address any RAM Disk, Hard Disk or even a Floppy Disk as if they were ordinary RAM.




C-Link \$99.00

This software package allows BetterBASIC to access C-language library functions from within BetterBASIC. Currently supported are Lattice and Microsoft C.




Screen Design System \$199.00

This package truly takes the drudgery out of creating display screens and data entry screens. An interactive Screen Editor lets you "paint" your display screens exactly as you want them to appear in your program. The completed screens take the form of disk resident images. A run time library module provides many new BetterBASIC procedures and functions for interacting with the display screens to simplify the use of pop-up menus and data entry screens.




Btrieve™ Interface \$99.00

This is a high level BetterBASIC interface to the ever popular Btrieve™ file manager from SoftCraft. Instead of Assembly language calls this module provides high level BetterBASIC program access to all Btrieve™ functions. Use it to design your own database application in BetterBASIC.




8087/80287 Math Module \$99.00

This module allows you to use the 8087 or 80287 co-processor to significantly accelerate programs which are floating point calculations intensive.




Decimal Math Module \$99.00

If you are a business programmer, you are probably frustrated by the many roundoff problems caused by ordinary IEEE format floating point numerical operations. The BetterBASIC Decimal Math Module which offers variable precision from 6 to 24 digits, drastically reduces roundoff problems in business applications.



BetterTools™ \$99.00

This is a collection of more than 150 useful extensions to BetterBASIC such as time and date computations, encryption and decryption, low level file directory access, hyperbolic function and much more. No BetterBASIC programmer should be without BetterTools™.



Virtual Memory Manager-Network Version \$250.00

This version of the Virtual Memory Manager allows Virtual Memory to be distributed throughout a Local Area Network. It also provides File, Records and Field Locking to control access to shared data.

**Call our Toll Free Order Line
1-800-255-5800**

Better BASIC.

Summit Software Technology, Inc.™

106 Access Road, Norwood, MA 02062

contents of the indicated number register.

There are preincrement and decrement syntaxes, too: `\n+x`, `\n+(xx`, `\n-x`, and `\n-(xx`. With these syntaxes the number register is incremented (or decremented) by a predetermined amount before the escape sequence is interpolated. Nonexistent

number registers expand to 0. You can use number registers both in commands and embedded in the text.

Several number registers are created and maintained by `nr` itself (see Table 5, below). These hold such things as the current page number.

You can use number registers to do things such as keep track of the current footnote number. For example, `.nr fn 0` creates a number register called `fn` that will hold the footnote

number. You can access this register with `\n(fn`, but if you use `\n+(fn`, then the register will be incremented automatically before it's expanded. This process can in turn be hidden in a string—`.ds * \u \n+(fn d`. Here the `\u` and `d` send the cursor up and down half a line. You need two backslashes to prevent `nr` from expanding the number register at definition time. You can now expand the string with a `**` in the text, thereby both printing and incrementing the current footnote number. The number register is incremented before it's expanded.

Number registers can be expanded into the text in several formats. That is, the number is just a number, but it can be expanded as an Arabic number (with optional zero fill), as an uppercase or lowercase Roman numeral, in outline format (`a`, `b`, `c`, `z` . . . `aa`, `ab` . . . `az`), or in English words (one thousand, two hundred fifty-seven).

`.nr name [+ -]N [[-]M]`—create or modify number register `name` by `N`. For example, `.nr x 10` creates a number register called `x` and initializes it to 10, and `.nr x +5` increases the contents of `x` to 15. `M` is the increment amount (the default is 1 if `M` is absent). When the number register is accessed using the `\n+x` or `\n+(xx` syntax, then `M` is added to the register before it is expanded. `M` may be negative. Unlike `nroff`, `nr`, with no arguments, prints a list of all currently defined number registers and their contents.

`.rr name`—remove the named number register.

`.af name mode`—alter the expansion format of the named number register to the indicated mode. Default is Arabic. Legal values of `mode` are shown in Table 6, page 109. The leading 0s in the Arabic formats (as in the second and third lines of Table 6) determine the field width of the number.

In my next column, I'll conclude this user's manual by describing tabulation, control flow, hyphenation, line numbering, and more.

Availability

The February, March, and April 1987 C Chests have been combined to cre-

The following parameters are saved:

- the unprinted contents of the fill buffer (the buffer is cleared after its contents are stored)
- the input line trap (it's cleared after being saved)
- the count associated with the `.cu`, `.ul`, `.bo`, or `.os`—all these are set to zero after being saved
- the adjustment mode (as set with `.ad`)
- the current font (as set with `\f` or `.ft`)
- the command character (as set with `.cc`)
- the escape character (as set with `.ec`)
- the current no-break character (as set with `.c2`)
- the fill status (line filling enabled [`.fi`] or disabled [`.nf`])
- the indent level (as set with `.in`)
- the page offset (as set with `.po`)
- the line spacing (as set with `.ls`)
- the line-numbering values (as set with `.nm`)
- the margin characters (`.mc` and `.lm`)
- the tab stops and the tab and leader expansion characters
- the line length (`.ll`)
- the temporary indent (`.ti`)
- the three-part title length (`.tl`)

Table 4: The contents of an environment

| | |
|------------------|---|
| <code>%</code> | current output page number |
| <code>dl</code> | width of (maximum line length of any line in) the most recently completed diversion |
| <code>dn</code> | height of (numbers of lines in) most recently completed diversion |
| <code>dy</code> | day when execution started (1–31) |
| <code>h</code> | hour when execution started (1–24) |
| <code>hp</code> | current horizontal place on input line |
| <code>ln</code> | current line number used by the <code>.nm</code> command for line numbering. |
| <code>m</code> | minute when execution started (1–59) |
| <code>nl</code> | current output line number (used by <code>.nm</code>) |
| <code>mo</code> | month when execution started (1–12) |
| <code>s</code> | second when execution started (1–59) |
| <code>wd</code> | day of the week when execution started (1–7, 1 is Sunday) |
| <code>yr</code> | year (for example, 1987) |
| <code>.\$</code> | number of arguments to the current macro |
| <code>.c</code> | number of lines read from current input file. |
| <code>.d</code> | vertical place in current diversion (distance from line 1). |
| <code>.f</code> | currently active font (can be stored and then passed to <code>.ft</code> later on). |
| <code>.i</code> | current indent column (as set with a <code>.in</code>) |
| <code>.l</code> | current line length (as set with a <code>.ll</code>) |
| <code>.n</code> | length of the text part of previous output line |
| <code>.o</code> | current page offset (as set with <code>.po</code>) |
| <code>.p</code> | current page length (as set with <code>.pl</code>) |
| <code>.t</code> | distance to next trap (in lines) (very large if there's no trap) |
| <code>.u</code> | 1 if in fill mode, 0 otherwise |
| <code>.v</code> | current line spacing (as set with <code>.ls</code>) |

Table 5: Predefined number registers

ate *Nr: An Nroff-Like Text Processor for MS-DOS*. This reprint is available with a source-code disk for \$29.95. Send prepaid orders to M&T Books, 501 Galveston Dr., Redwood City, CA 94063 or call (415) 366-3600, extension 216. Please add \$2.25 for shipping and handling (\$5 for foreign orders).

DDJ

(Listings begin on page 48.)

Vote for your favorite feature/article.
Circle Reader Service No. 4.

| Mode | Register Expands As |
|------|--|
| 1 | 1, 2, 3, 4, . . . |
| 01 | 01, 02, 03, 04, . . . |
| 001 | 001, 002, 003, 004, . . . |
| i | i, ii, iii, iv, v, vi, vii, . . . |
| I | I, II, III, IV, V, VI, VII, . . . |
| a | a, b, c, . . . z, aa, ab, ac . . . az, ba, bb, . . . |
| A | A, B, C, . . . Z, AA, AB, AC . . . AZ, BA, BB, . . . |
| e | one, two, three, four, five, six, . . . |
| E | One, Two, Three, Four, Five, Six, . . . |

Table 6: Number register output formats

Flotsam and Jetsam

➤ Definitions, Declarations, and Casts

Kernighan and Ritchie, for reasons unknown to myself, use the terms *declaration* and *definition* in a special way. Unfortunately, the way they use these words is the inverse of the way in which every other programmer thinks of them. A declaration is an announcement (at least according to *Webster's*). Consequently K & R use the word *declaration* to mean that you are announcing the presence of a variable to the compiler. You aren't allocating space for that variable; you're just announcing its presence somewhere in some module in your program. The linker will find the actual variable when the modules are linked. An *extern* statement is used to declare a variable in K & R's sense of the word.

On the other hand, *Webster's* says that to define an object is to "fix or mark the limits" of that object, to allocate space for the object. So a variable definition in C is what actually allocates space for a variable. This usage is backward from the normal usage, thus the confusion. A declaration is always implicit in a definition—when you allocate space for an object (define it), you also tell the compiler that the object exists somewhere (here).

The declaration/definition conundrum can cause problems. A particularly nasty one is brought about by implicit declarations of subroutines. If you use a subroutine that hasn't been previously declared (with either an *extern* statement or a real definition), the compiler assumes that the subroutine returns an *int*. The problem arises when you then use

the cast operator in conjunction with the implicit declaration.

A cast operator temporarily changes the type of a specific object. It is formed by writing a variable declaration of the required type, surrounding the declaration with parentheses, and then removing the name and semicolon. For example, you'd declare a character pointer with:

```
char *Dostoevski;
```

You change the declaration to a cast by surrounding the foregoing with parentheses:

```
(char *Dostoevski);
```

and removing the name and semicolon:

```
(char *)
```

You can now convert an object to a character pointer by preceding its use with the cast.

An example: you've defined an *int*-size variable called *baton* and want to pass it to a subroutine called *runner()*, which expects a *double*-size argument. You can force an *int*-to-*double* type conversion with a cast:

```
runner( (double) baton );
```

The definition/declaration problem arises when you try to use a cast to change the type of an object that was implicitly declared as type *int*. For example, the following will not work as expected in the 8086 medium or large models:

```
struct building *tourist;
tourist = (struct building *)
    malloc( sizeof(struct building) );
```

You had intended to convert the character pointer returned from *malloc()* into a building pointer. The compiler doesn't know that *malloc()* returns a character pointer, however. It assumes that *malloc()* returns an *int* because there's no preceding *extern* statement. Pointers and *ints* are different sizes in the 8086 medium or large models, however. (An *int* is probably 16 bits wide, and a pointer is probably 32 bits wide.) Because the compiler thinks that *malloc()* returns an *int*, it truncates the 32-bit pointer down to 16 bits—the size of an *int*. Only now will it look at the cast operator, converting the *int* back to a pointer. Unfortunately, the precision that you lost when the variable was truncated is still lost. That is, the upper 16 bits of the pointer are lost forever, converted to 0s.

You can fix the problem by telling the compiler that *malloc()* indeed returns a pointer of some sort. Use either:

```
extern char *malloc();
tourist = (struct building *)
    malloc( ... );
```

or:

```
extern struct building *malloc();
tourist = malloc( ... );
```

In the first example, you're converting a character pointer to a building pointer. As both of these pointers are the same width, no precision is lost. ☐

80386 Resources

Attendees of the November 1986 Comdex in Las Vegas found themselves deluged by Intel 80386 hype and hysteria from vendors and press alike. I'll be discussing this interesting new supermicro at length in these pages after Santa brings me a 80386-based machine or accelerator board to play with; in the meantime, here are some helpful sources of information:

80386 Programmer's Reference Manual. About 350 pages. Intel order number 230985-001.

This manual covers architecture, memory management, memory protection, multitasking, input/output, exception and interrupt handling, debugging support, virtual 8086 mode, and mixing 16-bit and 32-bit code, and it has a full reference section on the individual instructions. It's a must-have for would-be 80386 programmers.

80386 Hardware Reference Manual. Intel order number 231732-001.

This book covers internal architecture and pipelining, local bus interface, coprocessor interface, and memory cache. It's for hardware knowledgeable types only.


Introduction to the 80386. Intel order number 231252-001.

A nice readable overview of the 80386 in its native 32-bit processing

by Ray Duncan

mode and its support for paging, memory protection, and multitasking. It also includes a discussion of upward compatibility from 8086, 286 protected mode, and the virtual 86 mode.

80386: A Collection of Article Reprints. 60 pages. Intel order number 231737-001.



A compilation of recent feature articles from *Electronic Design*, *IEEE Micro*, *Computer Systems*, and *Tech Notes*.

The 80386: A High Performance Workstation Microprocessor. Intel order number 231776-001.

An evaluation of the throughput of the 80386 and comparisons with other popular processors. It includes the C source code for the Dhrystone and Whetstone benchmarks.

80386 High Performance 32-Bit Microprocessor with Integrated Memory Management. Product data sheet dated April 1986. 131 pages. Intel order number 231630-002.

A very terse summary of the hardware reference and programmer's reference mentioned earlier.

You can order all the above from Intel Literature Sales, P.O. Box 58130, Santa Clara, CA 95052-8130; (800) 548-4725. Intel's telephone order service is courteous, and delivery is prompt. The Intel publication catalog, order number 210620-010, is free for the asking.

80386 Un-Resources

Murray, William H., III, and Pappas, Chris H. *80386/80286 Assembly Language Programming*. Berkeley, Calif.: Osborne/McGraw-Hill, 1986. 548 pages with index. ISBN 0-07-881217-8.

This is the 80386 reference book not to buy; it is a sad example of a publisher's unscrupulous attempt to cash in on a new technology. Murray's book is essentially about 8086 programming with a few nods to the

additional instructions and protected mode of the 80286, and it makes only token references to the 80386. The few program fragments that illustrate the 80386's 32-bit instructions would never run if assembled in current environments because they don't include the 32-bit override byte. Some of the more interesting features of the 386, such as caching, pipelined instruction execution, segments up to 4 gigabytes in length, and bit instructions, are not covered at all.

Assembly-Language Resources

The November/December 1986 issue of *Programmer's Journal* contains two articles that 16-Bit Toolbox readers will find especially useful. M. Steven Baker has contributed an explanation of Terminate and Stay Resident utilities that includes discussion of the In-DOS flag (*int 21h*, function 34h) and the Multiplex Interrupt (*int 2fh*). George Defenbaugh has written an article on "Parents, Children, Redirection, and Piping" that discusses the MS-DOS *DUP* and *CDUP* functions (*int 21h*, functions 45h and 46h).

The Byte Information Exchange (BIX) has an exceptionally active and useful conference called MS-DOS Secrets. This conference already contains nearly a thousand messages about undocumented MS-DOS interrupts, TSR techniques, MS-DOS bugs and work-arounds, and the like. If you are a serious MS-DOS programmer, you will find the cost of a BIX account more than justified by this conference alone.

William Claff was kind enough to send me copies of the first eight issues of his monthly newsletter, *PC Tech Report*. These issues cover such topics as the *ASSUME* and *GROUP* directives, making .EXE files resident, device driver templates, 8087 programming, and a complete critical error

SAS Institute Inc. Announces

Lattice C Compilers for Your IBM Mainframe

Two years ago...

SAS Institute launched an effort to develop a subset of the SAS® Software System for the IBM Personal Computer. After careful study, we agreed that C was the programming language of choice. And that the Lattice® C compiler offered the quality, speed, and efficiency we needed.

One year ago...

Development had progressed so well that we expanded our efforts to include the entire SAS System on a PC, written in C. And to insure that the language, syntax, and commands would be identical across all operating systems, we decided that all future versions of the SAS System—regardless of hardware—would be derived from the same source code written in C. That meant that we needed a C compiler for IBM 370 mainframes. And it had to be good, since all our software products would depend on it.

So we approached Lattice, Inc. and asked if we could implement a version of the Lattice C compiler for IBM mainframes. With Lattice, Inc.'s agreement, development began and progressed rapidly.

Today...

Our efforts are complete—we have a first-rate IBM 370 C compiler. And we are pleased to offer this development tool to you. Now you can write in a single language that is source code compatible with your IBM mainframe and your IBM PC. We have faithfully implemented not only the language, but also the supporting library and environment.

Features of the Lattice C compiler for the 370 include:

- **Generation of reentrant object code.** Reentrancy allows many users to share the same code. Reentrancy is not an easy feature to achieve on the 370, especially if you use non-constant external variables, but we did it.
- **Optimization of the generated code.** We know the 370 instruction set and the various 370 operating environments. We have over 100 staff years of assembler language systems experience on our development team.
- **Generated code executable in both 24-bit and 31-bit addressing modes.** You can run compiled programs above the 16 megabyte line in MVS/XA.
- **Generated code identical for OS and CMS operating systems.** You can move modules between MVS and CMS without even recompiling.
- **Complete libraries.** We have implemented all the library routines described by Kernighan and Ritchie (the informal C standard), and all the library

routines supported by Lattice (except operating system dependent routines), plus extensions for dealing with 370 operating environments directly. Especially significant is our byte-addressable Unix®-style I/O access method.

- **Built-in functions.** Many of the traditional string handling functions are available as built-in functions, generating in-line machine code rather than function calls. Your call to move a string can result in just one MVC instruction rather than a function call and a loop.

In addition to mainframe software development, you can also use our new cross-compiler to develop PC software on your IBM mainframe. With our cross-compiler, you can compile Lattice C programs on your mainframe and generate object code ready to download to your PC.

With the cross-compiler, we also offer PLINK86™ and PLIB86™ by Phoenix Software Associates Ltd. The Phoenix link-editor and library management facility can bind several compiled programs on the mainframe and download immediately executable modules to your PC.

Tomorrow...

We believe that the C language offers the SAS System the path to true portability and maintainability. And we believe that other companies will make similar strategic decisions about C. Already, C is taught in most college computer science curriculums, and is replacing older languages in many. And almost every computer introduced to the market now has a C compiler.

C, the language of choice...

C supports structured programming with superior control features for conditionals, iteration, and case selection. C is good for data structures, with its elegant implementation of structures and pointers. C is conducive to portable coding. It is simple to adjust for the size differences of data elements on different machines.

Continuous support...

At SAS Institute, we support all our products. You license them annually; we support them continuously. You get updates at no additional charge. We have a continuing commitment to make our compiler better and better. We have the ultimate incentive—all our software products depend on it.

For more information...

Complete and mail the coupon today. Because we've got the development tool for your tomorrow.



SAS Institute Inc.
SAS Circle, Box 8000
Cary, NC 27511-8000
Telephone (919) 467-8000 x 7000

I want to learn more about:

- ☐ the C compiler for MVS software developers
- ☐ the C compiler for CMS software developers
- ☐ the cross-compiler with PLINK86 and PLIB86

today...so I'll be ready for tomorrow.

Please complete or attach your business card.

Name _____
Title _____
Company _____
Address _____
City _____ State _____ ZIP _____
Telephone _____

Mail to: SAS Institute Inc., Attn: CC, SAS Circle, Box 8000, Cary, NC, USA.
27511-8000. Telephone (919) 467-8000, x 7000

DDJ 3/87

(int 24h) handler. The more recent newsletters range from 6-11 pages in length and have a heavy emphasis on working source code. Subscriptions cost \$18 per year. Contact Mr. Claff at 7 Roberts Rd., Wellesley, MA 02181; (617) 235-9505.

Call for Papers

The Waite Group, a San Francisco-based computer book developer and publisher, is looking for contributing authors for a new book on MS-DOS entitled *The MS-DOS Papers*.

The news release from the Waite Group says: "The *MS-DOS Papers* will be a collection of learning tutorials written by a broad range of MS-DOS experts, gurus, wizards, and spokespersons. The *MS-DOS Papers* will provide insightful information on the MS-DOS operating system, revealing the more hidden and obscure truths about MS-DOS in an interesting, easy to read Waite Group format. Its contributed nature allows us to include subjects that might not support a separate book as well as subjects that are on the cutting edge of MS-DOS technology. The audience level is intermediate to advanced businesspeople, programmers, and anyone who wants the most up-to-date information about this popular operating system. Examples are given in both MS-C and MASM.

"The book will consist of three types of contributions:

- Tutorials on topics that have never been adequately discussed in the literature. These include inside BIOS, tips and undocumented secrets, stay resident programming, advanced MASM programming, and debugging as well as new concepts arising in MS-DOS, such as protected mode MS-DOS and CD ROMs.
- Issue papers by experts in a particular area of MS-DOS. These will discuss past controversies, the future of MS-DOS, and so on.
- Case-history papers, which will tell the bottom line about real MS-DOS machines, projects, and software tools."

For more information, contact Mitchell Waite at one of the follow-

ing electronic mail addresses:

BIX: mwaite

The WELL: mitch

Usenet: lll-lcc, hplabs)!well!mitch

A Nifty Tool

Cruise Control is a Terminate and Stay Resident (TSR) utility for IBM PCs and compatibles that eliminates *cursor runon*, the term the utility's author uses for the behavior of programs that cannot process keystrokes as fast as the keyboard's auto-repeat rate. When you are using such a pro-

gram and hold down a key, the keystrokes pile up in the type-ahead buffer until it is full and then you hear a beep that tells you to release the key. The piled-up keystrokes are then processed until the buffer is empty, so you frequently tab or scroll much farther than you intended to. Lotus 1-2-3, WordStar, and Microsoft Word are three commonly used programs that have this problem on older 8088 or 8086-based PCs.

The primary effect of Cruise Control is that it monitors the type-ahead buffer and dynamically adjusts the

Name

PASTE—horizontally concatenate two files

Synopsis

paste [-paste] [-b <string>] [-<n>] [file1] [file2]

Description

PASTE will append to the lines of <file1> the corresponding lines of <file2>, with an optional string between them. PASTE writes to standard output.

The following flags are recognized by PASTE:

- p <file1> does not exist (<string> is prepended to each line).
- a <file2> does not exist (<string> is appended to each line).
- s Do not print <string> with lines from only one file.
- t Resolve the ambiguous command *paste <file>*. The -t flag forces <file> to trail standard input—that is, *paste <file>* is equivalent to *paste <file> <stdin>*, and *paste -t <file>* is equivalent to *paste <stdin> <file>*.
- e Do not print <string> if both input lines are empty (contain no characters but '\n').
- b Indicates that a string of characters follows. The string is inserted between each line of <file1> and <file2>. The string can contain all the standard escape codes with the exception of '\0'. The escape sequence '\s' is also known to represent a blank. Blanks may also be embedded in a string by enclosing the string in quotes.
- <n> Print n lines of <file1> before appending lines of <file2>. If n is negative (for example, *paste - -3*), then n lines of <file2> will be printed first.

Bugs

On some systems, you'll have to use an escape sequence to represent capital letters in *string*. Also, a quoted string with multiple blanks can have them reduced to single blanks on systems that do not recognize quote marks as special—use the escape sequences '\s' or '\ '.

As of this writing, the standard escape sequences are:

```
\b  backspace
\f  form feed
\n  new line
\r  carriage return
\t  tab
\0  null character (not allowed in string argument)
\\  literal backslash
\"  literal quote mark
\'  literal apostrophe
\ddd bit pattern, consisting of 1 - 3 octal digits
```

Escape sequences special to PASTE:

```
\s  space
```

A backslash followed by any other character merely represents that character.

Author

John M. Gamble, January 1984

Table 1: Instructions for using the PASTE utility

keyboard auto-repeat rate to match the program's capability to process the keystrokes. This means that you never tab, page, or scroll past your desired destination. For those programs that can handle it, the apparent speed of many keys (such as the arrow or page keys) is drastically increased.

It sounds like a simple concept, but the difference in the behavior of your computer and favorite editor with Cruise Control installed is dramatic. I have used it with both Microsoft Word and MicroPro's WordStar with excellent results. Cruise Control also offers a few nifty fringe benefits, such as an automatic screen dimmer after a configurable time delay, on-line help, and a date and time stamp with configurable formats. The vendor claims that the utility is compatible with most other RAM-resident programs; it worked fine for me with both SideKick and ProCED.

You can obtain Cruise Control from Revolution Software Inc., 715 Rte. 10 E, Randolph, NJ, 07869; (201) 366-4445.

Programming Pearl of the Month

Richard Rodman, of Falls Church, Virginia, writes: "Here's a helpful hint for programmers attempting to write adapting I/O routines.

"The IBM PC data bus is not pulled up. If you try to read a data port to see if the board is or is not installed, and the board is not installed, you may get a false indication because the floating bus still contains the last data byte that was fetched by the CPU.

"To correct this problem, you need to ensure that the bus contains a pattern with as many bits set to 1 as possible. One method of doing this is shown below:

```
clc
clc
clc
clc
clc
clc
in al,dx
clc
clc
clc
clc
clc
clc
```

"The 8088's instruction prefetch queue is 6 bytes long. The six *clc* instructions (opcode *0f8h*) on each side of the *in* instruction allow the bus to float at a value of *0f8h* hex for unimplemented hardware.


"The real solution, of course, would have been a terminated bus. Unfortunately, the IBM PC was a quick and dirty design."

The PASTE Utility

John Gamble of West Lafayette, Indiana, has sent in a useful program called PASTE that appends the lines of one file to the end of the lines of an-

other file and writes the resulting lines to the standard output device. PASTE can be used to horizontally concatenate tables or columns of information that have been edited separately. The program optionally prepends, appends, or inserts a string into the newly generated lines. Table 1, page 112, contains instructions for using the program, and the program's source code accompanies this column as Listing One, page 78. I have tested the program before publication with Microsoft C, Version 4.0, and MS-DOS, Version 3.1.

John writes: "I have found this pro-



There's never been a better time to buy Lattice C. Professional programmers the world over have made Lattice C the standard compiler for serious MS-DOS programming. Our compiler features include: ANSI language constructs including, *unsigned* as a modifier, *void* data type, *enum* data type, structure assignments, structure arguments, structure returns, and argument type checking.

The library contains more than 200 new functions, including: ANSI/UNIX/XENIX compatibility; extended support for MS-DOS; extended support for networking including file sharing, file locking, and I/O redirection; and flexible error handling via user traps and exits. Plus the library has also been re-engineered to produce much smaller executables.

Try the new Lattice C Compiler. Because C-ing is believing.




Lattice, Incorporated
P.O. Box 3072
Glen Ellyn, Illinois 60138
312/858-7950
TWX 910-291-2190

INTERNATIONAL SALES OFFICES:

Benelux: Ines Datacom (32) 2-720-51-61 Japan: Lifeboat Inc. (03)293-4711
England: Roundhill (0672)54675 France: SFL (1)46-66-11-55
Germany: (49)7841/4500 (49)8946/13290

PROFESSIONAL PROLOG FOR THE PROFESSIONAL PROGRAMMER



**The AI Starter Kit
from LOGICWARE.
All for \$220.00.**

You are in the market for serious AI tools. You are just getting started — but you have plans for bigger, more serious work. Your purchasing criteria:

- You want an inexpensive product — but not an "AI toy".
- You are doing your initial work on a PC — but you want a product that is flexible and portable. You want the option of expanding your serious work to other, larger computers.
- You do not want to face any dead ends a month or a year down the road.
- You want to invest in a product line that does not leave you stranded when you take that inevitable next step.

Logicware Inc., the leading supplier of Prolog and Prolog-based AI tools, has a solution for you — our *AI Starter Kit*. This starter kit includes:

- **The P-550 product:**
An inexpensive, but full-featured implementation of Prolog. It consists of our full MProlog *interpreter* and our interactive programming environment with a full screen editor. This product also contains *Eagle Graphics* — a full set of graphics predicates that allow you to create three-dimensional graphics for your PC applications.
- **The *Primer*:**
Our introduction to the Prolog language and to the concepts of logic programming — a 500-page textbook and two-diskette tutorial software. The best hands-on introduction to Prolog on the market today.

Both P-550 and the *Primer* software require 512K RAM, DOS 2.0 (or later) and a minimum of two floppy drives.

MProlog is also available for IBM mainframes, DEC VAX and M68000 workstations.

To order, clip and mail the postcard below. For more information call (416) 672-0300 and ask for Chris Glenn.

Circle no. 366 on reader service card.

Clip and mail to:

LOGICWARE INC., Micro Division,
70 Walnut Street, Wellesley, MA. 02181

Name _____

Address _____

State/Prov. _____

Zip/Postal Code _____

☐ Please bill my charge card

Charge Card Name: _____

Account #

| | | | | | | | | | | | | | | | | | | | |
|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|
| | | | | | | | | | | | | | | | | | | | |
|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|

Logicware Inc.

Company _____

Telephone _____


☐ Enclosed is a check or money order to LOGICWARE INC.

Valid from ____/____/____ to ____/____/____

Signature: _____


Think fast! Pick the better fit...

Our 5th Year Bonus!
Mention this ad when ordering
and get your choice of a V 20-8
(replaces 8088) or \$20 off on
your Battery Backup purchase!



FLOPPY DISK.

- Fills time between coffee breaks
- Makes a hard disk seem *fast*
- Your computer appears busy (even if you aren't!)
- Wears out moving parts



SEMIDISK Disk Emulator.

- Gets that job done *NOW*
- Makes a hard disk seem *slow*
- Maximizes your productivity with anything from databases to compilers
- Totally silent operation

...for YOUR demanding tasks.

SURPRISE! Neither is memory mapped, so they don't affect your precious Main Memory. *Both* retain data indefinitely - even with the computer turned off.

THE SEMIDISK SOLUTION. You could invest in a series of "upgrades" that turn out to be expensive band-aids without solving your real problem. Even those "Accelerator" and "Turbo" boards do little to speed up disk-bound computers. If your applications spend too much time reading and writing to disk (and whose don't?), you won't want to settle for anything less than a SemiDisk disk emulator. The SemiDisk comes in 512K and 2Mb capacity. More boards may be added to make up to an 8 Megabyte SemiDrive!

SPEED THAT'S COMPATIBLE. PC, XT or AT, if you need speed, the SemiDisk has it. How fast? Recent benchmarks show the SemiDisk is from 2 to 5 times faster than hard disks, and from 25% faster (writing) to several times faster (random reads) than VDISK and other RAMdisk software that gobble up your main memory.

MEMORY THAT'S STORAGE. Using our small external power supply, with battery backup, your data remains intact through your longest vacation or even a seven-hour power failure!

CELEBRATE WITH US! Now, SemiDisk celebrates its fifth birthday with a special offer for IBM-PC owners. Buy a SemiDisk now and we'll include an 8 MHz V-20 microprocessor (replaces the 8088) to make your new SemiDisk run even faster. Don't need the V-20? We'll take \$20 off the price of your Battery Backup Unit!

| | 512K | 2Mbyte |
|-------------------|-------|--------|
| IBM, PC, XT, AT | \$495 | \$ 795 |
| Epson QX-10 | \$495 | \$ 995 |
| S-100 SemiDisk II | \$795 | \$1295 |
| S-100 SemiDisk I | \$299 | ----- |
| TRS-80 II, 12, 16 | \$495 | \$ 995 |
| Battery Backup | \$130 | \$ 130 |

Someday you'll get a SemiDisk.
Until then, you'll just have to...wait.

SemiDisk



SemiDisk Systems, Inc., 11080 S.W. Allen Blvd., Beaverton, Oregon 97005 (503) 626-3104

gram useful for creating command files on the fly for systems such as VMS or MS-DOS by taking a directory listing as an input file and attaching strings to the beginning or end of the lines. The Unix shell can do this by itself, but there are still some tricks that can be played with PASTE. For example, the command

```
paste -a -b '\n' afile.txt
```

will double-space the lines in afile.txt.

"I think that, if the program needs any improvement, it is in its method of input/output—it is done character by character. I really ought to have made it more efficient, but I fell foul of the 'good enough' syndrome and lost interest.

"[After writing this program] I learned that there is a similar Unix System V utility, also called PASTE. It appends the lines of one file to another, too, but it automatically inserts a tab between the lines and will accept more than two files on the command line—I think it is meant more for nroff text processing."

Semester Final

Larry Heberlein, of Maryville, Maryland, submits this little tidbit:

"Final Exam: Algorithm Design 101 Extra-Credit Question

You attempt a search and replace operation using a commercial word processor—the latest version of Word from Microsoft, the world's largest microcomputer software house. . . . You load a 20K file into a PC with 640K RAM. With the program and file loaded, 400K of memory are free. You attempt to replace every carriage return in the file with a space. Less than a quarter of the way through the file, the operation aborts with the error message 'insufficient memory.' You observe that this happens reliably, in any file, on any replacement, with a sufficiently large number of occurrences.

"An A for the course goes to any student who turns in a replacement algorithm so bad that it can't succeed in memory 20 times the size of the data."

Assembly vs. High-Level Languages

Charles Lyall of Kingman, Alberta, writes: "I couldn't let your invitation in the July 1986 issue of *DDJ* to discuss the assembly-language vs. high-level-language issue go unanswered.

"I am an EDP consultant who hacked his first piece of code in 1963 on an IBM 1620. Even in those days we were arguing the relative merits of assembly vs. higher-level languages. Now we have several fourth-genera-

***It is not
always true
that assembly-
language programs
run faster
than high-level
programs.***

tion languages that help to spice up the debate even more.

"I must take issue with your statement that 'It doesn't take me more than an hour or two to write a program the size of TEE from scratch in assembly language. . . .' The statement is false! Oh, I am quite sure that you could write it in Microsoft MASM for the IBM PC. Could you write it in two hours in assembly language for the VAX? No, then how about a Data General NOVA? A UNIVAC 1100 perchance? I think not. I can keep two assembly languages in my head at one time, but that is it. I doubt if you are truly fluent in more than two assembly languages either.

"What you really meant is that you can write TEE in assembly language for one particular machine in two hours. Mr. Gary Woodman can write the equivalent program in a few minutes for every machine that has a C compiler. I suggest that the C compiler is infinitely more productive.

"To quote you again: 'For me, the benefits of the superior performance and compactness of an assembly-language program almost always outweigh all other considerations for utility programs I am going to run more than once.' I submit that this is illogical. Let us put some numbers on it, Ray. Suppose Gary Woodman's

program runs in 10 seconds and your program runs in 1 second. But you took two hours to write your program, and Gary probably took 15 minutes. That's a difference of 105 minutes, or 6,300 seconds, of coding time. At a 9-second advantage per run, you are going to have to run the little turkey 700 times in order to break even on total elapsed time.

"It is not necessarily always true that assembly-language programs run faster and take less space than equivalent high-level-language programs. A case in point is a little routine available to strip the high-order bit from WordStar files. It is written in assembly language and handles its input and output one character at a time, and it uses DOS to redirect both input and output. It is slowwww! I wrote a C program that reads in 16K of input, strips the bit off using register variables for my pointers to make things trot along, and then writes the buffer. Now that moves. True, my routine is much bigger, but in this case I will cheerfully trade size for speed. It took only a few minutes to write, too.

"Your emphasis on performance and compactness is not without merit, and I can argue your side of the debate, too. The microcomputers we have had to deal with in the last ten years have been characterized by very limited memory, poor CPU performance, and expensive slow backing storage. Under these circumstances you can raise a heck of a good defense for your position. But this situation is coming to an end. A half megabyte of memory is now common. Processors such as the 80286 can almost get out of their own way, and the latest generation of 68000 chips are quite peppy. The 80386 machines will probably accept 16 megabytes of directly addressable memory (a 24-bit memory bus) and be two or three times as fast as the AT machines. [*The 80386 can actually address 4 gigabytes of physical memory and some 70 terabytes of virtual memory.*—Ray]

"Look what happens now to the numbers I gave you a few paragraphs back. If the machine is three times as fast, then your utility will run in 0.3 seconds and Gary's will run in 3.3 seconds. It will now take 2,100 executions of the utility before you

Subscribe to Micro/Systems Journal



**Yes! I want to subscribe to
Micro/Systems Journal
and save over 15% off the cover price.**

__ 1 Year (6 issues) \$20 __ 2 Years (12 issues) \$35

__ Please charge my: __ Visa __ MC __ American Express
__ Payment enclosed __ Bill me later

Card # _____ Exp. date _____

Signature _____

Name _____

Address _____

City _____ State _____ Zip _____

Canada & Mexico add \$3 for surface mail; \$7 for airmail. All other countries add \$12 for airmail. All foreign subscriptions must be prepaid in U.S. dollars drawn on a U.S. bank. Please allow 6-8 weeks for delivery of first issue.

A Publication of M & T Publishing, Inc.



**Yes! I want to subscribe to
Micro/Systems Journal
and save over 15% off the cover price.**

__ 1 Year (6 issues) \$20 __ 2 Years (12 issues) \$35

__ Please charge my: __ Visa __ MC __ American Express
__ Payment enclosed __ Bill me later

Card # _____ Exp. date _____

Signature _____

Name _____

Address _____

City _____ State _____ Zip _____

Canada & Mexico add \$3 for surface mail; \$7 for airmail. All other countries add \$12 for airmail. All foreign subscriptions must be prepaid in U.S. dollars drawn on a U.S. bank. Please allow 6-8 weeks for delivery of first issue.

A Publication of M & T Publishing, Inc.



**Yes! I want to subscribe to
Micro/Systems Journal
and save over 15% off the cover price.**

__ 1 Year (6 issues) \$20 __ 2 Years (12 issues) \$35

__ Please charge my: __ Visa __ MC __ American Express
__ Payment enclosed __ Bill me later

Card # _____ Exp. date _____

Signature _____

Name _____

Address _____

City _____ State _____ Zip _____

Canada & Mexico add \$3 for surface mail; \$7 for airmail. All other countries add \$12 for airmail. All foreign subscriptions must be prepaid in U.S. dollars drawn on a U.S. bank. Please allow 6-8 weeks for delivery of first issue.

A Publication of M & T Publishing, Inc.



NO POSTAGE
NECESSARY
IF MAILED
IN THE
UNITED STATES

BUSINESS REPLY MAIL

FIRST CLASS PERMIT NO. 790 REDWOOD CITY, CA

POSTAGE WILL BE PAID BY ADDRESSEE

For the Advanced Computer User

Micro/Systems Journal™

501 GALVESTON DR.
REDWOOD CITY, CA 94063



NO POSTAGE
NECESSARY
IF MAILED
IN THE
UNITED STATES

BUSINESS REPLY MAIL


FIRST CLASS PERMIT NO. 790 REDWOOD CITY, CA

POSTAGE WILL BE PAID BY ADDRESSEE

For the Advanced Computer User

Micro/Systems Journal™

501 GALVESTON DR.
REDWOOD CITY, CA 94063



NO POSTAGE
NECESSARY
IF MAILED
IN THE
UNITED STATES

BUSINESS REPLY MAIL


FIRST CLASS PERMIT NO. 790 REDWOOD CITY, CA

POSTAGE WILL BE PAID BY ADDRESSEE

For the Advanced Computer User


Micro/Systems Journal™

501 GALVESTON DR.
REDWOOD CITY, CA 94063



Subscribe to
Micro/Systems Journal

YOUR SYSTEM'S KEY COMPONENT



At last there is a magazine that brings you to strictly technical but practical information you need to stay up-to-date with the ever changing microcomputer technology . . .

In future issues of *Micro/Systems Journal* you'll find such useful and progressive articles as:

- Interfacing to Microsoft Windows
- Multiprocessing and Multitasking
- Using 80286 Protected Mode
- High Resolution PC Graphics
- 80386 Programming
- Unix on the PC

You'll get the hands-on, nuts and bolts information, insight and techniques that *Micro/Systems Journal* is famous for . . . in-depth tutorials, reviews, hints . . . the latest information on computer integration, networks and multi-tasking, languages, operating systems and hard-hitting reviews.

To start your subscription to *Micro/Systems Journal*, simply fill out one of the attached cards or write to *Micro/Systems Journal*, 501 Galveston Dr., Redwood City, CA 94063. You'll receive a full year (6 issues) of *Micro/Systems Journal* for just \$20, and enjoy the convenience of having M/SJ delivered to you each month. Don't wait . . . subscribe today!

Micro/Systems Journal™

break even! The faster a machine is, the less benefit assembly-language code is on that machine.

"A similar argument can be made about storage. The cheaper mass storage and memory become, the less advantageous compact code becomes. Accountants call it a rise in the opportunity cost. In other words, by writing a utility in assembly language, you forego the other utilities that you could have written if you had used a more productive language. Against this you balance benefits of program size and run time, which become less and less significant as computer speeds rise and primary and secondary storage costs decline.

"As a high priest, to use Jerry Pournelle's epithet, I use assembly language to answer two classes of problems: when I can't describe the procedure in a high-level language and when a critical small portion of the program runs too slowly.

"With the advent of true fourth-generation languages, your position is going to be even harder to defend. I

am currently designing a system using Powerhouse, a fourth-generation language for superminis. In less than three hours, I can generate a procedure to paint a screen with a form, accept any number of fields from that screen, and update a record or create a new record in a file that has three indexes. The generated procedure is about 8K long. On a VAX machine, the run time is sufficiently close to zero that it isn't material. I have no doubt that a good macro assembler programmer could write a similar routine in about a week. The resulting routine costs the client \$150 if I write it in three hours. The same routine written in assembly language is not worth a penny more. The Powerhouse code, which is nonprocedural, will be trivial to maintain.

"Interestingly enough, my company has encountered a problem with a communications handler, and the communications expert, a red-hot macro programmer, intends to solve that one in FORTRAN. Certainly he could solve it in assembly language, but he can do it cheaper in FORTRAN. On a 16-megabyte VAX 780, the run time and space disadvantages are

immaterial.

"In the long run, we spend three times as much time and effort on code maintenance than we do on the initial design and coding. To me, the benefits of clarity and simplicity in code and ease of maintenance outweigh all other considerations about 90 percent of the time. The other 10 percent of the time, we are dealing with the nasty bits that shouldn't be discussed in a family magazine.

"In conclusion, my position is that languages are tools to be used to solve problems and they are not ends in themselves. They have merits only to the extent that they help us meet our objectives. Two of these objectives are speed and compactness. Other objectives are clarity, simplicity, self-documentation, maintainability, programmer productivity in lines per day, and so on.

"A person who uses only one programming language puts me in mind of the man whose only tool is a hammer. All his problems look like nails."

Thanks, Charles, for a beautifully written, educational, and witty letter. I wouldn't want you to go away believing that my only tool is a hammer; I use Forth, C, and even BASIC (I hope that at least one of those meets your criteria for a high-level language). But I feel most at home with assembly language, and contrary to your assertion that it is not possible to be fluent in more than two assembly languages, I consider myself quite fluent in 8080, Z80, 80x86, PDP-11, and Raytheon 703 assembly language. I can also get by well enough in 6502, 8051, 8096, 68000, and 1802 assembler language. But I admit to total ignorance of the UNIVAC, Data General, and VAX that you mentioned!

Availability

All the source code for articles in this issue (except for C Chest) is available on a single disk. To order, send \$14.95 to Dr. Dobb's Journal, 501 Galveston Dr., Redwood City, CA 94063 or call (415) 366-3600 ext. 216. Please specify the issue number and format (MS-DOS, Macintosh, Kaypro).

DDJ

(Listing begins on page 78.)

Vote for your favorite feature/article.
Circle Reader Service No. 5.

Feel Constrained By PC BATCH Languages?

You need OPAL, a rich, full-functioned executive shell language for the experienced programmer.

Previously, you've had only limited capabilities with the batch exec languages available on the IBM PC. Now, OPAL frees you from the limitations and drudgery of BATCH, and other primitive executive languages.

OPAL, as an interpretive language, makes it easy to program the control you need in your applications. And, OPAL's compiler gives you even greater machine efficiency, when required.

Functionally, OPAL is a flexible shell that offers a high degree of programming, featuring flow-of-control, Menu and Form screen definition, CALLs, DO statements, DATE and string functions, to name a few. OPAL is so complete, some users have used it for prototyping entire applications!

Moreover, OPAL provides benefits through its synergy with DOS. OPAL understands how to work with and enhance your DOS environment.

If you feel encumbered and constrained by your current exec language, you *NEED* OPAL...

...only **\$169**

Texas residents add 6.125% sales tax
Shipping \$4.00
MasterCard, VISA Accepted

To order or receive more information:

(214) 490-0835

The Software Factory
INCORPORATED

15301 Dallas Parkway
Suite 750 LB 44
Dallas, TX 75248

IBM is a registered trademark of International Business Machines Corp.
OPAL is a trademark of The Software Factory, Inc.

Circle no. 361 on reader service card.

DR. DOBB'S TOOLBOOK SHELF

Dr. Dobb's Toolbook of 68000 Programming

In this complete collection of practical programming tips and techniques for the 68000 family, you'll find the best articles on 68000 programming ever published in Dr. Dobb's, along with new material from 68000 experts. You'll find a set of development tools, routines, useful applications, and examples to show you why computers using the 68000 chip family are easy to design, produce and upgrade. All programs are available on disk.

68000 Toolbook Item #040 \$29.95
68000 Toolbook with disk Item #041 \$49.95

Please specify one of the following disk formats: MS-DOS, CP/M 8", Osborne, Macintosh, Amiga, Atari 520st.

68000 Cross Assembler

An executable version of the 68000 Cross-Assembler discussed in the book is also available, complete with source code and documentation. Requires CP/M 2.2 with 64K or MS-DOS with 128K. Specify: 8" SS/SD, Osborne, MS-DOS

68000 Cross Assembler Item #042 \$25.00

Dr. Dobb's Toolbook of C

This authoritative reference contains over 700 pages, including the best C articles from Dr. Dobb's Journal, along with new material. You'll find hundreds of pages of valuable C source code, including a complete compiler, an assembler, and text processing programs.

Toolbook of C Item #005 \$29.95

The Small-C Compiler & Small-C Handbook

This compiler and handbook provide everything you need for learning how compilers are constructed, and for learning C at its most fundamental level. You'll find a discussion of assembly language concepts and program translation tools, and of how to generate a new version of the compiler. Full source code is included. Please specify MS/PC-DOS or CP/M: Kaypro, Osborne, Apple, Zenith Z-100 DS/DD, 8" SS/SD.

CP/M Compiler & Handbook Item #006B \$37.90
MS/PC-DOS Version Item #006C \$42.90

Small-Tools: Programs for Text Processing

This package of Small-C programs performs specific, modular operations on text files. It is supplied as source code with full documentation. With the Small-C Compiler, you can select and adapt these tools to meet your needs. Please specify MS/PC-DOS or CP/M: Kaypro, Osborne, Apple, Zenith Z-100 DS/DD, 8" SS/SD.

Small-Tools Item #010A \$29.95

Small-Mac: An Assembler for Small-C

This package includes: a simplified macro facility, C language expression operators, object file visibility, descriptive error messages and an externally defined instruction table. Source code and documentation is included. CP/M only. Please specify: Kaypro, Osborne, Apple, Zenith Z-100 DS/DD, 8" SS/SD.

Small-Mac Item #012A \$29.95

Dr. Dobb's Toolbook of Forth

Ed. by Marlin Ouverson

This comprehensive collection of useful Forth programs and tutorials contains Dr. Dobb's best Forth articles, expanded and revised, along with new material. Contents include: Mathematics in Forth, Modifications/Extensions, Forth Programs, Forth--The Language, Implementing Forth. All screens in the book are also available on disk as ASCII files.

Toolbook of Forth Item #030 \$22.95
Toolbook of Forth with disk Item #031 \$39.95

Please specify one of the following disk formats: MS/PC-DOS, Apple II, Macintosh, CP/M. For CP/M disks, specify Osborne or 8" SS/SD.

The Turbo Pascal Toolbook

Ed. by Namir Clement Shammas

This book contains routines and sample programs to make your programming easier and more powerful. You'll find: an extensive library of low-level routines; external sorting and searching tools; window management; artificial intelligence techniques; mathematical expression parsers including two routines that convert mathematical expressions into RPN tokens; and a smart statistical regression model finder. All routine libraries and sample programs are available on disk for MS-DOS systems. Over 400K of Turbo Pascal source code is included.

Turbo Pascal Toolbook Item #080 \$25.95
Turbo Pascal Toolbook with disk Item #081 \$45.95

Order Form

To Order: Return this order form with your payment to M&T Books, 501 Galveston Dr., Redwood City, CA 94063
Or, Call **TOLL-FREE 800-533-4372** Mon-Fri 8AM-5PM
In CA call **800-356-2002**

Name _____

Address _____

City _____ State _____ Zip _____

| Item # | Description | Price |
|--------|-------------|-------|
| | | |
| | | |
| | | |
| | | |

Please specify disk format

☐ MS/PC-DOS ☐ Macintosh ☐ Apple II

CP/M: ☐ Kaypro ☐ Osborne ☐ Apple ☐ Amiga

☐ Zenith Z-100 DS/DD ☐ 8" SS/SD ☐ Atari 520st

Subtotal _____

CA residents
add sales tax _____%

Add \$2.25 per item
for shipping _____

☐ Check enclosed. Make Payable to M&T Publishing.


Charge my ☐ VISA ☐ M/C ☐ Amer.Exp. **TOTAL** _____

Card No. _____

Exp. Date _____

Signature _____

BASIC: Quo Vadis?



In this issue, I discuss the differences between the IBM PC BASICA and the new True BASIC and QuickBASIC. I also include a short utility program to show interdialect translation and discuss several differences in these BASIC dialects.

In most cases, BASIC is the language that microcomputer users learn first, and in the IBM PC world, the implementation they encounter is Microsoft's BASICA. BASIC has been judged inadequate for large software projects, difficult to maintain, and lacking many new programming concepts. With the advent of structured languages, such as Turbo Pascal, programmers have been given the taste of better techniques, and the myth that BASIC will always be *the* language is no longer true.

New BASIC Dialects

The wheel of progress has not spared BASIC from change, however. Two years ago, the original authors of BASIC (Kemeny and Kurtz) launched True BASIC, a more structured implementation that is close to the new proposed ANSI BASIC. Almost simultaneously, Microsoft launched a new BASIC compiler version, QuickBASIC, and in mid-1986, it introduced Version 2.0, which includes a versatile environment. QuickBASIC is not just another compiler for BASICA—it brings with it a new syntax, similar in many instances to that of True BASIC.

by Namir Clement
Shammas

QuickBASIC does not require line numbers; instead, you place alphanumeric labels in your programs to direct branching. True BASIC, however, requires the entire program either to have line numbers or to have none at all. If you use *GOTO* or *GOSUB* in True BASIC, you need the line numbers; otherwise, they are not manda-

tory. To my disappointment, True BASIC does not support labels.

Both True BASIC and QuickBASIC support more structured program code. Multiline functions and subroutines (with argument lists) enable you to create more modular code that is easier to maintain and enhance. The new dialects also implement external libraries with the added notion that not all variables are global, which resembles many features in FORTRAN.

What about translation between BASICA and True BASIC or QuickBASIC? As you may expect, because Microsoft wrote both BASICA and QuickBASIC, the two dialects have many built-in functions and statements in common. As a rule of thumb, the aspects of BASICA not available to the QuickBASIC compiler, such as *CHAIN* *MERGE*, are related to the interpreter features. In general, BASICA is upward compatible with QuickBASIC.

Translating programs from BASICA to True BASIC requires more work. True BASIC Inc. sells a BASIC converter to handle many systematic conversion steps. Like the Logitech Translator I discussed in my last column, the BASIC converter does not translate 100 percent of the BASICA code. Later I will present a sample BASICA program and its translated versions in True BASIC and QuickBASIC. To pave the way, I will first discuss several differences between the three dialects.

Similarities and Differences

Concerning data types, BASICA and QuickBASIC support an identical set of strings, integers, and single- and double-precision reals. True BASIC

supports even simpler types: strings and numbers. The distinction between integers and reals is context-sensitive—if a number has no fractional part, it is stored as an integer; otherwise, it is stored as a real. String manipulation follows a different syntax in True BASIC. For example, when you extract and assign substrings in BASICA, you use something such as *MIDS(L\$,FIRST%,LONG%)*. In True BASIC this is written as *L\$[FIRST:(LONG+FIRST-1)]*. The square brackets and the colon inside them specify the first and last characters (as opposed to the number of characters in BASICA). True BASIC uses the ampersand to concatenate strings and names several string functions differently.

True BASIC supports matrix operators, functions, and I/O procedures. While hand-translating BASICA programs that perform matrix operations, you can substitute blocks of code lines with single *MAT* statements.

Loop constructs in BASICA and QuickBASIC are identical. I look forward to seeing more powerful *REPEAT...UNTIL*-like loops in the next version of QuickBASIC. True BASIC offers a variety of loops that include the *FOR...NEXT*, *DO, DO WHILE*, and the double-test *DO WHILE...LOOP WHILE* loops. If you perform manual translation, many BASICA logical loops with *GOTO*s can be rewritten using any of the True BASIC loops, which enhances readability.

Decision-making constructs in QuickBASIC and True BASIC are superior and far more readable than in BASICA. QuickBASIC and True BASIC support multiline *IF...THEN...ELSE...END IF* constructs and even allow for *ELSEIF* clauses. The *ON GOTO* and *ON GOSUB* use labels with QuickBASIC. QuickBASIC does not support the *CASE* statement, whereas True BASIC does. Translating BASICA *IF...THEN...ELSE* statements enables you to use the clearer multiline

version in the other dialects. Gone are the frustrating branchings in the *THEN* or *ELSE* clause that breathe chaos in your program. The *ON GOTO/GOSUB* are easily translated to the superior *SELECT CASE* statement in True BASIC.

How many times have you felt the limitations of BASICA in defining functions? How many times did you have to use a subroutine to simulate multiline functions? QuickBASIC and True BASIC make these painful memories a thing of the past. Now function definitions can extend over numerous lines and freely use loops and decision-making constructs. Whereas True BASIC supports recursive functions, QuickBASIC in its current version does not.

Regarding subroutines, both QuickBASIC and True BASIC support the *GOSUB <label or line number>* and *CALL <subname>* forms. The called subroutines take optional argument lists. Both QuickBASIC and True BASIC provide functions that return the lower and upper bounds of arrays. These functions are vital for writing general-purpose routines that manipulate arrays and matrices.

Both QuickBASIC and True BASIC support external libraries of routines. At the time of writing this column, True BASIC Inc. announced True BASIC, Version 2. One of its highlights is the introduction of modules! I will discuss True BASIC modules in my next column, once I obtain more information on the exact syntax and features. I will also discuss any aspects of similarity between library modules in True BASIC 2.0 and Modula-2. Although BASICA does not support explicit libraries, you may want to consider creating external libraries that contain your favorite and frequently used routines.

BASICA programs that use low-level features (*DEF SEG*, *VARPTR*) translate easily into QuickBASIC. True BASIC does not support such machine-specific statements, however, because they make programs less portable to other machines. For the same reason, the valuable *SHELL()* statement found in both BASICA and QuickBASIC has no similar implementation in True BASIC. The Developer's Toolkit, offered by True BASIC Inc., does provide several low-level access routines for the IBM PC implementation.

High-resolution graphics is another area in which BASICA programs need more effort to be converted into True BASIC. I think that True BASIC's built-in graphics features are superior to those of BASICA. For example, True BASIC supports the *PICTURE* type of routines, special kinds of subroutines that make animation of objects easy.

File I/O is very similar in BASICA and QuickBASIC. True BASIC uses a slightly different syntax and organization, which means additional editing of converted BASICA programs. The *LPRINT* statement in BASICA is not supported by True BASIC. Instead, you must open a buffer for the printer (for example, *OPEN #<Buf_Num> : PRINTER*) and then send all the printer output using "*PRINT #<Buf_Num>*" statements, similar to file output. In translating BASICA programs, you must insert the *OPEN* statement and replace every *LPRINT* with "*PRINT #<Buf_Num> :*".

Error handling in BASICA and QuickBASIC is also similar, both using the *ON ERROR GOTO* and *RESUME* statements. QuickBASIC uses labels to direct the program flow to error handling sections. True BASIC uses a different and more structured mechanism—a *WHEN ERROR IN...USE...END WHEN* construct. The code section suspected of generating errors is located in the *WHEN* clause and the exception handling code in the *USE* clause. By enclosing the suspected code portion in the *WHEN* clause, the extent of error trapping is most noticeable.

Interdialect Translation

Listing One, page 88, presents a BASICA utility program. The user types in the number and names of data files containing text. This is followed by several search strings, with the options of simply locating or replacing strings with others. The entire set of strings is used in text manipulation with each file. The program prints the text lines found or altered and writes back the text files to update them. The replace mechanism is fully automatic and has no query option.

Using the BASIC converter from True BASIC Inc., I converted the BASICA program. Listing Two, page 89, shows the True BASIC version after manual editing that was needed to

make the program function. The converter inserts several lines at the beginning of the original BASICA listing. These include the use of the *deflib.tru* library, which contains True BASIC functions that clone certain BASICA functions, listed in lines 25 and 26. Three author functions are defined within the converted program. The *Eof()* function is used by the utility. The *OPTION BASE 0* is also used and does not conflict with my program. Notice the following changes made either by the converter or by hand coding:

1. The original *DEFINT* declaration is rendered passive by converting it into a comment.
2. Each dot character used in the name of a BASICA variable is replaced with two underscore characters.
3. BASICA program lines containing multiple statements are broken down into single statements per line in True BASIC.
4. I inserted line 1945 to open a buffer for printer output. All BASICA *LPRINT* statements were flagged by the converter. I changed each *LPRINT* into *print #9 :*.
5. The BASICA *SPC()* function is replaced by *REPEAT\$(" ", <number>)* to produce the same effect. Using *TAB()* is another alternative.
6. The converter moved the BASICA *END* statement from line 3000 to the very end and replaced it with a *stop*. In True BASIC, there must be one and only one *end* statement at the end of the program. If I manually replace the *stop* with *end*, all the subsequent subroutines become external (the current *end* location makes them internal). The difference between internal and external subroutines is in the scope of variables. Internal routines access all the variables of the main program, but external routines do not. Library files containing nothing but external routines must begin with the keyword *EXTERNAL*.
7. I edited the *OPEN* statements for file I/O to add the *create old* clause, which indicates that the file must already exist.
8. I added the *erase #1* in line 9015. This erases the contents of the file before I write back to it. Unlike BASICA, True BASIC does not allow you to overwrite existing text, so you must erase a file before updating its

AVAILABLE NOW!

Dr. Dobb's Bound Volume 11

ALL OF 1986!

Bound Volume 11: 1986 The promise of power. With the introduction of the first true 32-bit microprocessors, desktop computers began to rival minis and mainframes in power. DDJ covered the changes with special issues on the 68000, parallel processing, artificial intelligence, the 80386, and multitasking. We supported the new chips with assemblers, translators and other cross-development tools. Other features included a special graphics issue, reviews of Dan Briklin's DEMO program and Jef Raskin's SwyftCard, and our sixth annual Forth issue. We introduced a new structured languages column, led by Michael Ham and Namir Shammas, while Ray Duncan and Allen Holub continued to provide their own valuable columns.

Item #020F **\$35.75**

Bound Volume 1: 1976 The working notes of a technological revolution. Before there was Apple, DDJ put a programming language on the first microcomputers, and became a chronicler and instrument of the microcomputer revolution.

Item #013 **\$30.75**

Bound Volume 2: 1977 Running light without overbyte. By year two the formula was clear: serious technical questions handled with a minimum of reverence; much source code; and a commitment to tight coding.

Item #014 **\$30.75**

Bound Volume 3: 1978 The roots of Silicon Valley growth. The S-100 bus was hashed out in DDJ's pages. Steve Wozniak and others published in DDJ code that would help build an industry.

Item #015 **\$30.75**

Bound Volume 4: 1979 In the midst of the gold rush. Three years before IBM moved in, the neighborhood was less civilized. DDJ published a gold mine of tips, tricks, and algorithms.


Item #016 **\$30.75**

Bound Volume 5: 1980 C and CP/M. 1980 saw an all-CP/M issue, including Gary Kildall's history of CP/M, and Ron Cain's original Small-C compiler.

Item #017 **\$30.75**

Bound Volume 6: 1981 The first of Forth. This was the year DDJ launched its first Forth issue and Dr. Dobb's Clinic. Plus: PCNET, the Conference Tree, and 6809 Tiny BASIC.

Item #018 **\$30.75**



Bound Volume 7: 1982 Legitimacy. DDJ Observed the IBM phenomenon, reviewed MS-DOS and CP/M-86, and looked forward to fifth-generation computers.

Item #019 **\$35.75**

Bound Volume 8: 1983 Power tools. Professional software development on a PC was getting easier; DDJ helped, with Small-C, the RED editor, and an Ada subset.

Item #020 **\$35.75**

Bound Volume 9: 1984 Shaping things to come. In 1984 DDJ examined new programming environments: Prolog, expert systems, Modula-2, and a \$49.95 Pascal. Plus Allen Holub's GREP, Unix internals, and two encryption systems.

Item #020B **\$35.75**

Bound Volume 10: 1985 The year of living dangerously. In 1985, iconoclastic DDJ beat Apple to the goal of adding more memory, a SCSI port, and a hard disk to the Macintosh. Also: powerful software tools in C, Modula-2, Forth, Pascal, assembly language, and prolog.

Item #020D **\$35.75**

SPECIAL OFFER!

Receive 11 years worth of useful code and fascinating history, the complete Dr. Dobb's library of 11 volumes for only \$299! That's a savings of over \$60!

Item #020A **\$299**

TO ORDER: Return this order form with your payment to: M&T Books, 501 Galveston Dr., Redwood City, CA 94063. Or, call **TOLL-FREE 800-533-4372** Mon-Fri 8AM-5PM (In CA call **800-356-2002**)

Name

Address

City State Zip

☐ Check enclosed. Make payable to M&T Publishing.

Charge my ☐ VISA ☐ M/C ☐ Amer. Exp.

Card No. Exp.

Signature

| Item # | Description | Price |
|--------|-------------|-------|
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |

Subtotal

CA residents add sales tax %

Add \$2.25 per item for shipping

TOTAL

3125A

Version 3.0

New Features

Windows, Data Entry, Help Management, Menus, Text Editing, plus ...

SOURCE CODE

Vitamin C

It's good for your system!

The Vitamin C Difference

With **Vitamin C**, your applications come alive with windows that explode into view! Data entry windows and menus become a snap, and context sensitive pop-up help messages are nearly automatic.

With **VCScreen**, you'll save time by interactively painting windows and forms so what you see is what you get! Then, one button generates C source code ready to plug into your program and link with Vitamin C.

Easy enough for the beginner. Versatile enough for the professional. Vitamin C's **open-ended design** is full of "hooks" so you can intercept and "plug-in" special handlers to customize or add features to most routines.

Of course, Vitamin C **includes all source code FREE**, with no hidden charges. *It always has.* That means you'll have everything you need to adapt to special needs without spending hundreds of dollars more.

Windows

Create as many windows as you like with one easy function. Vitamin C automatically takes care of complicated tasks like saving and restoring the area under a window.

Options include titles, borders, colors, pop-up, pull-down, zoom-in, 4-way scrolling, scroll bars, sizes up to 32k, text file display & editing, cursor display, and more.

Unique built-in feature lets users move and resize windows during run-time via a definable key.

Access the current window by default or a specific window any time, even if it's hidden or invisible. Save and load windows on disk for more versatility!

Data Entry

Flexible dBase-like data entry and display routines feature protected, invisible, required, and scrolling fields. Picture clause formatting, full color/attribute control, selection sets, single field and full screen input, and unlimited data validation via standard and user definable routines. That means you aren't locked into one way of doing things.

Vitamin C even provides true right-to-left input of numeric fields with dynamic display of separators & currency symbols.

High Level Functions

Use our integrated help management, multi-level menus, and text file routines, or build your own handlers using Vitamin C's basic windowing and data entry routines.

Standard help handler provides context sensitive pop-up help messages any time the program awaits key strokes. The help text file is stored on disk and indexed for quick access. So easy to use that a single function initializes & services requests by opening a window, locating, formatting, displaying, and paging through the message.

Multi-level "Macintosh" & "Lotus" style menus make user interfaces and front ends a snap. Menus can call other menus, functions, even data entry screens, quickly and easily.

Text editor windows can be opened for pop-up note pads, memofields, or general purpose editing. Features include insert, delete, word wrap, and paragraph formatting.

VCScreen

Screen Painter/Code Generator

Just as Vitamin C's reusable functions speed your programming, VCScreen makes it even *faster and easier* by automatically generating C source code for your data entry screens!

With VCScreen's interactive screen editor, you actually draw your forms. You can define input, output and constant fields, headings, boxes, lines and even a window for the form to run in.

What you see is what you get. If you don't like the position of an object, just "pick it up" with the cursor and move it! Changing colors, attributes, copying, and deleting is just as easy.

VCScreen generates readable C source code. It declares variables with names you provide and can even generate structures.

With VCScreen choosing the right functions, parameters and sequences, and Vitamin C supplying the functions to choose from, you can stop worrying about semi-colons, matching braces, and calling conventions and concentrate on creating your application!

30 Day Money Back Guarantee

Better than a brochure. More than a demo disk. If you're not satisfied, simply return the package within 30 days and receive a full refund of the purchase price.

Vitamin C \$225.00

Includes ready to use libraries, tutorial, reference manual, demo, sample, and example programs, and quick reference card. For IBM PC and compatibles. Specify Microsoft, Lattice, Computer Innovations, Aztec, Mark Williams, Wizard, DeSmet, or Datalight C compiler AND compiler version number when ordering.

Vitamin C Source ... FREE*

*Free with purchase of Vitamin C

VCScreen \$99.95

Requires Vitamin C and IBM PC/XT/AT or true compatible.

ALL ORDERS:

SHIPPING: \$3 ground, \$6 2-day air, \$20 overnight, \$30 overseas. Visa and Master Card accepted. All funds must be U.S. dollars drawn on a U.S. Bank. Texas residents add 7% sales tax.

For Orders or More Information, Call ...

(214) 245-6090

creative
PROGRAMMING

Creative Programming Consultants, Inc.
Box 112097 Carrollton, Texas 75011

STRUCTURED PROGRAMMING

(continued from page 121)

contents.

9. Each assignment statement in True BASIC begins with the keyword *let*. It is mandatory in Version 1, but the new Version 2 enables you to issue a directive and make the *let* optional.

Listing Three, page 91, shows a True BASIC version that differs from that in Listing Two in the following ways:

1. No line numbers are used.
2. Some of the tests in the *IF... THEN* constructs have been reversed to make use of the multiline *THEN* and *ELSE* clauses and to bypass the need for line numbers.
3. Subroutine *CALLS* are used instead of *GOSUB*. I have deliberately used argument lists to give a sense of structured code. I could have made the subroutines parameterless and their code access global variables.
4. The *BASICA NOT EOF()* test used in detecting the end of file is replaced with the True BASIC *MORE #1* function, which performs the same task.

tion, which performs the same task.

Listing Four, page 92, shows the first QuickBASIC version of the BASICA utility. I wrote it to demonstrate the following QuickBASIC features:

1. No line numbers.
2. The *GOSUB* statements are followed by alphanumeric labels. The corresponding labels are located at the start of each subroutine. This QuickBASIC looks slightly more modular than its parent BASICA versions.

Listing Five, page 94, shows the second, more structured QuickBASIC version. The *GOSUB* statements are replaced by subroutine *CALLS*. The argument lists of the subroutines are identical to those of True BASIC in Listing Three. Listings Three and Five show strong similarities between QuickBASIC and True BASIC with respect to program segmentation. This gives you a feeling that both QuickBASIC and True BASIC really promote more structured code. Compared to Pascal, these BASIC dialects retain simple data types with the declaration of variables limited to arrays. Compared to FORTRAN, they represent a true challenge because they offer many of FORTRAN IV and FORTRAN-77's features.

I have focused on the one-way translation of programs written in BASICA to QuickBASIC and True BASIC. In a future column, I will look at the two-way translation between QuickBASIC and True BASIC programs. I also plan to look at Better BASIC, another "new wave" BASIC dialect, which I have not discussed this time because of space limitations.

Availability

All the source code for articles in this issue (except C Chest) is available on a single disk. To order, send \$14.95 to Dr. Dobb's Journal, 501 Galveston Dr., Redwood City, CA 94063 or call (415) 366-3600 ext. 216. Please specify the issue number and format (MS-DOS, Macintosh, Kapro).

DDJ

(Listings begin on page 88.)

Vote for your favorite feature/article.
Circle Reader Service No. 6.

PVCS

The Most Powerful & Flexible Source Code Revision & Version Control System.

The POLYTRON Version Control System (PVCS) allows programmers, project managers, librarians and system administrators to effectively control the proliferation of revisions and versions of source code in software systems and products. PVCS is a superb tool for programmers and programming teams. If you allow simultaneous changes to a module, PVCS can merge the changes into a single new revision. If changes conflict, the user is notified. Powerful capabilities include: Storage and retrieval of multiple revisions of text; Maintenance of a complete history of revisions to act as an "audit trail" to monitor the evolution of a software system; Maintenance of separate lines of development or "branching"; Levels of security to assure system integrity; An intelligent difference detector to minimize the amount of disk space required to store a new version. Requires DOS 2.0 or higher. Compatible with the IBM PC, XT, AT and other MS-DOS PCs. **Maintains source code written in ANY language.**

Only PVCS meets the needs of Independent Programmers and Corporations. Once you standardize on PVCS, the "Logfiles" used to track and monitor changes are interchangeable between any PVCS product. You will receive full credit for your initial purchase if you upgrade to a higher-priced PVCS.

Personal PVCS — Offers most of the power and flexibility of the Corporate PVCS, but excludes the features necessary for multiple-programmer projects.

\$149

Corporate PVCS — Offers additional features to maintain source code of very large and complex projects that may involve multiple programmers. Includes "Branching" to effectively maintain code when programs evolve on multiple paths (e.g., new versions for different systems, or a new program based on an existing program). Single User License Price.

\$395

Network PVCS — Extends Corporate PVCS for use on Networks. File locking and security levels can be tailored for each project. 5-Station License \$1,000. Call (503) 645-1150 for pricing on Licenses for more than 5 Stations.

\$1000

TO ORDER: VISA/MC 1-800-547-4000. Dept. No. 355.
Oregon and outside US call (503) 684-3000. Send Checks, P.O.s to: POLYTRON Corporation, 1815 NW 169th Place, Suite 2110, Dept. 355 Beaverton, OR 97006.

POLYTRON
High Quality Software Since 1982

Circle no. 283 on reader service card.

THE PROGRAMMER'S SHOP

Offers a 31 Day Money Back Guarantee on any product in this ad. Call Today.

COBOL PROGRAMMING PRODUCTIVITY!

screenplay™
SCREEN MANAGEMENT SYSTEM

SUBSTANTIALLY REDUCE APPLICATION DEVELOPMENT TIME!

Save valuable time by avoiding the tedious, time consuming process of writing screen handling source code. *screenplay's* easy-to-use panel painter allows you to create I/O panels, pop-up help windows or menu panels which you use in your program. **FLEXIBILITY IN PANEL PAINTING; FLEXIBILITY AT RUNTIME!**

True screen handling flexibility is yours with *screenplay*, because you can override default panel settings to design practically any type of panel imaginable! *screenplay* continues to provide the flexibility you need during the operation of your program by allowing you to change just about any panel characteristic at runtime.

PROTOTYPE PANELS BEFORE YOU WRITE CODE!

With *screenplay*, you can prototype your draft screens before you write a single line of COBOL source code. These can then be reviewed with your boss or your customer for final approval, before you start writing source code.

MORE THAN ONE LINKING OPTION!

In addition, linking *screenplay's* runtime unit is your choice! You can link *screenplay* by interrupt or directly to your application. And if your compiler doesn't allow a direct link, you can take advantage of a dynamic load option for linking *screenplay* to your application.

FULL CONTROL OVER KEY ASSIGNMENT!

You can assign practically any keyboard key to serve as a specific cursor function and define exactly which keys will return control to your application. *screenplay* gives you the power to entirely reconfigure the keyboard for your program.

POWERFUL, ONE-STEP PANEL PAINTING

screenplay's panel painting process is a "one-step" approach. There's no need to go through a separate process to establish fields on your I/O panel. What's more, you can use any ASCII character in your *screenplay* panels. You also have full control over character attributes such as foreground and background color, intensity and blinking.

EASY PANEL FILE MANAGEMENT!

Panels are stored in an ASCII file which is compressed to save memory and disk space. *screenplay's* Panel Management Facility allows you to easily copy panels across and within files, rename panels, delete panels, test and print panel details. You can even print an image of the panel for your documentation!

NO ROYALTIES / NOT COPY PROTECTED!

screenplay's panel control runtime unit, better known as The Panel Control Facility may be linked to your program without paying a dime in royalties. In addition, *screenplay* isn't copy protected to make it even easier-to-use. The Panel Control Facility allows you to control almost every panel characteristic by using parameters.

SUPPORTS MANY COBOL COMPILERS!

Supports IBM COBOL, Microsoft COBOL, Realia COBOL, Ryan-McFarland COBOL and Ryan-McFarland COBOL 8X; List Price \$175.00, OUR PRICE \$155.00

flexus

PROFESSIONAL TOOLS
FOR PROFESSIONAL
PROGRAMMERS

HELP

is at hand

HELP/Control™ — an on-line help system for the IBM-PC. **HELP/Control** includes **HELP/Runtime**, **HELP/Popup** and our help screen compiler.

With **HELP/Runtime**, a few simple subroutine calls add context sensitive on-line help to your application. **HELP/Runtime** includes tested interfaces for C (Microsoft and Lattice), Pascal (Microsoft and Turbo), IBM BASIC (Interpreter and Compiler), Microsoft FORTRAN, COBOL (IBM and Realia) and assembler.

Use our concise screen definition language to build your help files. You define the bold captions on your help screens and specify the links to other screens. If you have existing documentation files, it's easy to mark them up to get on-line quickly. You can put an entire user or reference manual on-line, completely accessible to the user at all times.

HELP/Popup provides memory resident access to your custom help screens.

The complete package (software, on-line manual, printed manual, and demo programs) costs \$125.00 and includes a royalty-free license to add **HELP/Runtime** to your applications and a license to make 25 copies of **HELP/Popup**.

Circle no. 303 on reader service card.

LIST: \$125
OURS: \$109



MDS, Inc. 207/772-5436

Double Your C Language Programming Productivity

Instant-C is an **incremental compiler** for C that makes every aspect of C programming as fast as possible. Load your existing C source code into *Instant-C*. Whenever you change your code with *Instant-C's* built-in full-screen editor, only the changed portions of your programs are recompiled. The fully automatic compilation process includes linking of your multiple modules, and therefore **takes no link time**. *Instant-C* compiles more than twice as fast as normal compilers. More importantly, compile time is proportional to how much code you change, not to the size of your entire program. With *Instant-C*, you will be running your program within a few seconds after editing a change.

Instant-C's over 350 precise diagnostic messages help you understand immediately how to fix the problem. *Instant-C* shows any errors on the editor screen, with the cursor placed exactly at the trouble spot.

Instant-C runs your program at compiled speeds with **full run-time checking** of pointer references and array indexes. Run-time checking catches problems as they occur, when they are easiest to fix and understand. This checking **reduces** the number of times you need to modify and test your program.

Instant-C has the **best testing and debugging** capabilities available. You have full access to the C language and to your program. At any time you can examine or modify variables (including locals), evaluate expressions or macros, and call functions interactively. You can examine and change your code, then resume execution. Use any number of conditional breakpoints. *Instant-C's* **visual debugging** shows your source code, highlighting the line being executed. *Instant-C* supports multiple screens, virtual screens, and non-standard graphics devices. *Instant-C's* **data monitor** stops execution when specified variables or memory areas are changed.

Instant-C is compatible with Lattice 2.x, 3.x and Microsoft 3.0, 4.0. Get *Instant-C's* superb debugging, run-time checking, and incremental compilation to **double your C programming productivity**.

Rational P.O. Box 480
Natick, MA 01760
Systems, Inc. (617) 653-6194

Quelo® 68000 Software Development Tools

Quelo Cross Assembler Packages are **Motorola compatible**. Each package includes a macro assembler, linker/locator, object librarian, utilities for producing **ROMable code**, extensive indexed typeset manuals and produces **S-records**, Intel hex, **extended TEK hex**, **UNIX COFF** and symbol cross references. **Portable source** written in "C" is available. It has been ported to a variety of mainframes and minis including **VAX, Sun, Apollo, Masscomp, and Charles River**. Native versions available for Amiga and Atari ST.

68020 Cross Assembler Package

Supports 68000, 68010, 68020, 68881 and 68851.
For CP/M-68K and MS/PC-DOS, \$750

68000/68010 Cross Assembler Package

For CP/M-80, -86, -68K and MS/PC-DOS, \$539

68000/68010 Simulator

For MS/PC-DOS by Big Bang Software, Inc.

SIM68K is a cost-effective software simulator for debugging 68000/68010 code on an IBM-PC or compatible, \$285.

Circle no. 302 on reader service card.

Trademarks: CP/M, Digital Research; MS, Microsoft Corporation; Quelo, Quelo, Inc.

HOURS


8:30 A.M. - 8:00 P.M. E.S.T.

800-421-8006

THE PROGRAMMER'S SHOP™

5-D Pond Park Road, Hingham, MA 02043
Mass.: 800-442-8070 or 617-826-7531

Object-Oriented Programming



The theme for my next few columns will be object-oriented programming in AI. This is a rather vast but very hot topic, and I'll approach it from a few different vantage points. As mentioned in the previous column, object-oriented languages represent a programming paradigm, which is a much more significant development than just another new programming language or programming technique. Most programming languages to date have been for programming in a single paradigm, that of procedural programming. Because all programmers already know this paradigm, I will concentrate on the newer ones.

As I see it, object-oriented programming is not a direction that is entirely new and without precedent in computer science; rather, it takes various developments in programming languages to their next logical step, for reasons of clarity, modularity, and programming efficiency. In one sense, you can think of object-oriented programming as the programming paradigm that takes structured programming to its natural logical conclusion. In structured programming, variables can be local to a particular procedure and these procedures typically pass arguments such as strings and numbers between them. With object-oriented systems all this is taken much further. Variables are no longer local just to procedures. The main building blocks are now objects—protected areas of sys-

tem and received by objects. In this respect, objects resemble smaller computers within the host computer, each with their own data and code areas.

Most object-oriented systems have at least two different types of objects: classes and instances. Classes may have a logical relation between one another such that one might be the subclass or superclass of another. Generally speaking, the superclass is the more abstract class and the subclass is the more specific. So, for example, if you created the class *Furniture*, then you could create the class *Chair* as the subclass of *Furniture* and *Desk-Chair* as a subclass of *Chair*. In this example, *Furniture* would be the superclass of *Chair*, which is in turn the superclass of *Desk-Chair*.

Object-oriented systems have at least three obvious advantages. One very nice one is that, once you have written the code for a class, you can have as many instances of that class present in the system at the same time as memory will allow. A class is simply a template on which each instance is modeled and provided with its own area of memory that cannot be accessed by any other object except by using the object's own local methods. So, for example, this means that, in an object-oriented system, you can have as many graphics pens, windows, editors, interpreters, and so on as you like copresent without any fear that they will interfere with one another. The second advantage is that, through the mechanism of inheritance, subclasses automatically share all the variables and methods

of their superclasses. This means that you can write greater and greater specializations of functions just by adding the part that is unique—the rest is inherited automatically. The third immediate advantage is that you can provide a uniform interface over the widest possible range of object types because you can use the same name for methods of different objects that have to be implemented differently, and this action can remain invisible to the user. So, for example, you might create different classes for a variety of different geometric polyhedra. Then, for each separate class, you would define the methods volume and surface area. The actual formulas and their implementations would vary, but the calling names would all be the same. Then you could say *Tetrahedron-1* volume or *Cube-3* volume, and in each case methods would be invoked that returned the value of the object's volume.

Some people say that the key advantage of object-oriented programming is the ability to reuse code for many different programs. But in itself this is not significantly different from library functions. The real difference is an improved ability to handle complexity in a transparent manner. An advantage of object-oriented programming that is not necessarily immediately obvious—but which experienced programmers who have worked with these systems will nearly always testify to—is that object-oriented languages give you more leverage in working on very large programs. This does not come for free, though, and it's not guaranteed. Factoring a large program into the right parts is a large part of the battle. It is also necessary to learn the right techniques for managing the code and making life easy for the members of a programming team. Object-oriented systems are usually diffuse,

by Ernest R. Tello

tem memory—which can have both local variables and local procedures. Moreover, the building blocks do not communicate with one another just by passing arguments. The procedures themselves, usually called methods, which are local to objects, are actually the messages that are

NEW COMMON LISP Development System for Your PC or AT

Introducing TransLISP PLUS™, The Consultant's LISP Over 400 Primitives, a C Interface, and Optional Runtime System

People call you because you're an expert. Your customers want to keep up with what's going on. They want software that is more intelligent and responsive, or software that does something that just wasn't possible before. So they call you.

Now you can write and deliver a whole new category of software with TransLISP PLUS, a practical, efficient LISP system. You can also add Artificial Intelligence to your software. We include several features, like a C Interface and Optional Runtime System, so you can control the performance and security of your programs. And your users only need to have a PC (can even be non-compatible) with 320K and 1 floppy drive. Now, what could you write for a \$700 PC? . . . or a \$7000 PC? . . .

Add AI Technologies to Your Software

Most of the programs you write are accessed by a user who doesn't have your expertise. Use intelligent interfaces to make your programs more responsive to the end user.

You can even use the C Interface included with TransLISP PLUS to customize LISP, or combine C functions with LISP programs.

Take advantage of AI technologies to make your programs smarter and more flexible.

Extensive Development Environment Over 400 Primitives

TransLISP PLUS provides you with over 400 primitives for development, including extras for hardware support and operating system access. Their spectrum ranges from control constructs, macros, and special forms, to multi-dimensional arrays, reader support for binary, octal, and hex constants, improved list processing, and system interrupts.

DOS commands and applications can be invoked from within TransLISP PLUS, as can the fast editor. Of course, you can use your own editor if you like.

A variety of debugging tools are provided. The trace facility tracks the evaluation of any built-in or user-defined function or macro.

Traceback, Break, Cross Reference, and Pretty Printer are also provided to help you spot problems.

The ONLY Full Featured Common Lisp with a C Language Interface

The best of both worlds. The interface to Microsoft C gives you a powerful extension to TransLISP PLUS — now you can write code in LISP and C. And you don't need an AT, it will run on your PC!

The C Interface makes it practical for you to write a C program and add it as a new function to TransLISP PLUS. Your function can:

- extend and/or change the LISP syntax
- be an entire system of programs

Create your own BUILT-IN primitives which are directly tied to the system and called at full speed by the interpreter. Extend the functionality of your program by including features of your own like macros, functions, and special forms.

Code from C libraries produced by other vendors can be integrated into your program to perform tasks not normally part of LISP.

Use PLUS for Your Applications. No Royalties.

Once you own TransLISP PLUS, you may want to use it to distribute applications. No problem.

The Optional TransLISP PLUS Runtime supplies you with a special interpreter. You can distribute an executable version of your program without distributing source code.

The Runtime is available for \$150 and TransLISP PLUS is required.

Don't Know LISP?

Get a solid understanding of LISP with the comprehensive, easy-to-understand tutorial. Each section walks you through a new concept and reinforces it with examples — both text and online.

Over 30 demo programs supplement the tutorial. Use them for an in-depth introduction to LISP programming techniques. Commented source is included so you can see how and why the program operates.

The demos cover a wide variety of applications including: Select a word processor, Read dBASE SDF files, Job Counselor, and many, many more.

The Fundamentals

If you are interested in learning LISP but don't need all the extras in TransLISP PLUS, order TransLISP for \$95. It's a full, easy-to-use introduction to LISP that includes the tutorial and demo programs described above, and over 300 primitives.

It is a solid subset of COMMON LISP; and you can write programs of up to 12000 lines.

COMMON LISP Standard

Programs written carefully with TransLISP PLUS will be completely "portable" to any other COMMON LISP system on a micro, mini, or mainframe computer. This allows you, for example, to write a program with TransLISP PLUS on your PC at home, and compile and run it on the VAX at work.

System Requirements

TransLISP PLUS requires at least 320K RAM and a 360K disk drive.

TransLISP requires 256K RAM and a 360K disk drive.

| | |
|----------------------------------|-------|
| TransLISP PLUS | \$195 |
| TransLISP | \$ 95 |
| Upgrade TransLISP to PLUS . . . | \$158 |
| TransLISP PLUS Runtime | \$150 |

TO ORDER OR FOR DETAILS CALL



800-821-2492



**Solution
Systems™**

Use TransLISP PLUS to program with and deliver to lots of machines . . . Use your existing C libraries . . . Distribute your applications

MONEY BACK GUARANTEE

Try TransLISP PLUS (\$195) for 30 days — if not satisfied get a full refund.

with parts of applications being dispersed among a large number of classes and subclasses. To program efficiently with such a system, it is essential to have the proper tools and an effective method for keeping the application well focused and well organized.

It is important to point out that object-oriented programming cannot be regarded as an easy thing to pick up rapidly, as it is a totally different paradigm from the one to which most programmers are accustomed. As programming approaches go, it is a knowledge-intensive one. In other words, the readily available modular code is only useful providing that programmers know what they have available to them and how it may be best used. Many programmers resist learning new languages, not to speak of new programming paradigms, so it is important to spell out again in clear-cut, pragmatic terms just what the real advantages are to programming with objects. As I see it, there are four main ones:

1. standard calling conventions for a broad range of operations that exhibit differences in behavior, as do variations on a theme
2. a means of managing very large programming projects by breaking up large problems into smaller, independently functioning, highly visible parts
3. a truly modular programming environment in which redundancies in coding are kept to an absolute minimum
4. the ability to spawn multiple instances of a given function or object from the same code without the codes for the instances interfering with one another

Object-Oriented LISP: An Overview

Although Smalltalk was the first true general-purpose object-oriented language, and implementations such as Digitalk's Smalltalk/V are specifically aimed at AI applications, the main uses of this programming paradigm so far in AI have been with object-oriented LISP. The reason for this is probably because people in the AI

field are most familiar with LISP.

The most interesting things that have occurred with object-oriented LISP are some of the clear innovations it has made in object-oriented programming generally. Not only did LISP have little difficulty absorbing the object-oriented paradigm but also it introduced some important innovations to this programming approach as it did so. I would like to discuss three innovations in particular—mixins, method combination, and multimethods. The mixin feature is the LISP version of multiple inheritance, which consists of the ability to create a new class that inherits from more than just a single superclass. In effect, it means the ability to build an object hierarchy that can be a network or tangled hierarchy rather than just a simple tree. Although multiple inheritance is theoretically present in the latest release of Smalltalk-80, it was an afterthought in this language and has nothing close to approaching the readily usable and trouble-free operation of mixins in object-oriented LISP.

Method combination is a bit more difficult to explain than mixins but is no less important. The first appearance of user-defined method combination in LISP was with Symbolics' Flavors system. This system does not just copy the approach to method combination used in Smalltalk but introduces a new approach. The Flavors implementation lays stress on the order in which components are combined to produce a flavor. This is particularly true with methods, the procedures that are local to flavors. The heart of the Flavors system is the way the methods of various components are combined. The problem is this: if you define a flavor that inherits from several other flavors or classes, each of which have their own specialized versions of the same message, then how will the method for this new flavor be constructed? The Flavors system offers a variety of ways for combining methods and even provides for user-defined method combinations. It is designed so that, if you want to, you can define entirely new ways of combining methods.

The default for method combination in Flavors is to ignore all but the latest implementation of the method,

meaning the one defined in the most specific of the flavors from which the new flavor will inherit. If you decide to define an entirely new method for the new flavor, then all the others will naturally be overridden. The general format for the more complex types of method combination in Flavors is for one flavor to be selected to provide the primary method and for any other flavors to provide what are called daemon methods. The primary method has control of handling the main function associated with the message, whereas the daemon methods are responsible for subsidiary tasks.

Flavors has two kinds of daemon methods—*before* and *after*. The terminology is derived from the order in which the method functions are called. The basic way that combined methods work is that they first call all the before methods, then the primary method, and finally all the after methods. Each of these component methods is passed the same arguments in turn as were passed to the combined method. Only the values returned by the primary method will be returned by the combined method, however. All values returned by the daemon methods are ignored. If there is more than one before method, then the before methods are called in the same order as that in which the flavors are combined, whereas after methods are called in reverse order.

What is the point of these method combinations? They can have a variety of different uses, but one of the most obvious is to provide an additional type of modularity that captures the whole spirit of the object-oriented approach. With method combination, if you can't find all you want for a flavor method in any of the flavors from which it will be inheriting, yet part of what you want is available, then method combination can often save you from having to rewrite the entire function from scratch. What you can do is select a method to inherit that can serve as your primary method. Then you just write the before and after methods that can be added to this primary method to produce the desired result. Naturally this won't be possible in all cases. It will work only in situations in which the function desired

can be combined from several separate functions. You will find that this applies to a surprisingly large number of cases, however.

Multimethods, a capability first made available in CommonLoops, could well be the most important contribution object-oriented LISP has made so far to object-oriented programming. Multimethods are functions that can be considered as messages to any number of types of objects. Prior to the development of multimethods, object-oriented LISP made a distinction between the object to which a message was sent and the arguments to the message procedure. So, in the expression:

(send Rectangle draw-at 10 40)

the class *Rectangle* is solely responsible for recognizing the message and is distinguished from the numbers 10 and 40, which are arguments to the *draw-at* message. This is somewhat artificial, for in Smalltalk numbers are treated as instances of the class *Number* and arithmetical operations such as multiplication are considered as messages to the numbers to multiply themselves. Multimethods take this even further by considering the class to which a message is sent as just another one of the arguments. In principle any number of arguments can be passed to a multimethod, and each of the arguments is an instance of its own class. So a multimethod is really a message to an indefinite number of objects, with the method combination required to complete this message determined by the actual arguments used.

One "problem" with object-oriented LISP is that it is just too popular for its own good. It has become a favorite tool not only for programming AI applications but also for systems programming and developing user interfaces. The result of this diversity is a somewhat conflicting set of requirements for users of different types. Systems programmers and those developing user interfaces and advanced graphics applications are usually interested in high-performance, bug-free code. AI researchers are willing to trade some performance for greater flexibility and generality.

What are some of the primary con-

Tom Rettig's Library™

Prewritten Solutions to Programming Problems

Clipper Edition

Advanced Extended Library

- Convenient .LIB library file to link
- Separate object files so only the code actually used is added to your program
- Optimized for speed and code size
- Requires Clipper, Winter '85 or later

dBASE III PLUS Edition

Advanced Programmer's Library


- Interface to C/assembler is fully compatible with Clipper's Extend system
- Functions are CALL procedures
- Requires dBASE III PLUS, any version, and 128K of additional memory

Each edition comes complete with...

- Entire source code, nothing withheld. Cleanly written, liberally commented, easy to modify, helpful for learning.
- Support by phone and electronic mail
- No royalties or copy protection
- Documentation inserts for dBASE or Clipper manual. Accurate, complete, easy to use, page-per-command.
- Handy plastic reference card
- Full money-back guarantee

Over 175 functions; 55% written in C, 35% in Assembler, 10% in dBASE

\$99.95 per edition at dBASE/Clipper dealers or direct



9300 Wilshire Boulevard, Suite 470
Beverly Hills, CA 90212-3237, U.S.A.
(213) 272-3784 ■ Telex: 4996426 RETTIG
Source: BCR480 ■ CompuServe: 75066,352

dBASE and dBASE III PLUS are Ashton-Tate trademarks, Clipper is a Nantucket trademark

Call or write for free product information

Circle no. 175 on reader service card.

HELP

123
STYLE HELP

is at hand

HELP/Control™ - an on-line help subsystem for the IBM-PC. Increases the value of your software. Save development time and money.

HELP/Runtime. A few simple subroutine calls add context sensitive on-line help to your application. **HELP/Runtime** includes tested interfaces for Microsoft C, Lattice C, Turbo Pascal, IBM BASIC (Interpreter and Compiler), Microsoft FORTRAN, IBM COBOL and assembler. It is distributed with demonstration programs in each language.

HELP/Popup. Add a powerful help system to existing applications, even in dBase or 123, without reprogramming, even without a programmer. It may be memory resident, or, installed with an application, it terminates when the application exits, releasing its memory.

HELP/Generation. Use your favorite editor and our concise screen definition language to build your help files. Compile them into a help system usable by either **HELP/Runtime** or **HELP/Popup**. The package includes sources for sample help files illustrating such features as full-sized or windowed screens.

HELP/Convenience. The screens include highlighted captions. The user selects a caption with the cursor control keys and advances to a new screen, just as with 123.

HELP/Documentation. A detailed manual, both on-line and printed, for the documentation writer and programmer includes instructions which may be incorporated into the user manual.

HELP/Environment. PC-DOS 2.0 or greater is required. **HELP/Runtime** requires approximately 9K for code and buffers for full size help screens.

HELP/Pricing. The complete package (software, both manuals, and demo programs) costs \$125.00 and includes a royalty-free license to add **HELP/Runtime** to your applications and to make 25 copies of **HELP/Popup**. A demonstration diskette, including the on-line manual, costs \$15.00. A free update to Release 1.1 is available to registered owners. To order, or for more information (including dealer, multiple-copy and site-license pricing) call MDS at 207/772-5436. We accept MasterCard and VISA.




MDS, INC., P.O. BOX 1237, PORTLAND, MAINE 04104

Circle no. 285 on reader service card.

Professional Programming Products

for Microsoft C, PASCAL, FORTRAN, and Assembly Language



FREE!

PC-WRITE™ text editor



**PROGRAMMERS AND SOFTWARE DEVELOPERS - LOOK AT THESE PRODUCTS!
NO ROYALTIES REQUIRED**

ASMLIB

The Programmer's Library

- A linkable library with over 210 assembly language sub-routines which are directly CALLable from Microsoft™ Assembler, C, PASCAL, and FORTRAN.
- Virtual disk file handling.
- Text WINDOWing allows up to 64 overlapping windows.
- Int. driven asynch. support.
- Graphics on EGA, herc. and CGA.
- Floating point math and trig outlines with 8087 support.
- Installable keyboard activated programs are easily written with ASMLIB's special functions.
- Plus much, much more.
- Supplied with complete source code.

Only \$149.00 Complete



FPLIB

FPLIB™-IEEE Floating Point for REALIA™ COBOL!

- A full IEEE floating point math package for your REALIA COBOL programs.
- 8087 numeric co-processor support and EMULATION. Switching from emulation to true 8087 instructions is done automatically at RUN time - transparent to the user!
- A full set of both arithmetic and TRIGONOMETRY functions have been provided.
- Conversion routines allow your REALIA program to pass data to and from FPLIB by either using DISPLAY types or COMP-5 data types.
- FREE Updates for 1 year.
- SOURCE CODE available.

Only \$149.00 Complete

asmTREE

The Programmer's B+Tree Data File Management System

- A complete single/multiuser database development system written in assembly language and CALLable directly from Microsoft™ Assembler, C, FORTRAN, PASCAL, and LATTICE™ C programs.
- Up to 256 users.
- Up to 256 index and data files.
- Multiple key types.
- Multiple indices per index file.
- Duplicate and variable length keys.
- Read DBASE data files directly.
- Plus much, much more
- Supplied with complete source code.

Only \$395.00 Complete



Turbo.ASM

For TURBO Users!

Turbo.ASM™ (turbo dot a.s.m.)

- A unique programming tool which is a must for every Turbo Pascal user. The only package designed for the Turbo user who wants to get into Assembly Language.
- Outlines 4 different ways to add assembly language routines to Turbo programs without effecting your code space.
- Fully explains internal workings of Turbo Pascal and data passing methods.
- Includes a library of Assembly routines which can be used directly from Turbo Pascal.
- NO ROYALTIES required.

Only \$99.95 Complete

B C ASSOCIATES

3261 No. Harbor Blvd., Suite B
Fullerton, CA 92635

1-800-262-8010

in Calif. Call

(714) 526-5151

Call for information on complete line of
SimpleNET networking products.

Outside CA, call TOLL FREE 1-800-262-8010

USE YOUR VISA OR MASTERCHARGE -  

All prices include UPS shipping within continental United States. Outside U.S. please add \$10 per package. Calif. residents please add 6.5% sales tax.

Now You Know Why **BRIEF** is **BEST**

"If you need a general-purpose PC programming editor, look no further. Recommended."

- Jerry Pournelle, Byte, 12/86

The Program Editor with the **BEST** Features

Since its introduction, BRIEF has been sweeping programmers off their feet. Why? Because BRIEF offers the features **MOST ASKED FOR** by professional programmers. In fact, BRIEF has just about every feature you've ever seen or imagined, including the ability to configure windows, keyboard assignments, and commands to **YOUR** preference. One reviewer (David Irwin, DATA BASED ADVISOR) put it most aptly, "(BRIEF)... is quite simply the best code editor I have seen."

Solution Systems™

WINDOWS

Brief does do windows, and it does them your way!

You can split the screen horizontally and vertically multiple times, creating as many windows as will fit on the screen. Each window can show any part of any file.

BRIEF's flexible, easy to use windows make working with several files a breeze.

"The main thing is that it [BRIEF] will do just about anything you want it to. It has windows— boy, does it ever have windows!...

For the last few months... I've got a raft of mail urging me to try Brief. Now that I've tried it I see why."

Jerry Pournelle - Byte Magazine, Dec. 1986

Every Feature You Can Imagine

Compare these features with your editor (or any other for that matter).

- FAST
- Full UNDO (N Times)
- Edit Multiple Large Files
- Compiler-specific support, like auto indent, syntax check, compile within BRIEF, and template editing
- Exit to DOS inside BRIEF
- Uses all Available Memory
- Tutorial
- Repeat Keystroke Sequences
- 15 Minute Learning Time
- Windows (Tiled and Pop-up)
- Unlimited File Size (even 2 Meg!)
- Reconfigurable Keyboard
- Context Sensitive Help
- Search for "regular expressions"
- Mnemonic Key Assignments
- Horizontal Scrolling
- Comprehensive Error Recovery
- A Complete Compiled Programmable and Readable Macro Language
- EGA and Large Display Support
- Adjustable line length up to 512

MONEY-BACK GUARANTEE

Try BRIEF (\$195) for 30 days - If not satisfied get a full refund.

TO ORDER CALL (800-821-2492)

Program Editing YOUR Way

A typical program editor requires you to adjust your style of programming to its particular requirements - NOT SO WITH BRIEF. You can easily customize BRIEF to your way of doing things, making it a natural extension of your mind. For example, you can create ANY command and assign it to ANY key - even basic function keys such as cursor-control keys or the return key.

The Experts Agree

Reviewers at BYTE, INFO WORLD, DATA BASED ADVISOR, and DR. DOBB'S JOURNAL all came to the same conclusion - **BRIEF IS BEST!**

Further, of 20 top industry experts who were given BRIEF to test, 15 were so impressed they scrapped their existing editors!

NOT COPY PROTECTED

siderations in using object-oriented LISP for AI purposes? As I have already suggested, certainly one of the most important is the dynamic behavior of class systems. This refers to the ability of an object system to change dynamically to reflect changing circumstances in the world. In many AI programs it is of considerable importance that the system be able to update itself automatically to a greater or lesser degree. It is helpful to consider what this implies.

A minimum condition for such an automatic system is to keep a running tally of all the system's current objects of various kinds in a form that is easily accessible. In LISP this generally means maintaining a list of such items and being able to update the list as necessary. More specifically, it is necessary to be able to access at any given time all the instances that are currently alive and know their classes. If the system does not already do this in some way, then it is essential that it at least support the minimum functions that would allow these features to be implemented.

Closely related to this requirement is the ability to write functions that can create new objects with names that are determined only at run time. Although this may sound trivial, in LISP it is easy to create new objects by programming them with names the programmer specifies in the code, but it is not nearly as straightforward to write functions that automatically create objects when needed with names that have to be specified at the time. Compared with this, "uncreating" objects is relatively trivial. If there is no function corresponding to *remob* in use, then it is still always possible to make a new object with the same name as the uncreated one and set it equal to nil.

Such functions are necessary for creating what are known as composite objects, for example. These are objects of a complex structure that contain other objects as parts. So, for example, a *desk* object could be described as a composite object composed of a *top*, *legs*, and *drawers*. In such a case, the components might well be instances of classes in their own right. To create a composite ob-

ject automatically, therefore, would involve naming and creating all those instances that are parts of the composite.

In a sense, the parts of a composite object can form another hierarchy that can exist alongside the abstraction hierarchy of classes containing the main composite object. The composite object approach seems to have real limits as far as creating very large hierarchies is concerned, however. It is difficult to imagine creating very large systems such as spacecraft in any degree of detail. Are such systems necessary? If you want to be able eventually to create deep systems for diagnosing problems and predicting various consequences in emergency situations, or even for failure-mode analysis for design purposes, then such systems appear to be indispensable.

Many LISP programmers are anxious for an object-oriented extension to Common LISP and wish there were already such a standard for the dialect. At the present time several LISP vendors have developed their own proposed extensions, which they hope will be adopted as the standard object-oriented extension to Common LISP.

In the Spotlight

I asked some experts in object-oriented LISP both what they wanted to see happen and what they thought would happen in the quest to develop an agreed-upon standard for object-oriented programming in Common LISP. Currently, there is an organized effort to develop such a standard with formal ANSI recognition. Toward that end, a committee has been formed to draft a proposed standard that will then be made available to the programming community for its feedback so that a true "community standard" might emerge. The members of this object-oriented working group include Dan Bobrow and Gregor Kiczales of Xerox; David Moon, Dan Weinreb, and Sonja Keene of Symbolics; Richard Gabriel and Linda Demichael of Lucid; Jim Kempf of Hewlett-Packard; and Patrick Dussud of Texas Instruments.

Gabriel is the president of Lucid, a vendor of Common LISP for a variety of different machines, and author of

the book *Performance and Evaluation of Lisp Systems* (MIT Press, 1985). I spoke to him regarding the developing standard for an object-oriented extension to Common LISP. Gabriel sees his own role as a kind of "buffer zone" to help mediate the potentially inflammatory relations between Xerox, advocate of CommonLoops, and Symbolics, advocate of New Flavors. Although Gabriel is not optimistic about the solution of many of the subtle problems in formulating an adequate standard rapidly, he feels that a reasonable standard is emerging that has many of the features of New Flavors "on the surface" while utilizing much of CommonLoops "underneath."

I asked Gabriel about some of the difficult issues involved in formulating the new standard, such as the issue of dealing somehow with the fact that readable code is often not efficient and, conversely, efficient code is often not readable. Gabriel admits that this is a pervasive problem that will not go away easily. One difficulty is that often programmers who know the details of a given application can find various ways to exploit certain idiosyncrasies of the way it is coded to improve performance considerably. Tricks of this kind are obviously specific to the particular application and are often opaque to another programmer reading the code. The main reason for this, according to Gabriel, is that "most efficient code uses side effects to a considerable degree." Gabriel thinks that advanced knowledge-based systems for program optimization will ultimately be necessary to solve this problem. Another possibility is parallel LISP because, as Gabriel points out, "the programs with the least side effects run fastest on parallel machines." Gabriel is currently working on Qlisp, a parallel LISP language, with John McCarthy, the inventor of LISP.


Another problem specific to object-oriented systems is that currently instances in most systems are strictly subservient to classes in that an instance object is always an instance of one and only one predefined class, which is used as a kind of template for creating the instance. This has a built-in bias for the abstract over the concrete, which could put a limit on

the type of object-oriented AI programs that can be written. For example, it might be highly desirable in certain AI programs that an object be created that is not initially an instance of any particular class but that later on might be. One way around this would be to first make the object an instance of a neutral holder class, such as *Object* in Smalltalk or *t* in CommonLoops, and have a provision for changing the object's parent class at a later time.

Another person I asked for comments about the object-oriented extension to Common LISP was Gerry Barber, chief scientist at Gold Hill Computers, the main vendor for a subset of Common LISP on MS-DOS machines. The main issues Barber and his group at Gold Hill seem concerned about are that the standard make use of those features that are well understood and trouble-free. In this respect, he has some doubts about the metaobject protocol that forms the heart of CommonLoops. Barber is apparently not as confident as members of the standards working committee are that the metaclass approach that works so well in Smalltalk and CommonLoops is well-tested enough in the LISP environment to find a place in the standard. He agrees that it would be desirable to have a system that has an inherent flexibility and generality, but "it is important," he says, "to find the right generality and the right flexibility." Barber sums up the outlook at Gold Hill as follows: "Our strategy is to rely on things that have been shown not to have problems." Regardless of whether the new standard is ready in time, Gold Hill plans to release its own object-oriented extension to Common LISP—a system that will probably closely resemble the Flavors system from Symbolics—early in 1987.

The third person I spoke to on the same topic was Dan Bobrow of the Intelligent Systems Laboratory at Xerox PARC, considered by many to be the foremost authority on object-oriented programming in AI. Compared with Gabriel and Barber, Bobrow is most optimistic concerning the emerging standard for objects in Common LISP. He doesn't feel that what has been reached so far is simply a compromise between the Xerox

ISN'T IT A PITY...



Everything Isn't As Accommodating As

c-treeTM / r-treeTM
FILE HANDLER / REPORT GENERATOR

Performance and Portability

For all the time you devote to developing your new programs, doesn't it make sense to insure they perform like lightning and can be ported with ease?

c-tree: Multi-Key ISAM Functions For Single User, Network, & Multi Tasking Systems

Based on the most advanced B+ Tree routines available today, **c-tree** gives you unmatched keyed file accessing performance and complete C Source Code. Thousands of professional C programmers are already enjoying **c-tree's** royalty-free benefits, outstanding performance, and unparalleled portability.

Only FairCom provides single and multi-user capabilities in one source code package, including locking routines for Unix, Xenix, and DOS 3.1., for one low price! In addition, **c-tree** supports fixed and variable record length data files; fixed and variable length key values with key compression; multiple indices in a single index file; and automatic sharing of file descriptors.

r-tree: Multi-File Report Generator

r-tree builds on the power of **c-tree** to provide sophisticated, multi-line reports. Information spanning multiple files may be used for display purposes or to direct record selection. You can develop new reports or change existing reports without programming or recompiling and can use any text editor to

create or modify **r-tree** report scripts including the complete report layout. At your option, end users may even modify the report scripts you provide.

Unlimited Virtual Fields; Automatic File Traversal

r-tree report scripts can define any number of virtual fields based on complex computational expressions involving application defined data objects and other virtual fields. In addition, **r-tree** automatically computes values based on the MAX, MIN, SUM, FRQ, or AVG of values spread over multiple records. **r-tree** even lets you nest these computational functions, causing files from different logical levels to be automatically traversed.

Unlike other report generators, **r-tree** allows you to distribute executable code capable of producing new reports or changing existing reports without royalty payments, provided the code is tied to an application. Your complete source code also includes the report script interpreter and compiler.

How To Order

Put FairCom leadership in programmers utilities to work for you. Order **c-tree** today for \$395 or **r-tree** for \$295. (When ordered together, **r-tree** is only \$255). For VISA, MasterCard and C.O.D. orders, call 314/445-6833. For **c-tree** benchmark comparisons, write FairCom, 2606 Johnson Drive, Columbia, MO 65203.



Complete C Source Code & No Royalties!

Xenix is a registered trademark of Microsoft Corp. Unix is a registered trademark of AT&T

Circle no. 93 on reader service card.

IT'S ABOUT TIME

APL. 68000

- Macintosh
- Atari ST
- Amiga

APL. 68000 is a highly optimized 68000 Assembler based APL Interpreter which takes full advantage of these computers' special features including user-defined pull-down menus and Dialog and Alert boxes. All this, along with a complete interface to graphics, are the reasons that APL. 68000 sets the industry standard for performance and capabilities.

Also available on PC & compatibles using 10MHZ 1MB MC68000 Coprocessor for \$995. Call for details

\$295

Order direct for \$295 + shipping (\$7 US, \$10 Canada). VISA/MC/AMEX add 4%. Check, MO or COD. Demo Disk available for \$15 + shipping (\$2.50 US, \$6 Canada) May be applied to full version purchase.

30 DAY MONEY BACK GUARANTEE

SPENCER ORGANIZATION INC.

P.O. Box 248 Westwood, N.J. 07675
(201) 666-6011



Circle no. 381 on reader service card.

The Advanced Programmer's Editor That Doesn't Waste Your Time

EPSILON

- Fast, EMACS-style commands—completely reconfigurable
- Run other programs without stopping Epsilon—concurrently
- C Language support—fix errors while your compiler runs
- Powerful extension language
- Multiple windows, files
- Unlimited file size, line length
- 30 day money-back guarantee
- Great on-line help system
- Regular Expression search
- Supports large displays
- Not copy protected

Only \$195

Lugaru
Software Ltd.

5740 Darlington Road
Pittsburgh, PA 15217

**Call
(412) 421-5911**

for IBM PC/XT/AT's or compatibles

Circle no. 135 on reader service card.

ARTIFICIAL INTELLIGENCE (continued from page 133)

and Symbolics proposals. He feels that what is happening is a genuine synthesis of the best ideas that are around right now in object-oriented LISP. To him, the atmosphere is not one of tension between competing proposals but rather a true professional collaboration, much in the same spirit that produced the original Common LISP standard.

I also asked Bobrow what some of the limitations might be with the emerging standard. Here again, his answers were positive. For example, I raised some of the issues I had discussed with Gabriel, such as the need in advanced AI applications to be able to have the same object simultaneously present in several different hierarchies. Here he felt certain that the new standard did not rule out the ability to program such applications. I also raised the issue of efficiency and trouble-free operation vs. adaptability and flexibility. Once again he was optimistic and indicated that it would indeed be possible to include different compilation options for different uses of objects. This would mean, for example, that those programmers using objects for systems programming and user interfaces, who are primarily interested in producing fast, unmodifiable, trouble-free code, could use one compilation and those who use objects in AI programs that need to have greater flexibility and the ability to modify themselves dynamically could use a different compilation option. In this way, both types of users could be satisfied.

In my next column I'll continue the theme of object-oriented AI by focusing on some specific implementations of object-oriented languages.

Bibliography

Bobrow, D., et al. "Merging LISP and Object-Oriented Programming." *OOPSLA '86 Proceedings*.

Moon, D. "Object-Oriented Programming with Flavors." *OOPSLA '86 Proceedings*.

DDJ

Vote for your favorite feature/article.
Circle Reader Service No. 7.

15 SUCCESS MANUALS that could solve your money problems once and for all!

FASTEST, EASIEST ... PROVEN PROFITABLE BUSINESSES YOU CAN QUICKLY START AND OPERATE FROM HOME WITH LOW OR NO CAPITAL ... PART TIME OR FULL TIME...

No experience required ... Nothing complicated to study ... Strictly legal and honest ...

Each beginners Success Manual is Guaranteed to teach you everything you need to know to succeed fast! The perfect answer for ambitious men and women ...

1. FIFTY QUICK, EASY AND MOST UNUSUAL WAYS TO POCKET "GIANT DOLLARS!"

Here's your chance to discover how so many folks miss out on numerous opportunities to pull in some big, fast cash. A most unique money-opportunity book which quickly shows you how just ordinary men and women from all walks of life are building spare time and full time fortunes; plus home businesses, money secrets, wealth-building methods, out-of-the-ordinary plans and odd blue prints to success, plus more. (only \$6.95)

11. HOW TO SIT BACK AND RAKE IN A BUNDLE SELLING BOOKS BY MAIL:

Practically all mail order experts agree that absolutely nothing sells better by mail than books ... and there's nothing that sells easier than books. Better yet — you stand to make bigger and faster net profits from selling books by mail than you could realize on any other items. You will be shown everything from A to Z. (only \$6.95)

HOW TO SIT BACK AND RAKE IN A BUNDLE SELLING BOOKS BY MAIL



2. HOW TO STACK UP HUGE MAIL ORDER PROFITS — HAND OVER FIST WITHOUT BREAKING YOUR BACK (OR RISKING AN ARM OR A LEG)

Shows you how to immediately set up — and get your operation off to a smooth flying start. Quickly teaches you short cut mail order fundamentals from A to Z. Crammed with insider "tricks of the trade" and revealing "money getting gimmicks." Imagine yourself receiving envelopes containing hundreds of dollars or more a day every day — that's the potential of mail order. (only \$6.95)

HOW TO STACK UP HUGE MAIL ORDER PROFITS — HAND OVER FIST WITHOUT BREAKING YOUR BACK (OR RISKING AN ARM OR A LEG)



3. HOW TO SEW YOUR WAY TO PRETTY PROFITS FAST!

It's a fact that millions of women (and men, too) own their own sewing machines ... and truly enjoy sewing. This peculiarly profitable book clearly demonstrates to them how to, virtually, turn their sewing machines into money making machines ... and take fast and full advantage of today's most promising market conditions. Especially — considering the present sky-high prices. (only \$6.95)

HOW TO SEW YOUR WAY TO PRETTY PROFITS FAST!



4. HOW TO TURN YOUR TELEPHONE INTO A MONEY MAKING MACHINE:

Right now your phone is only costing you money — but if you knew how to make it work for you, it could be making you money. Many people have heard about men and women making handsome incomes, via their telephone. But only a few people know exactly how it's done. Complete easy-to-follow instructions. (only \$6.95)

HOW TO TURN YOUR TELEPHONE INTO A MONEY MAKING MACHINE



5. HOW TO EARN A FISTFUL OF MONEY WITH NEWSPAPER CLIPPINGS:

Imagine, earning good money by clipping articles from newspapers? This unusual book instructs you in straight-to-the-point, how-to-information. Fast starting operation by mail on a tiny shoestring capital. Unusual way to earn \$50, \$100, \$300 or more, weekly. Ideal for ambitious Homeworkees, spare-time or full. (only \$6.95)

HOW TO EARN A FISTFUL OF MONEY WITH NEWSPAPER CLIPPINGS



6. HOW REAL ESTATE CAN MAKE YOU A FORTUNE ... USING OTHER "FOLKS MONEY:"

Real estate has produced more millionaires than any other field. The plans inside this amazing fast, fortune-building book tells why and how, in easy-ABC fashion; learn how to let other folks money work for you; speculate in raw land and get back \$5 for every \$1 you put in; rake in huge profits on Uncle Sam's losses; set up a nice income for yourself and your family with little or no investment. (only \$6.95)

HOW REAL ESTATE CAN MAKE YOU A FORTUNE ... USING OTHER "FOLKS MONEY:"



7. WORK-AT-HOME SUCCESS GUIDE (For Men and Women)

Time and time again — successful spare time and full time businesses are made with out-of-the-ordinary methods; off beat money making ideas, prosperous home enterprises. Shows how plain every day folks from all walks of life can stack up good money. Here's your opportunity to go after incredible wealth. (only \$6.95)

THE AMAZING HOME WORKERS' WORK-AT-HOME SUCCESS GUIDE (For Men and Women)



8. AMAZING MONEY MAKING TREASURY OF 1 & 2 INGREDIENT FORMULAS THAT COULD PUT YOU ON EASY STREET

This startling opportunity book places the little "beginner" operator with tiny capital in a most profitable position to manufacture sellable products. All preparations require no more than two chemicals, many just one. All represent a popular best-seller kind of product with both genuine merit and wide sales appeal. No expensive equipment or facilities required. You can almost always pack everything from your kitchen. (only \$6.95)

AMAZING MONEY MAKING TREASURY OF 1 & 2 INGREDIENT FORMULAS THAT COULD PUT YOU ON EASY STREET



9. WORLD'S EASIEST MOST PROFITABLE MAIL ORDER BUSINESS ...

A relatively uncrowded business that any man or woman can enter regardless of age. Book shows you how to start small, with "piggy bank" capital and grow prosperous year after year. Reveals the surest, most profitable and safest items to sell by mail. Crammed with all the precious, easy-to-understand details. (only \$6.95)

WORLD'S EASIEST MOST PROFITABLE MAIL ORDER BUSINESS



10. TWELVE SIMPLE LITTLE-KNOWN WAYS TO MAKE BIG MONEY FAST!

An amazing book that clearly reveals a dozen ways men and women could pocket some real fast cash profits — if they only knew the right wealth building moves to make. This book quickly teaches you all the necessary moves, shows you exactly how and what to do to help assure your success. (only \$6.95)

TWELVE SIMPLE LITTLE-KNOWN WAYS TO MAKE BIG MONEY FAST!



12. HOW TO WIN BIG CASH AND VALUABLE PRIZES CONTESTS:

This unique book quickly shows you all the important inside tricks. Opportunity to win national and local contests again and again. Cash, cars, homes, appliances, furs and vacations ... No other publication on the market exactly like it. (only \$6.95)

HOW TO WIN BIG CASH AND VALUABLE PRIZES CONTESTS



13. BIG FAST FULL TIME AND PART TIME PROFITS FOR WOMEN:

This book is a remarkable treasury of unique but common sense, easy to operate Little "big" money making businesses for many millions of today's serious and enterprising women interested in fabulous earnings, independence and security. Little or no investment and fast starting full- and part-time income increasing activities. (only \$6.95)

BIG FAST FULL TIME AND PART TIME PROFITS FOR WOMEN



14. EASIEST AND FASTEST WAY TO START A SUCCESSFUL MAIL ORDER BUSINESS ON A SHOESTRING:

Simple, and most effective, step-by-step mail order start-up and operating instructions written especially for beginners. Crammed with vital facts ... Covers every aspect of this exciting big money field. (only \$6.95)

EASIEST AND FASTEST WAY TO START A SUCCESSFUL MAIL ORDER BUSINESS ON A SHOESTRING



15. HOW TO SEE THE WORLD ... TRAVEL AND GET PAID WELL FOR IT:

Everyone enjoys traveling. But most people cannot afford to travel to those far away places they dreamed of visiting. Here's your chance to take in the wonderful sights throughout the world — and actually get paid for doing it. Yes, it's truly possible that this little known strictly legal method could provide you with the information for doing it. (only \$6.95)

HOW TO SEE THE WORLD ... TRAVEL AND GET PAID WELL FOR IT



Fifteen Ways For You To Have Bulging Bank Accounts, Beautiful Homes, Expensive Clothes, Jewelry, Exotic Vacations ... The Very Best Colleges For Your Kids ... Plus, Keep A Steady Income Flowing In!

Everyone of the 15 Manuals' home-based businesses, can be successfully operated, by a single person, retirees, unemployed people — most ideal for husband/wife teams — and can be, almost, instantly turned into an enterprising family operated business, kids can help too. With everyone pitching in ... your business could suddenly take off, and profits could increase fast!

So, be sure to keep in mind that: Even though, it's true — some good money could be made with just a single one of these start-up success manuals working for you ... but, much better than that, you could give yourself a greater opportunity to make your profits multiply much faster, by simply putting together a super powerful profitable combination of five, ten, or more of these fifteen — fastest, easiest ... proven profitable businesses out of over a thousand in our files. Imagine having them all operating, and bringing in big hefty profits for you, at the same time! But you must send your order in right away. Supplies are extremely limited at these special introductory low prices!

FREE The More Success Manuals You Order The More FREE Limited Editions You Get

Buy Any 2 to 5 SUCCESS MANUALS And Get Free! Any One Of The Three LIMITED EDITIONS Below, or Buy Any 6 to 10 SUCCESS MANUALS And Get Free! Any Two Of The Three Below, or Buy Any 11 to 15 SUCCESS MANUALS And Get Free! All Three Below.

HOW TO RAISE ALL THE CASH YOU NEED IN A HURRY



How to raise all the cash you need in a hurry. If you need \$5,000, \$20,000, \$100,000 or more to help get your new business off the ground — then, you'll most certainly want to read this book. Even if you've already been turned down by banks ... and finance companies.

HOW TO QUICKLY WIPE OUT ALL YOUR DEBTS AND TURN BAD CREDIT RATING INTO GOOD



How to quickly wipe out all your debts and turn bad credit rating into good. Now with this amazing book — you can stop bill collectors cold in their tracks. Here's your golden opportunity to get out of debt without borrowing.

HOW TO RETIRE YOUNG AND LIVE LUXURIOUSLY ON VERY LITTLE MONEY



How to retire young and live luxuriously on very little money. Finally — It's possible for you to say "goodbye" and "good riddance" to that old out-dated idea that you must remain on a boring nickel and dime wage slave, time-clock punching job until you reach 65.

FINALLY—A REAL OPPORTUNITY TO ENJOY A RICHER ... BETTER LIFE

Our organization — Successful Business Publishers, offers what is perhaps the largest Collection of Unique "Home-business" Beginner's Success Manuals in the world! Out of over a thousand of businesses in our organization's files — our home business specialists, have painstakingly selected The 15 Fastest, Easiest ... Most highly Profitable part-time and fulltime Businesses you and other beginners can quickly start and easily operate from home — with very low or, virtually, no investment.

How many of these Proven, Highly Profitable Enterprises, can you combine together and successfully operate — and Benefit From At The Same Time? Possibly, all fifteen if you're that ambitious ... The big Shrewd Corporations, call this almost secret method "diversification" which is, merely, a high sounding big word, which simply boils down to — having a lot of different businesses, operating ... and pouring fast-fat profits into your pockets, at the same time.

Let's face it — Plain common sense says that — the more of these 15 Proven Profitable Businesses, you choose to operate at the same time ... the bigger, and faster your profits could be! Of course, our organization will profit a few more dollars if you choose to put five, ten or all fifteen of our proven profitable, start-up success manuals, to work for you.

But then — why should our making a modest few dollars of profit bother you — when it's you, who makes ... and keeps all the income — no matter how much — Your different home businesses bring in? The demand for our unique wealth-building, Beginners Start-Up Success Manuals has been so overwhelming ... and, understandably so too, since, there's absolutely nothing like them on the market!

Our No-Risk Success Guarantee To You

You must be absolutely, positively, and totally convinced that the actual money making success profitability of each manual is real — and may quickly increase your income or you may return everything within 10 days for a prompt no hassle refund.

Remember, those who snooze will certainly lose. However, those who choose right now, to begin — can win, and right now, while there's still time, is the best time to begin. You'll be making a very wide and highly profitable move. ORDER NOW!

Beginners Start-Up Success Manuals Order Form

Circle the manuals you are ordering

| | | | | | | | |
|---|----|----|----|----|----|----|---|
| 1 | 2 | 3 | 4 | 5 | 6 | 7 | 8 |
| 9 | 10 | 11 | 12 | 13 | 14 | 15 | |

I have circled above the catalog number of each Success Manual I am ordering, and I've included the proper amount to help cover shipping and handling, as indicated below. Also, I'm fully protected by your organization's strong, no-risk success guarantee that — unless I am totally convinced that the actual money making success profitability of my manual(s) is real — and may quickly increase my income. Also, I may return everything within 10 days, for a prompt, no-hassle, full refund.

Total Success Manuals Ordered

Full Amount Enclosed

Be sure to include proper shipping and handling fee — see charges below:

SHIPPING AND HANDLING CHARGES

Ordering just one Success Manual Add \$1.25 for S&H

Ordering from 2 to 5 Success Manuals Add 90¢ per each manual

Ordering from 6 to 14 Success Manuals Add 50¢ per each manual

ENJOY BIG SAVINGS ON ORDERS FOR ALL 15 SUCCESS MANUALS — We pay all Shipping & Handling Cost. (a hefty savings of \$7.50).

Note: We pay shipping and handling on each Limited Edition Manual your order qualifies for.

Check the box below which indicates each desired FREE Limited Edition Manual's Title(s) which your order qualifies you to receive FREE:

- ☐ How to quickly wipe out all your debts and turn bad credit rating into good
- ☐ How to raise all the cash you need in a hurry
- ☐ How to retire young and live luxuriously on very little money

METHOD OF PAYMENT (all prices are in U.S. funds):

☐ My check or money order is enclosed (do not send currency through the mail).

Sorry — due to high percentage of sale charged by card companies — charge card orders not accepted.

SHIP TO

Name _____

Address _____

City _____


State _____ Zip _____

Complete this order form and mail to:

SUCCESS BUSINESS PUBLISHERS
110 W. 5th Street
Winston-Salem, N.C. 27101

© 1985 Successful Business Publishers

DDJ ON LINE



#: 8534 S0/General/DDJ office

05-Dec-86 17:31:07

Sb: Screen Weirdness!

Fm: Chris Johnston

71505,1752

To: All

I know that this is going to sound crazy, but I was sitting at my desk at work, talking to a coworker who was running Microsoft Word on a 6-MHz IBM PC/AT with a CGA. I was finishing my lunch, crunching on one of those big hard pretzels, when I noticed that every time I crunched the screen image moved! Nothing else did, just the image on the screen, which seemed to get smaller along the vertical axis, as if the tube lost power momentarily. This is not a real change in the image because you have to be crunching to see the effect, but everybody else who tried it saw the same thing. Our assumption is that the vibrations set up when you crunch are some multiple of the vertical frame rate, causing an apparent change in the screen. On some machines I can see the vertical retrace line when I try this. It doesn't seem to happen on a TV set.

Is anybody interested in trying this out and seeing if it is a universal phenomenon? We've been talking about trying to measure the 'crunch frequencies' with an accelerometer but haven't tried it yet.

P.S. It works with hard cookies, too.

***There is a reply: 8538

#: 8538

Sb: Screen Weirdness!

Fm: Ray Duncan [DDJFORUM]

76703,4265

It's not crazy. I've been noticing the same thing for about a year in my office. The funny thing is, I never see it on my *own* screen, but I can easily see it on the screen of the guy who sits on the other side of the room. I always assumed it was 'real' and wondered why he never said anything about it, and I never really could dream up a reason for it.

*** There is a reply: 8549

#: 8549

Sb: Screen Weirdness!

Fm: Pete Becker 76347,3151

I'd guess it's physiological. Maybe the vibration from the crunch shakes the retina or something. Such an effect would be more pronounced on distant objects: because they produce a smaller image, an identical displacement is proportionately much larger.

*** There is a reply: 8552

#: 8552

Sb: Screen Weirdness!

Fm: Chris Johnston

71505,1752

That makes a lot of sense. We have an HP spectrum analyzer and one of those accelerometer-hammer things that you use for measuring the vibration frequencies of mechanical parts. You give the item a whack to excite it, and then it senses the vibrations that result. We have been thinking about trying the pretzel crunch test with the accelerometer pressed firmly against a cheekbone to see what happens. My bet is the resultant frequencies are some multiple of the 60-Hz vertical frame rate.

*** There is a reply: 8554

#: 8554

Sb: Screen Weirdness!

Fm: Pete Becker 76347,3151

There probably aren't any well-defined resultant frequencies—just a bunch of garbage, which, of course,

consists of all frequencies. I suppose a true controlled experiment would consist of putting the accelerometer against your cheekbone and hitting your jaw with a hammer so you have reproducible conditions. Any volunteers?

*** There are replies: 8555, 8603

#: 8603

Sb: Screen Weirdness!

Fm: Chris Johnston

71505,1752

No, I think I will skip the 'hit your jaw with a hammer part.' Somebody at work did suggest putting strain gauges on the pretzel! I'll try to remember to fire up the accelerometer/frequency analysis system and try out the less painful part of the test. I'll let you know!

#: 8555

Sb: Screen Weirdness!

Fm: jhon stanley 73765,1026

The wiggle is not psychological—it really exists. It is due to the vibration of the muscles of the eye, which try to correct themselves and therefore move the eye. It is so common that the brain automatically corrects for it. It can do a great job correcting those things that do not move but has trouble with moving things—like, for example, a band of light sweeping down the face of a CRT. The region of the CRT lit at any given time is small, maybe 1/2–1-inch tall. If your eye moves up while the band moves down, the screen will appear taller. Likewise, move the eye down and the picture gets smaller (somewhat like moving an original on the copy machine while the machine scans it). So, vibrate, and the picture wiggles.

I have shown this to many people, and they are always amazed. They don't believe it until they try it themselves.

*** There are replies: 8564, 8604

#: 8604

Sb: Screen Weirdness!

Fm: Chris Johnston

71505,1752

As I understand it, the eye wiggles a little all the time because nerves that are continuously stimulated shut down after a little while. The places where the receptors see light and dark alternate is near an edge. At a low level, we have an automatic edge discriminator built into the system.

#: 8564

Sb: Screen Weirdness!

Fm: Pete Becker 76347,3151

To: Jhon Stanley 73765,1026

I said 'physiological,' not psychological! Your explanation sounds good.

#: 8637

Sb: Screen Weirdness!

Fm: Jhon Stanley 73765,1026

The same thing happens, I have noticed recently, with LED clocks. The digits are scanned, as in a CRT, so the numbers also wiggle when you chew.

*** There is a reply: 8639

#: 8639

Sb: Screen Weirdness!

Fm: Pete Becker 76347,3151

Synchronicity! I was at my sister's this afternoon, and she called me into the kitchen and asked me to click my teeth together while looking at the clock on her microwave oven. Of course, I wouldn't do anything so undignified, but I gave her your explanation.

*** There is a reply: 8696

#: 8696

Sb: Screen Weirdness!

Fm: Jhon Stanley 73765,1026

I told a friend of mine at work to go brthththththphphphptttt at the 19-inch monitor we use because it would do something neat. He gave me this funny look and a half-heart-

ed brrrththt. I told him to try again. He did, and the look on his face told me he saw the effect. Ain't science wonderful?

DDJ

Vote for your favorite feature/article.
Circle Reader Service **No. 8.**

FTL MODULA-2 \$49.95

*The most programming power
for your money*

FTL MODULA-2 gives you:
► Full implementation of MODULA-2.
► Split screen, multi-file editor.
► Sources to the run-time modules.
► Complete support for the product.
► 8087 reals available for MSDOS.*

FTL MODULA-2 meets the standards in Niklaus Wirth's book, "Programming in MODULA-2", third edition. No other language gives you better flexibility, code design, or ease of code maintenance.

FTL MODULA-2 gives you compact, rommable code quickly. This is the language of the future. If you program in Pascal or C, FTL MODULA-2 will increase your output per programming hour. If you want to learn high level structured language programming, this is the best starting point.

FTL MODULA-2 was named "product of the year" by Jerry Pournelle in his column, "Computing at Chaos Manor", BYTE Magazine, April, 1986.

* 8087 support is an additional \$39.95

FTL Editor toolkit \$39.95

The source code to the editor is offered as a toolkit. The editor was written in FTL MODULA-2 and this set of programs provides the novice with working sources to speed up learning. The experienced programmer will find the wealth of pre-written modules a time-saving bonanza.

SAVE \$10.00

Buy both the compiler and the editor toolkit for only \$79.95. That's a \$10.00 savings off the regular price. **FTL MODULA-2 is available for both MSDOS and CP/M-80 systems.**



SEND
CHECK OR
MONEY ORDER
TO:

**Workman
& Associates**

1925 E. Mountain Street
Pasadena, CA 91104
(818) 791-7979 voice
(818) 791-1013 data M-F 8pm-8am
Or join us on BIX (Byte Information eXchange
W.A.N.D.A. Conference.)


Circle no. 244 on reader service card.



MasterCard and VISA welcome.
Please add \$3.00 Shipping and Handling.
Calif. residents please add 6% sales tax.



THE STATE OF BASIC



More BASIC Modules and Libraries

One of the shortcomings of the early versions of microcomputer BASIC was the absence of formal libraries of reusable code. The lack of support for multiline functions, callable BASIC subroutines, and local variables weakened any attempts to "simulate" BASIC libraries. The implementors of "new wave" BASICs, a phrase you will hear often, have recognized the need for supporting user-defined libraries. The solutions given by these new BASICs vary in the degree of flexibility and syntax, however. Let's take a look.

QuickBASIC lets you create libraries in two steps. First, you write the source code for a library and compile it into .OBJ form. The next step is to "build" an .EXE library file by using BUILDLIB.EXE, which is supplied with QuickBASIC. BUILDLIB.EXE is able to take one or more library object files and create a bigger library. To avoid confusion between libraries in .OBJ and .EXE files, you can rename the former as sublibraries. QuickBASIC permits your BASIC programs to use one library only. The default library is USERLIB.EXE, but you can instruct BUILDLIB.EXE to create libraries with other names. You must specify these library names when invoking QuickBASIC from the DOS command line.

The preceding discussion gives the impression that QuickBASIC supports one library at a time. The good news is that you can expand and update your .EXE library files by including new or modified sublibraries. To do this, you must store the .OBJ sublibrary files because you may rebuild a library periodically.

Example 1, below, shows a short subroutine that calculates the square root of a number using Newton's method. The library body has no formal declaration. Functions in QuickBASIC libraries are local to the library, so I have used a callable subroutine instead. A client QuickBASIC program need not make any special declarations to use the library subroutines; the burden falls on the program author to document external subroutine calls. The scheme of calling library subroutines in QuickBASIC offers a good degree of language extension.

In True BASIC, library files begin with the keyword *EXTERNAL*. Unlike QuickBASIC, all the subroutines and functions are accessible to the client program. Local variables are not automatically shared with other library routines or client programs; data flows through argument lists and data files. Unlike QuickBASIC, True BASIC enables your application program to use multiple libraries. You use the

syntax *LIBRARY <library names list>* to indicate the files containing the sought libraries. Functions imported from libraries must be declared in *DECLARE DEF <function names list>* statements. This feature of True BASIC permits you to maintain libraries in a more independent way than you can in QuickBASIC. In addition, libraries can call other libraries in True BASIC—a valuable feature for modular software development.

Example 2, below, shows the square root function in a True BASIC library. The library/module loading feature enables you to do away with explicit *LIBRARY* and *DECLARE DEF* statements related to the loaded libraries. In that respect, True BASIC also offers a vehicle for language extension.

BetterBASIC supports modules, so much so that the implementation itself is modular. A customizable configuration text file is used to list the modules that are loaded into memo-

```
SUB SQRROOT(X,S) static
  IF X >= 0 THEN
    ACCR = 1.0E-8
    S = X / 2
    WHILE ABS(S * S - X) > ACCR
      S = (X / S + S) / 2
    WEND
  ELSE
    S = -1 ' result for a negative argument
  END IF
END SUB
```

Example 1: QuickBASIC library subroutine to compute the square root using Newton's method

```
EXTERNAL ! declaration needed to define a True BASIC library
DEF FNSQRT(X)
  IF X >= 0 THEN
    LET ACCR = 1.0E-8
    LET S = X / 2
    DO WHILE ABS(S * S - X) > ACCR
      LET S = (X / S + S) / 2
    LOOP
    LET FNSQRT = S
  ELSE
    LET FNSQRT = -1 ! result for a negative argument
  END IF
END DEF
```

Example 2: True BASIC library function to compute the square root using Newton's method.

NEW RELEASE—Version 2.01
NOW Faster Than Ever!

| | Ackerman | | Sieve | | I/O | |
|-----------------------|----------|-----------|-------|-----------|------|-----------|
| Marshal Pascal | 11.9 | 3.5K | 4.8 | 2.4K | 1.8 | 5.1K |
| IBM Pascal | 12.4 | 34.7K | 11.7 | 27K | 2.5 | 24.5K |
| Turbo Pascal | 22.7 | 11.6K | 14.2 | 11.5K | 2.2 | 12.5K |
| Microsoft C 4.0 | 15.9 | 9.3K | 5.8 | 6.5K | 1.9 | 8.9K |
| Oregon Pascal-2 | 18.2 | 13.9K | 7.2 | 11.7K | 2.5 | 22K |
| | Sec. | Code Size | Sec. | Code Size | Min. | Code Size |



POWER CORRUPTS!

Actually, it only took him a couple of days with Marshal Pascal. Marshal Pascal produces code smaller and faster than any other High Order Language on the PC. Period. Even optimized C compilers don't come near our performance. And Marshal Pascal allows you to generate an assembly language listing of your code, to boot. So it's not surprising that some people would fudge the truth.

However, speed and compactness are not enough. Power and ease of use are important, too. With Marshal Pascal you may address as much memory as your operating system allows and a variety of memory models are supported. Among the useful extensions included are: separate compilation of modules (both Modula-2 and Pascal forms), structured constants and structured function values, variable-length string types, overlays, long integers and procedural parameters. Our relocatable linker allows you access to the Microsoft family of languages and assemblers. The data-flow analyzer in the compiler automatically crunches your code far better (and with less headaches) than one can achieve by manually utilizing register variables. We support the Intel 8087-80287 math processors *inline*. If you don't have the math chip, then '87/287 simulation is a provided option. We also provide a number of compile options, including an optimization by-pass for speedier compiles, I/O "fine-tuning," and constant folds. A wealth of compile-time checks will help reduce your debug time enormously.

If that weren't enough, we also give you a **Turbo Translator**, allowing you to use the hundreds of application and utility programs written in Turbo Pascal® that are available in source from the public domain. Marshal Pascal supports most of the same extensions that are in Turbo Pascal, including low level hooks and inline coding, providing the Turbo user with the easiest and most comprehensive "step up" possible.

Space does not permit us to list all the features of Marshal Pascal, all of which are provided USER options, not additional COST options. Our compiler is not broken apart to make many products out of what should be only one good one.

Only, please folks, no matter how tempting it may be, don't fib to people once you start programming with Marshal Pascal!

the Price?

\$189.

Marshal Pascal™

Supports PC-DOS®, MS-DOS®, CP/M-86®, Concurrent Dos®
and soon Xenix 286/386®!

Marshal Pascal is a TM of Marshal Language Systems. CP/M-86 and Concurrent Dos are R of Digital Research, Inc., PC-DOS is a R of IBM Corp., Turbo Pascal is a R of Borland International, Inc., MS-DOS and Xenix 286/386 are R of Microsoft Corp. Pascal-2 is a TM of Oregon Software.

To order your copy of Marshal Pascal call: (800) 826-2222
In California: (415) 947-1000

Marshal Language Systems

1136 Saranap Ave., Ste. P, POB 2010, Walnut Creek, CA 94595
Circle no. 317 on reader service card.

New Version 2.0

Complete C Programs in Half the Time, with *Instant-C*TM

You can create programs much faster with *Instant-C* than with conventional programming tools. How? Because *Instant-C* is a high-performance interpreter, there are **no compile or link delays**. Change your program, then test it immediately. No matter how large your program, the turnaround time is just seconds.

"Instant-C means instant gratification." —*PC Magazine*. **Editor's Choice** for best C interpreter.

Powerful **source-level debugging** saves your time. Conditional breakpoints, single-stepping by statement, source code backtraces, data monitoring, and many other debugging features make it easy to wipe out bugs quickly. Direct execution of any statement or function makes testing a breeze.

"The resulting debugging and testing capabilities are fantastic and the detailed trace/debug/display commands make it easy." —*The C Journal*

Instant-C checks pointer references for reasonableness, and checks that array indexes are within declared bounds. This **run-time checking** stops your program as soon as errors occur, for easiest debugging.

Not only does *Instant-C* help you quickly change, test, check and debug your code, but it runs your program **fast enough for real-time applications**.

"It is much faster than any of the other products mentioned and was the only one able to complete the standard SIEVE in a reasonable time. Clearly, this high speed allows much more complex problems to be attacked with *Instant-C* than with any of the other products discussed." —*Computer Language*

Immediate feedback and precise diagnostics make *Instant-C* great for learning C. Full K&R and the ability to **link compiled object code and libraries** (Lattice and Microsoft) makes *Instant-C* compatible with your existing programs.

Instant-C makes all parts of the programming task as fast as possible.

"Clearly, *Instant-C* is the performance champion." —*PC Tech Journal*

Version 2 works with MS-DOS and PC-DOS, and has a full 31 day **money back guarantee**. *Instant-C* is only \$495. Order today! Call or write for full information.

Rational Systems, Inc. P.O. Box 480
Natick, MA 01760
(617) 653-6194

Circle no. 145 on reader service card.

THE STATE OF BASIC

(continued from page 138)

ry to provide your BASIC applications with additional routines. Some of the libraries are used to make Better BASIC compatible with BASICA.

To create a module in BetterBASIC, you create a new workspace in which you define local and exported routines as well as module initialization. You use a *PUBLIC* declaration as an export list; any routine not listed is strictly local. Creating a module in BetterBASIC is an interactive process. It involves a *MAKE MODULE <name>* command in which BetterBASIC requests you to verify your *PUBLIC* declaration and *MAIN* code (used to initialize the module). An affirmative answer puts your module in memory and makes its functions accessible as an extension of the language. Information is passed to module routines via argument lists, data files, or the use of pointers.

Example 3, below, shows a module that exports the BetterBASIC version of my square root function. Notice that BetterBASIC requires line numbers in some portions of the code. The declarations of variables are similar to those of Pascal (more about this in a future column). BetterBASIC uses a reserved identifier *RESULT* instead of the function name to return the result of a function. Also notice that the function arguments are not listed immediately after the function name but on the line that follows the function name declaration.

The implementation of libraries in the new wave BASICs, among other new features, offers an enhanced level of software engineering. The

presence of software libraries acknowledges the following:

- the need for reliable software building blocks
- the shortening of development time by reusing existing routines
- support for structured and more systematic program development



Vote for your favorite feature/article.
Circle Reader Service No. 9.

Vendors

BetterBASIC

Summit Software
106 Access Rd.
Norwood, MA 02062
(617) 769-7966
\$199
Reader Service Number 50

QUICKBASIC

Microsoft Corp.
16011
N.E. 36th Way
Redmond, WA 98052
(206) 882-8088
\$99
Reader Service Number 51

True BASIC

True BASIC Inc.
39 S. Main St.
Hanover, HN 03755
(603) 643-3882
(call for prices)
Reader Service Number 52

```
PUBLIC: SQROOT

REAL FUNCTION: SQROOT
REAL ARG: X
REAL: S, Accr
10 Accr = 1.0E-8
20 S = X / 2
30 WHILE ABS(S * S - X) > Accr DO
40 S = (X / S + S) / 2
50 REPEAT
60 RESULT = S
END FUNCTION
```

Example 3: BetterBASIC library function to compute the square root using Newton's method

AVAILABLE NOW!

SK: The System Kernel & DS: The Console Display

OF THE TELE OPERATING SYSTEM TOOLKIT

Tele is a multitasking operating system written in C and assembly language for IBM PC compatibles. **SK: The System Kernel** of the Tele Operating System, including the most crucial part of Tele—the task scheduling algorithm first published in Dr. Dobb's December 1986 issue, and **DS: The Console Display** are now available.

SK: The System Kernel is required by **DS: The Console Display**, and by the soon-to-be released File and Index systems of the Tele Operating System Toolkit. When all components of the Toolkit are integrated they form an independent operating system for any 8086-based machine. **Tele** has also been designed for compatibility with MS-DOS, Unix and the MOSI standard.



SK: The System Kernel contains an initialization module, general purpose utility functions, and a real time task management system. **SK: The System Kernel** provides MS-DOS applications with multitasking capabilities. Only \$49.95!

SK: The System Kernel

Item #090

\$49.95


DS: The Console Display contains BIOS level drivers for a memory-mapped display, window management support and communication coordination between operator and tasks in a multitasking environment. Only \$39.95!

DS: The Console Display

Item #091

\$39.95

Both SK and DS include
all C and assembler
source code as well as
the precompiled libraries!
MS-DOS disk format.



Order Form

To Order: Return this order form with your payment to M&T Books,
501 Galveston Dr., Redwood City, CA 94063
Or, Call **TOLL-FREE 800-533-4372** Mon-Fri 8AM-5PM
In CA call **800-356-2002**

Name _____

Address _____

City _____ State _____ Zip _____

☐ Check enclosed. Make payable to M&T Publishing.

Charge my ☐ VISA ☐ M/C ☐ Amer. Exp.

Card No. _____ Exp. _____

Signature _____

Item #

Description

Price

| | | |
|--|--|--|
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |

Subtotal _____


CA residents add sales tax _____ % _____

Add \$2.25 per item for shipping _____

TOTAL _____

3125A

OF INTEREST



Languages

Pecan Software Systems' implementation of UCSD Pascal for the Apple IIGS is source-compatible with Apple Pascal. Extensions beyond Apple Pascal are offered in areas of multitasking, dynamic memory management, extended-precision arithmetic, and separate compilation. The software is ProDOS compatible and utilizes the new features of the Apple IIGS, including extended memory, sound, and graphics. The Power System Professional Pak is available for \$199.95. Reader Service No. 16.

Pecan Software Systems Inc.
1410 39th St.
Brooklyn, NY 11218
(718) 851-3100

Hard Disks/Utilities

Storage Dimensions has introduced the AT160F, a 320-megabyte, high-performance, internal, dual hard-disk drive for IBM PC/ATs and compatibles. The AT160F reduces access time, breaks the 32-megabyte DOS barrier, and surpasses ROM BIOS maximum storage restrictions. It is fully compatible with the IBM PC/AT and its standard Western Digital controller card. Price for the AT160F ranges from \$5,995 to \$9,995, depending on storage capacity, number of drives, and the inclusion of controller. Reader Service No. 17.

Storage Dimensions
14127 Capri Dr.
Los Gatos, CA 95030
(408) 370-3304

The Storage Products Division of **Fujitsu America** has announced a high-performance, 5 $\frac{1}{4}$ -inch, optical disk drive with a 600-megabyte formatted capacity. The M2505A WORM (write

once, read many) drive utilizes a two-laser head design for fast throughput and interlink tracking to improve data reliability. The drive has a positioning time of 100 milliseconds, a rotational speed of 1,800 RPM, a transfer rate of 124K per second, and utilizes the Enhanced Storage Device Interface. The M2505A with M1080A controller is priced at \$3,500, and media for the 5 $\frac{1}{4}$ -inch drive is priced at \$100. Reader Service No. 18.

Fujitsu America
3055 Orchard Dr.
San Jose, CA 95134
(408) 946-8777

Design Software has released DSBACKUP+ and DSRECOVER, hard-disk backup and protection utilities for the IBM PC, PC/AT, PC/XT, and compatibles. DSBACKUP+'s features include five-minute backup of a 10-megabyte hard disk, verification of data while backing up or restoring, data compression for up to 40 percent more data on each disk or cartridge, multiple volumes to allow backup and restore from more than one drive at a time, and the ability to back up only those files that have been changed since the last backup. DSRECOVER's features include undeletes in one step, views of all deleted files, and the ability to reconstruct original formatting when a hard disk is reformatted. DSBACKUP+ is priced at \$79.95, and DSRECOVER is priced at \$49.95. Reader Service No. 19.

Design Software
1275 W. Roosevelt Rd.
West Chicago, IL 60185
(800) 231-3088
In IL, HI, AK (312) 231-4540

SunDog Software Corp. has announced Squish, a 40K resident file-compression program that compresses files on both hard and floppy disks. When the files are used, expansion of data takes place spontaneously in memory rather than on disk, and no advance planning is needed to use the files. All programs that use standard DOS functions for reading and writing can use "squished" files. Squish is also compatible with other resident programs. The program is available for IBM PCs, PC/XTs, PC/ATs,

and compatibles using DOS 2.0 and costs \$79. Reader Service No. 20.
SunDog Software Corp.
264 Court St.
Brooklyn, NY 11231
(718) 855-9141

Fail-Safe from **CSSL** is a fault-tolerant system that allows IBM PCs and compatibles to continue operating even after catastrophic hard-disk failures. It is the first level of a multitiered system that comes in three configurations. The other configurations are DFT (Disk Fault Tolerant), a software and half-card version, and DFT II, a hardware-only version built around firmware and a controller card. Each configuration contains solutions to the most common problems found in personal computer system failures. Fail-Safe requires DOS 2.0 or later and 24K RAM. The single-unit PC version is available for \$395. DFT, which is configured for a network linking up to 15 PCs, is available for \$595. Reader Service No. 21.

CSSL Inc.
909 Electric Ave.
Seal Beach, CA 90740
(213) 493-2471

Rabbit Industries has introduced the MagicDrive, a quick and powerful hard-disk drive for Macintosh computers that have at least 512K RAM. It is available in 20-, 30-, 65-, and 235-megabyte versions and includes such features as automatic error detection and correction, daisy-chaining, automatic head parking, print spooling, password security, and backup utilities. Prices range from \$699 to \$3,399, depending on the version. Reader Service No. 22.

Rabbit Industries
4505 Spicewood Springs Rd., Ste. 304
Austin, TX 78759
(512) 343-0781

Tools

Flash-Up Windows from **The Software Bottling Company** is a memory-resident utility for creating, controlling, and managing menus and help windows for DOS, BASIC, Pascal, C, COBOL, FORTRAN, dBASE, and most other software. It lets programs control windows, allows you to define

Personalize your computing environment.

**The MKS Toolkit now contains
the Korn shell command interpreter.**

The MKS version of Bell Labs' Korn shell has this and more:

- the full power of the UNIX System V.2 Bourne shell
- the most requested features of Berkeley's C shell
- the full-UNIX utility of executable shell files
- command aliases
- interactive command-line facilities
- previous command history and editing
- a powerful programming language
- shell variable expansion
- arithmetic evaluation

All this has been fine-tuned to create the optimum environment under DOS. The Korn shell is just one of over 100 commands — fully compatible with UNIX System V.2 — now contained in the MKS Toolkit, including the following:

| | | | | | | | | |
|-------|---------|-------|------|-------|------|-------|------|-------|
| awk | cat | chmod | cmp | cp | cpio | ctags | cut | date |
| dd | df | diff | du | echo | ed | egrep | ex | fgrep |
| file | find | head | help | join | lc | ls | more | mv |
| nm | od | paste | pg | prof | rm | sed | size | sort |
| split | strings | tail | time | touch | tr | uniq | vi | wc |

and much, much more...

These programs run from the shell or command.com under DOS on machines such as the IBM PC, XT, and AT, the AT&T 6300, and most PC compatibles. Full documentation is included. Phone support is available 9-6 EST. Not copy protected.

Everything for only \$139.

Mortice Kern Systems Inc.

43 Bridgeport Road East, Waterloo, Ontario, Canada N2J 2J4

For information or ordering call collect: **(519) 884-2251**

Prices quoted in U.S. funds. MasterCard and VISA orders accepted. OEM and dealer inquiries invited. UNIX is a trademark of Bell Labs. MS-DOS is a trademark of Microsoft Corp.

Circle no. 249 on reader service card.

SOFTOPIA '87 TOKYO

Leading-Edge Software Technology Exhibition

Period : Tuesday, April 7-Friday April 10, 1987

Japan's Best Software Show :

SOFTOPIA TOKYO is the most Aggressive and international minded software show in Japan and has been annually introducing the most advanced software technology on a world-wide level since 1984, which is sponsored by MITI, the American Embassy and the China Association For Science And Technology. In addition, SOFTOPIA TOKYO assists foreign companies who are planning to enter into Japanese market.

Furthermore, "AI Forum '87" will be held simultaneously.

Through Softopia Tokyo, we are sure you will find plenty of business opportunities in Japan.

■ Major software products displayed

AI, CAI, CMI, DBMS, UNIX, banking, general purpose software products, CAD/CAM/CAE, etc.

■ Late Foreign exhibitors :

IBM, AT&T, Applied Data Research, Analytic Science Technology, Compuware, Stone-house Technology, Allied Electronic Services, Tribune Cable Communications of California, Local Area Telecommunications, Infotel, China Computer Society, etc.

■ INVITATION TO SOFTOPIA '87 TOKYO

- Period : Tuesday, April 7-Friday, April 10, 1987
- Place : Tokyo Trade center(Main Building)

■ For Further Information :

Softopia International Trade Fair Association Secretariat in U.S.A. Cavalier Systems Incorp.
3711 Long Beach Blvd, Suite 709,
Long Beach, California 90712
Phone : 213-492-1157

Circle no. 378 on reader service card.

#1 Lint for MS-DOS

KILLS C BUGS FAST



**The professional
diagnostic facility for C**

PC-lint lets you zap swarms of C bugs and glitches at a time.

Now you can uncover the quirks, inconsistencies, and subtle errors that infest your C programs... waiting to bite you. PC-lint finds them all... or as many as you want... in one pass. Set PC-lint to match your own style.

Outperforms any lint at any price

- Full K&R support and common ANSI enhancements (even MS keywords)
- Finds inconsistencies (especially in function calls across multiple modules!)
- Modifiable library descriptions for 8 popular compilers
- Super fast, one-pass operation
- Suppress any error message
- Zillions of options

PRICE \$139 • MC • VISA • COD

Includes USA shipping and handling. Outside USA, add \$15. In PA add 6%.

**ORDER TODAY,
30-day guarantee**



Runs under MS-DOS 2.0 and up, and AmigaDOS. Uses all available memory.

Trademarks: PC-lint (Gimpel Software), MS, MS-DOS (Microsoft), Amiga (Commodore)

GIMPEL SOFTWARE

3207 Hogarth Lane,
Collegeville, PA 19426

(215) 584-4261



#1 CHOICE IN PROGRAMMABLE EDITORS

VEDIT PLUS has been the #1 choice of professionals since 1980. Our latest release is even better - you can open windows to simultaneously edit several files, access many editing functions with pop-up menus, use keystroke macros to speed editing, and run other programs or DOS commands from within VEDIT PLUS.

Whether your needs are program development, technical writing or word processing, VEDIT PLUS is your answer. With over 40,000 users you can depend on VEDIT PLUS to perform consistently and reliably. It is simple enough to learn for the novice, yet has the speed, flexibility and power to satisfy the most demanding professional.

Compare. No other editor is as powerful - unlimited keystroke macros, instant 'off-the-cuff' command macros utilizing a complete programming language, single command file comparison, special word processing and programming features. No other editor is as easy to use - on-line help, pop-up menus, 75 page tutorial, 380 page manual, and VEDIT PLUS is completely customizable.

Fully supports color windows on IBM CGA & EGA, and even windows on most CRT terminals (including CRT's connected to an IBM PC). Available for IBM PC, TI Professional, Tandy 2000, DEC Rainbow, Wang PC, MS-DOS, CP/M-86 and CP/M-80. Order direct or from your dealer. \$185

"To sum things up, VEDIT PLUS is a small, fast, sophisticated editor with a wealth of features and a good macro language. It offers many rewards for the dedicated programmer."

Computer Language, Chris Wolf, Scott Lewis, Mark Gayman 6/86

"VEDIT PLUS is a wholly remarkable program: blindingly fast, extremely powerful, and highly flexible."

Profiles Magazine, Robert Lavenda 4/86

VEDIT PLUS FEATURES

- Simultaneously edit up to 37 files of unlimited size.
- Split the screen into variable sized windows.
- 'Virtual' disk buffering simplifies editing of large files.
- Memory management supports up to 640K.
- Execute DOS commands or other programs.
- MS-DOS pathname and CP/M user number support.
- Horizontal scrolling - edit long lines.
- Flexible 'cut and paste' with 36 text registers.
- Customization - determine your own keyboard layout, create your own editing functions, support any screen size, any CRT.
- Optimized for IBM PC/XT/AT. Also 132 column & up to 70 lines.

EASY TO USE

- Interactive on-line help is user changeable and expandable.
- On-line integer calculator (also algebraic expressions).
- Single key search and global or selective replace.
- Pop-up menus for easy access to many editing functions.
- Keystroke macros speed editing, 'hot keys' for menu functions.

FOR PROGRAMMERS

- Automatic Indent/Undent for 'C', PL/I or PASCAL.
- Match/check nested parentheses, i.e. '{' and '}' for 'C'.
- Automatic conversion to upper case for assembly language labels, opcodes, operands with comments unchanged.
- Optional 8080 to 8086 source code translator.

FOR WRITERS

- Word Wrap and paragraph formatting at adjustable margins.
- Right margin justification.
- Support foreign, graphic and special characters.
- Convert WordStar and mainframe files.
- Print any portion of file; separate printer margins.

MACRO PROGRAMMING LANGUAGE

- 'If-then-else', looping, testing, branching, user prompts keyboard input, 17 bit algebraic expressions, variables.
- CRT emulation within windows, Forms entry.
- Simplifies complex text processing, formatting, conversions and translations.
- Complete TECO capability.
- Free macros: • Full screen file compare/merge • Sort mailing lists • Print Formatter • Main menu

VEDIT and CompuView are registered trademarks of CompuView Products, Inc. MS-DOS is a registered trademark of Microsoft. CP/M is a registered trademark of Digital Research. WordStar is a registered trademark of MicroPro.

Circle no. 122 on reader service card.

CompuView

1955 Pauline Blvd., Ann Arbor, MI 48103 (313) 996-1299, TELEX 701821

Here's a plug for dBASETM.

ClipperTM NEWS RELEASE

FOR IMMEDIATE RELEASE

For information contact:

 **Nantucket**
Nantucket Corporation®
12555 Jefferson Blvd.
Los Angeles, CA 90066
(213) 390-7923

CLIPPERTM NETWORKS DBASE APPLICATIONS

LOS ANGELES, California... Nantucket's Clipper now lets developers and business persons plug an unlimited number of workstations together to run their dBASE III and dBASE III PLUS applications, using Clipper's new networking capabilities.

This new release compiles programs to run on networks that support DOS 3.1 calls for networking functions, plus single-user programs for DOS 2.0 or greater.

Compiled Applications can be distributed freely, need no runtime module, no licensing fee or royalty. And there is no extra cost per user, regardless of how many users are connected to a Clipper network. Plus the new release now packs even more of Clipper's famous speed, on both single-user and networking applications.

The new Clipper also sports Expanded Memory support, additional functions and improved memo fields. The new release, dubbed Autumn '86, is not copy protected.

Clipper Autumn '86 is available for a suggested retail price of \$695. Registered users of Clipper may upgrade to the new version for \$139.

Clipper and Nantucket are trademarks of Nantucket Corporation.
Other products trademarked by others. Copyright 1986, Nantucket Corporation.

Circle no. 220 on reader service card.

Announcing Magic PC – the first breakthrough for database applications developers in over 20 years: Now you can develop professional applications 1000% faster than your 4GL or DBMS, totally free from programming, commands and syntax!

AKER Corp. MAGIC PC 12/03/86

13. Order Entry Screen

Execution Definition

| Change | Description | Prefix | Main | Suffix |
|--------|-------------|--------|------|--------|
| 1 | Record | -- | 42 | 8 |
| 2 | Task | -- | 2 | 1 |

Operations

| | |
|----|-------------|
| 0 | Remark |
| 1 | Set Field |
| 2 | Stop |
| 3 | Begin Link |
| 4 | End Link |
| 5 | Begin Block |
| 6 | End Block |
| 7 | Exec. Task |
| 8 | Exec. Prog |
| 9 | Upd. Field |
| 10 | Write File |
| 11 | Read File |
| 12 | Scan File |
| 13 | User Exit |

| Op | Operation | Type | No. | Description | Assign | Imp | Exp | F |
|----|-----------|-------------|-------|-------------|-------------------|--------|-----|---|
| 30 | 3 | Req. Link > | File> | 2 | Customers | Key> | 1 | |
| 31 | 1 | Set. Field> | R | 2 | Customer Name | | 0 | 0 |
| 32 | 1 | Set. Field> | R | 4 | Customer Discount | | 0 | 0 |
| 33 | 4 | End Link > | | | | | | |
| 34 | 0 | | | | | | | |
| 35 | 8 | Exec. Prog> | No.> | 18 | Item List | Parms> | 2 | |
| 36 | 0 | | | | | | | |
| 37 | 9 | Upd. Field> | No.> | 8 | Customer Discount | Exp> | 3 | |
| 38 | 0 | | | | | | | |
| 39 | 7 | Exec. Task> | No.> | 1 | Order Lines | Parms> | 0 | |

1>Opt 2>Undo 3>Del 4>Add 5>Zoom 6>Expr 7>Draw 8>Task 9>End 10>Help

A Magic PC program looks as simple as this. To design an application you quickly fill-in menu-driven decision tables **without having to write a single line of code**. For example, just by highlighting the Execute Program operation on this screen and also highlighting the Item List program in the Program Menu, you tell Magic PC to pop-up the Item List window shown in the adjacent screen, when the end-user hits the Zoom key.

Order Entry

Order No: 999 Order Date: 99/99/99 Customer No: 99999 Address: AAAAAAAAAAAAAAAAAAAAAA AAAAAAAAAAAAAAAAAAAAAA

| Line | Item | Type | Description | Quantity | Unit Price | Total Price |
|------|-------|------|-----------------------|----------|------------|-------------|
| 999 | 99999 | A | AAAAAAAAAAAAAAAAAAAAA | 9.999 | 999.999 99 | 999.999 99 |

Item List

| No. | Description | Type | Price |
|-----|-----------------------|------|---------|
| 999 | AAAAAAAAAAAAAAAAAAAAA | A | 999.999 |

Stock Status

In Stock: -999.999
Total Orders: -999.999
Avail to Sell: -999.999

| | | |
|--------|-------------|-------------|
| 99.99t | Order Sum | -999.999.99 |
| | Discount | -999.999.99 |
| 99.99t | Sub-Total | -999.999.99 |
| | Sales Tax | -999.999.99 |
| | Order Total | -999.999.99 |

1>Opt 2>Undo 3>Del 4>Add 5>Zoom 6>Expr 7>Draw 8>Task 9>End 10>Help

Magic PC gives your end-user the power to harness and retrieve data instantly, **without any commands or syntax** because at runtime you already have built-in options to Add, Delete, Modify, Query and get on-the-spot ad-hoc information simply by highlighting selections from menus. Data validation, security and error-checking are done automatically for you by Magic PC without programming.

Who needs another DBMS?

At last, Magic PC gives you the ultimate applications design tool, far ahead of 4GLs, DBMS and Application Generators.

Magic PC breaks through the language barrier with the revolutionary Un-Language concept:

NO PROGRAMMING, COMMANDS OR SYNTAX!

Free yourself from your programming language

Magic PC makes you, the professional, completely free from the drudgery of procedural programming. No more cryptic commands, syntax or unforgiving procedural structures, because Magic PC does all the programming automatically. There's your competitive edge. The rest is up to you...

The Professional Choice

Already an international success, Magic PC is a profit maker and career booster for DP Consultants, System Integrators, VARs, MIS professionals, System Analysts, Programmer Analysts and Software Engineers. If you design PC applications professionally, you can't afford not to Un-Language now.

IBM France: "IBM encourages this introduction and can not help but salute such evolution..."

Israeli Air Force: "We were convinced that it was not possible to have a design tool powerful enough to implement real-life applications without a programming language. Magic PC changed our mind..."

Jeff Duntemann, PC Tech Journal: "It's probably the best integrated database applications and screen generator that I have ever seen...very smooth system, and smoothness comes at a premium these days..."

The Magic PC Secret

You're so much more productive with Magic PC because there is **absolutely no programming** to slow you down. You design a Magic PC application by simply filling-in the **Data Dictionary Tables** (Files, Fields, Keys) and the **Task Description Tables** (Operations and Expressions).

Only 13 design **Operations** harness the power of Magic PC. Operations are specific enough to eliminate the need for tiresome syntax, yet elastic enough to produce robust custom applications. Use the Operations to describe **what you want** and Magic PC makes it happen. It's that simple.

Make Task nesting power available with a single **Execute Task Operation**. This powerful instruction triggers Magic PC to execute and display additional tasks or even external applications through **Window Zooms**. The 3-dimensional effect of Window Zooming lets you probe deep into your application through nested windows and manipulate the data underneath.


You describe a Magic PC Task or Program (composite Tasks) by filling your system analysis flow into the Task Description Tables. Choose the participating Data View, and Magic PC executes your desired Operations. You interface with the Tables by highlighting your selections from pop-up menu-driven windows. There's nothing to edit except your headings.

You're not confined to any particular design sequence as you are with most procedural languages. You can enter and change any Table spontaneously, on the fly, as ideas come to mind and Magic PC automatically maintains the application integrity.

A **Magic Inference Engine** automatically orchestrates your Task Description Tables into a single file of internal **Knowledge Base Rules** for optimum, bug-free performance. Knowledge Base Rules are executed by the **Magic Run** engine for stand-alone runtime operation, or by the **Magic Lan** engine for unrestricted Novell network sharing. You're free to design the Knowledge Base without worrying about the internal structure.

Discover fast,
language-free
programming
at no risk
for only \$

19.95



See for yourself how fast you can program language-free applications with our low-cost limited offer.

You'll get the full Magic PC software unprotected and limited to 100 records and 450 page documentation complete with a **free Order Entry** sample application. You'll also get our **free** telephone support for 90 days!

And your \$19.95 will be credited towards the full \$695 Magic PC purchase price. Even if you don't buy Magic PC right away, keep your \$19.95 Magic PC Trial as your application prototyping tool at this bargain price.

Our No-Risk Guarantee!

You have our no-risk 30-day money-back guarantee: if you're not completely satisfied for any reason, even Magic PC Trial for \$19.95, send it back for a refund.

Order now while supply lasts

Call this toll free number now with your Visa, MasterCard or American Express for immediate delivery, or send the Order Coupon below today to Aker.

1-800-345-MAGIC
in CA call 714-250-1718



Yes, please rush me:

- ☐ Magic PC Trial \$ 19.95
☐ Magic PC \$695.00
Add shipping \$ 5.00
In CA 6% tax \$

Prices valid in US only. Total \$

Ship to: _____
Address: _____
City/ST/Zip: _____
Phone: _____

AKER

Aker Corp. 18007 Skypark Circle B2, Irvine, CA 92714
(714) 250-1718, Elec. Mail Dialcom 41:AKR 001 Telex 4931184
AKR UI OEM and VAR inquiries are welcome.

Min. requirements PC DOS 2.0, IBM PC or 100% compatible with 512K and hard disk.
©1986 Aker Corp. Printed 1/87 Trademarks: Magic PC, Un-Language, Window Zoom, Magic Run, Magic LAN and Magic PC Trial are trademarks of Aker Corp. IBM PC and PC-DOS are trademarks of IBM Corp., Novell is a trademark of Novell Inc.

We Do Windows!



WARNING: This product may promote large incomes, high productivity, and excessive free time.

Magus, Inc. is proud to present Data&Windows: a window-oriented data-entry system based on a new, revolutionary design philosophy. The only problem is ... what should we call it?

It is easy to learn and use, like a **panel generator**, because it allows you to draw your text, fields, and colors on the video display. But we can't call it a panel generator, because it supports full windowing and scrolling, and because screen and field information may be stored in your program files (.EXE) rather than separate data files.

It is flexible and powerful, like a **library-oriented programmer's toolkit**, but you are not restricted to "visualizing" your data-entry windows as you type page after page of code to set up borders, fields, text and highlighting. Our innovative approach (called **static windowing**) eliminates the need for replication of static data in dynamic memory.

It produces tight code, like a **YACC** (Yet Another Compiler Compiler), but you don't have to tolerate a myriad of small program modules that need to be compiled and maintained. Instead, our "screen designer" creates Microsoft object files which you simply link with your applications.

Add to this new, superior design philosophy the fact that it has more features, produces tighter code, and yields higher performance than any of the above. Throw in a clear, concise user manual, a thorough on-disk tutorial, and some example programs. Top it off with a utility program that documents each screen and another that allows you to prototype (or simulate) your application before you write a single line of code. Now, what would you call it?

Let's settle on a single word.
Let's call it the "best."

But don't take our word for it. Order your demo disk today. You will receive a copy of the screen generator, the tutorial, and some documentation on the utility programs and library routines. Then make the decision yourself.

Or take advantage of our one-time introductory offer and get \$100 discount if you order before March 31, 1987.

Call (713) 665-4109 for more information. Major credit cards accepted.

SCREEN DESIGNER:

Move/delete/center/fill/highlight block, global field redefinition, move/resize window and buffer, add/modify/delete field, insert/delete/undelete line, test/save/abort window, graphics characters, paint, jump-to-field, many cursor movement options, monitor switching, operating system calls, help. Set validation mode, highlight current field, scrolling by line or page, input mask, tabs, initial values. More. Up to 400 lines per screen.

FIELD DEFINITION:

Left-justify/right-justify/center, uppercase translation, built-in character validation, byte/integer/word/long/float/double/string/date field validation, retain data, auto-erase, protected fields, input required, use commas, use zeros/spaces, margin bell. User-defined character validations, pattern-matching validations, picture validations, and field types. More. Up to 9999 fields per screen.

LIBRARY ROUTINES:

Open, close, move, display, and refresh windows. Allow user to edit data fields in window, or to view and manipulate a window but not change data stored in it. Pull-down and pop-up menus. Read screen object file from disk. Intercept keyboard filter. Override default key actions. Automatic and manual refresh. Switch display device, erase all data fields on window, plot data onto fields or entire screens, retrieve data from fields or entire screens, screen image dump, retrieve and modify screen and field attributes, locate field, force use of bios. Direct interfacing with some bios interrupts, including cursor and mouse control. More. Mnemonic and simple to use.

REQUIREMENTS:

IBM PC/XT/AT/JR or true compatible, DOS 2.0 or later, at least 128K free RAM, and the Microsoft C, Pascal, or Fortran compiler or the IBM C compiler. Support is available for other C Compilers and the XENIX operating system. Call for specifics.

IBM, IBM PC, IBM XT, and IBM AT are trademarks of International Business Machines. Microsoft and XENIX are trademarks of Microsoft Corporation.

Circle no. 336 on reader service card.

For More Information

(713) 665-4109

Data&Windows

Magus Inc.

Screen Designer

Let's Do Windows!

☐ C ☐ Pascal ☐ FORTRAN
☐ Please send ___ copies @ \$345.00
Introductory discount -100.00
Your price 245.00

☐ Data&Windows with Library
 Source Code \$695.00
Introductory discount -100.00
Your price 595.00

Hurry! Introductory offer expires March 31, 1987.

Show Me More!

☐ Send me a Demo \$10.00

In Texas add 6.125% sales tax _____
 Outside U.S. add 15.00 _____
Total enclosed \$ _____

Enclosed is

☐ Check ☐ Money Order
☐ Visa ☐ MasterCard
 Number _____
 Expiration Date _____

Name _____
 Company _____
 Address _____
 City _____
 State _____ Zip Code _____

Send to:

MAGUS, INC.
 4545 Bissonet Suite #114
 Bellaire, TX 77401

PC/VI™

UNIX's VI Editor Now Available For Your PC!

Are you being as productive as you can be with your computer? An editor should be a tool, not an obstacle to getting the job done. Increase your productivity today by choosing **PC/VI** — a COMPLETE implementation of UNIX® VI version 3.9 (as provided with System V Release 2).

PC/VI is an implementation of the most powerful and most widely used full-screen editor available under the UNIX operating system. The following is only a hint of the power behind **PC/VI**:

- Global search or search and replace using regular expressions
- Full undo capability
- Deletions, changes and cursor positioning on character, word, line, sentence, paragraph, section or global basis
- Editing of files larger than available memory
- Shell escapes to DOS
- Copying and moving text
- Macros and Word abbreviations
- Auto-indent and Showmatch
- MUCH, MUCH MORE!

Don't take it from us. Here's what some of our customers say: "Just what I was looking for!", "It's great!", "Just like the real VI!", "The documentation is so good I have already learned things about VI that I never knew before." — *IEEE Software*, September 1986.

PC/VI is available for IBM-PC's and generic MS-DOS+ systems for only \$149. Included are CTAGS and SPLIT utilities, TERMCAP function library, and an IBM-PC specific version which enhances performance by as much as TEN FOLD!

PC/TOOLS™

What makes UNIX so powerful? Sleek, Fast, and **POWERFUL** utilities! UNIX gives the user not dozens, but hundreds of tools. These tools were designed and have been continually enhanced over the last fifteen years! Now the most powerful and popular of these are available for your PC! Each is a complete implementation of the UNIX program. Open up our toolbox and find:

- | | | | | |
|----------|---------|---------|--------|-----------|
| • BANNER | • DIFF | • HEAD | • SED | • STRINGS |
| • BFS | • DIFFH | • OD | • SEE | • TAIL |
| • CAL | • DIFF3 | • PASTE | • SORT | • WC |
| • CUT | • GREP | • PR | | |

All of these for only \$49.00; naturally, extensive documentation is included!

PC/SPELL™

Why settle for a spelling checker which can only compare words against its limited dictionary database when **PC/SPELL** is now available? **PC/SPELL** is a complete implementation of the UNIX spelling checker, renowned for its understanding of the rules of English! **PC/SPELL** determines if a word is correctly spelled by not only checking its database, but also by testing such transformations as pluralization and the addition and deletion of prefixes and suffixes. For only \$49.00, **PC/SPELL** is the first and last spelling checker you will ever need!

Buy **PC/VI** and **PC/TOOLS** now and get **PC/SPELL** for only \$1.00! Site licenses are available. Dealer inquiries invited. MA residents add 5% sales tax. AMEX, MC and Visa accepted without surcharge. Thirty day money back guarantee if not satisfied! Available in 8", 5¼" and 3½" disk formats. For more information call today!

*UNIX is a trademark of AT&T. MS-DOS is a trademark of Microsoft.

CUSTOM SOFTWARE SYSTEMS

P.O. BOX 678 • NATICK, MA 01760
617 • 653 • 2555



Circle no. 268 on reader service card.

OF INTEREST

(continued from page 142)

windows, assigns windows to keys, and acts as a window macro enhancer by letting you send commands to running programs. Flash-Up Windows sells for \$90. Reader Service No. 23.

The Software Bottling Company
6600 Long Island Expwy.
Maspeth, NY 11378
(718) 458-3700

A general-purpose set of development tools and C function libraries called Real-Tools is available from **Pioneering Controls Technologies**. Real-Tools comprises a screen-management system, windowing capabilities, user-defined graphics, and assorted utilities and library functions. It is priced at \$99 for binary, \$299 for library source, and \$399 for complete source. Reader Service No. 24.

Pioneering Controls Technologies Inc.
510 Bering Dr., Ste. 300
Houston, TX 77057
(713) 266-8649

Csharp PC Drivers Package is a library of C language support routines for data acquisition and control hardware on the IBM PC, PC/AT, and compatibles from **Systems Guild**. It includes support for the Metrabyte Dash8 and Dash16 analog I/O boards, the Data Translation DT2801 and DT2808 analog I/O output boards, and the IBM PC DMA controller. Csharp PC Drivers Package can be used with the following C compilers: Microsoft 3.0 and 4.0, Lattice 2.15 and 3.10, and C86 from Computer Innovations. A special version of the product is available for use with Rational Systems' Instant-C incremental compiler. A source license for the Csharp PC Drivers Package costs \$195. Reader Service No. 25.

Systems Guild
P.O. Box 1085
Kendall Square Station
Cambridge, MA 02142
(617) 451-8479

O88 is an optimizer compatible with the C Ware Corp.'s DeSmet C88 compiler. The product, introduced by **Key Software Products**, can run stand-alone or installed as an automatic part of the compilation pro-

cess. In minimal 8088 mode, O88 typically eliminates 4–13 percent of the instructions and simplifies 7–12 percent of those that remain. IBM PC/AT or compatible users can use 80188 mode to eliminate another 5–9 percent of the instructions. Programs that make heavy use of an 8087 or 80287 floating-point chip can use 8087 mode to achieve significant performance improvements. O88 is available for \$49. Reader Service No. 26.

Key Software Products
440 Ninth Ave.
Menlo Park, CA 94025
(415) 364-9847

Six new programming toolkits for use with Kyan Pascal are available from **Kyan Software**. The toolkits save programmers time and help them add state-of-the-art graphics and other features to their Kyan Pascal programs. The toolkits run on Apple IIs with Kyan Pascal and are priced from \$29.95 to \$149.95. Reader

Service No. 27.
Kyan Software
1850 Union St., #183
San Francisco, CA 94123
(415) 626-2080

Greenleaf Software has released DataWindows, a windows and data entry library for C language programmers. DataWindows' features include overlaid windows with screen management, transaction-oriented data entry, and more than 135 functions. Portions of the program's object code can be used in other programs without royalty obligations. DataWindows sells for \$225, and the source code is available for an additional \$225. Reader Service No. 28.

Greenleaf Software
1411 LeMay Dr., Ste. 101
Carrollton, TX 75007
(214) 631-0811

Cytek has released three new packages to enhance its Multi-C multitask-

ing library. Multi-Comm is a full-featured communications library that supports high-speed, interrupt-driven data transfers, multiple device types in asynchronous or synchronous mode, and background communications by Multi-C tasks. Multi-Windows is a window development package for creating pop-up windows. Multi-Forms works with Multi-Windows to produce data entry and display screens. Source code is supplied for all hardware-dependent functions, allowing them to be used with any compiler-supported computer, including MS-DOS and ROM-based systems. Multi-Comm and Multi-Forms are priced at \$149 each, and Multi-Windows sells for \$295. Reader Service No. 29.

Cytek Inc.
805 Turnpike St., Unit 202
North Andover, MA 01845
(617) 687-8086

The C 386 Compiler and RLL 386 Relo-

Two great reasons to buy Turbo Pascal: System Builder \$99⁹⁵ and Report Builder \$75⁰⁰

From the Designer Series™ by Royal American Technologies.

State-Of-The-Art Program Generators that automatically build a **Relational Database system** without coding. Entry level "coders" can produce Database systems without coding. Developers have more flexibility and horsepower than any development tool on the market.

Self-documenting program includes screen schematics. System Builder will generate 2,000 lines of program code in approximately 6 seconds.



SYSTEM BUILDER FEATURES:

- Automatically generates Indented, Structured, Copy Book Source Code ready for compiling with Turbo Pascal (no programming needed)
- Paint Application and Menu screens using Keyboard
- Screens all use In-Line machine code for exceptional speed
- 16 Datafiles and 16 Index Keys per application
- Paint functions include: — Cut and paste blocks of text screen to screen — Draw and erase boxes — Access special graphic characters and character fill — Go straight from screen to screen — Define colors and intensities
- Support an unlimited number of memory variables
- File Recovery Program
- Automatically modify existing datafiles
- Experienced developers can modify the System Builder
- Develop systems for Floppy or Hard Disk
- Modify System Builder's output source code to include External Procedures, Functions and Inline Code
- Easy-to-use Interface Program included to access ASCII and Dbase Files

REPORT BUILDER FEATURES:

- Automatically generates Indented, Structured Source Code ready for compiling Turbo Pascal (no programming needed)
- Automatically inter-

"I think it's wonderful... prospective buyers should seriously consider DESIGNER even before dBASE III."

Mr. Greg Weale
Corporate Accounts Manager,
Computerland

"We used DESIGNER last year to program a major application. It saved our programmers so much time. We now use DESIGNER instead of dBASE III as our development standard!"

Mr. Peter Barge, Director
Services Division, Horwath & Horwath

faces to a maximum of 16 Datafiles created with System Builder

- Supports Global Parameters such as Headings, Footers, Lines Per Page, Print Size and Ad Hoc Sorting
- Page breaks on Sub-Totals
- Reports can also include Text Strings, Variables or Computed expressions containing references from up to 16 Datafiles
- Use range input screens allow End Users to select portions of a report as needed (i.e. specific account ranges can be requested)
- Easy-to-use Interface Program included to access dBase Files

SYSTEM BUILDER PERFORMANCE

(Typical 10 screen 8 file/index application)

| TASK | SYSTEM BUILDER | DBASE III™ |
|----------------------------------|-----------------------|------------|
| Planning and Design | 60 minutes | 60 minutes |
| Screen Painting | 15 minutes | 3 hours |
| Programming | 2 minutes | 10 hours |
| Elapsed time to completed system | 1 hour and 17 minutes | 14 hours |

VARS, System Integrators and Dealers, let's work together. Head office: (415)397-7500

Royal American Technologies
201 Sansome, Suite 202
San Francisco, CA 94104

(800) 654-7766

in California (800) 851-2555

Ask for Operator 102.

Please rush me: ____ copies of SYSTEM BUILDER at \$99.95 per copy; ____ copies of REPORT BUILDER at \$75.00 per copy. I've enclosed \$5.00 for postage and handling. California residents add 6% sales tax.

Name _____

Address _____

City _____

State _____ Zip _____

Phone _____

Payment: ☐ Check ☐ Money Order ☐ Cashiers Check ☐ AMEX ☐ VISA ☐ MASTERCARD

Expiration date _____

Card Number _____

Signature _____

30-Day Money-Back Guarantee. Not copy-protected. \$10 restocking fee if envelope is opened. System Requirements: IBM PC/XT/AT*, or similar, with minimum 256K RAM, dual floppy drives, or hard disk, color or monochrome monitor, MS* or PC DOS* version 2.0 or later, Turbo Pascal Version 2.0 or later (Normal, BCD or 8087 versions).

*Trademark of International Business Machines Corp.

*Trademark of Microsoft Corp.

*Turbo Pascal is a registered trademark of Borland International.

*dBASE is a registered trademark of Ashton-Tate.

ROYAL AMERICAN
Technologies Corporation™

Circle no. 312 on reader service card.

OF INTEREST

(continued from page 149)

cation, Linkage and Library Tools package from **Intel Corp.** are designed to help speed development of both embedded and on-target 80386 application software. Both packages support all the 80386's features, capabilities, and operating modes. The compiler produces object code that is compatible with Intel's other 80386 languages. The RLL 386 tools package allows programmers to design protected multiuser and multitasking operating systems. The C 386 Compil-

er and RLL 386 package sell for \$900 and \$600, respectively. Reader Service No. 30.

Intel Corp.

Literature Dept. W338

3065 Bowers Ave.

Santa Clara, CA 95051

(408) 987-8080

Graphics

Microfield Graphics has introduced T8, a single-board graphics system for the IBM PC/AT, RT/PC, and desktop

computers based on the Intel 80386. Based on a dual-processor architecture with 64-bit internal memory interface, the T8 is designed to meet the graphics requirements of high-end CAD/CAM, CAE, and mapping applications. Prices vary according to configuration. Reader Service No. 31.

Microfield Graphics Inc.

8285 S.W. Nimbus Ave., Ste. 161

Beaverton, OR 97005

(503) 626-9393

NSI Logic has introduced a half-size, enhanced graphics adapter called SMART (Single Monitor Adapter Technology) EGA. The adapter is compatible with any IBM PC software and operates in all the popular display modes on any standard EGA color monitor. It costs \$549. Reader Service No. 32.

NSI Logic Inc.

Cedar Hill Business Park

257-B Cedar Hill Rd.

Marlboro, MA 01752

(617) 460-0717

Editor

UniPress Software has released a Unix-oriented text editor called vi-PLUS that has some features not found in standard vi, such as multiple windows, an interactive interface to Unix, and extensibility through macros. It is available for many computer systems running Unix, Xenix, Ultrix, and other Unix derivatives. The PC version sells for \$645. Reader Service No. 33.

UniPress has also released C-macs, a program editor for C programmers that is built on top of the company's Emacs editor. C-macs checks and balances parentheses and braces and permits programmers to define an indenting style. The editor can run make while an edit session is underway and maintains "tags" of all system components. The PC version of C-macs costs \$645. Reader Service No. 34.

UniPress Software Inc.

2025 Lincoln Hwy.

Edison, NJ 08817

(201) 985-8000

DDJ

WIZARD systems


"the best
compiler
today"

Dr. Dobb's

Aug. 86

has
moved
to

alifornia



(408) 224-6015

Only \$450



Circle no. 116 on reader service card.

WIZARD
SYSTEMS SOFTWARE, INC.

17645 Via Sereno
Monte Sereno, CA 95030

ADVERTISER INDEX

| Reader Service No. | Advertiser | Page No. | Reader Service No. | Advertiser | Page No. |
|--------------------|---------------------------------------|----------|--------------------|--|----------|
| 369 | Aker Corporation | 146 | 300 | Micro Way | 106 |
| 350 | Aldebaran Laboratories | 43 | 286 | Microcompatibles | 41 |
| 321 | Alpha Computer Service | 48 | 215 | MicroHelp, Inc. | 82 |
| 250 | Austin Code Works | 60 | * | Micromint | 54 |
| 115 | Barrington Systems, Inc. | C-2 | 154 | Microport Systems, Inc. | 19 |
| 383 | Baysoft | 93 | 105 | Microprocessors Unlimited | 64 |
| 182 | BC Associates | 130 | 380 | Microsoft | 70-71 |
| 159 | Blaise Computing | 2 | 249 | Mortice Kern Systems, Inc. | 143 |
| 217 | Blaise Computing | 78 | 309 | Nanosoft Associates | 53 |
| 263 | Block Island Tech | 60 | 220 | Nantucket Corporation | 145 |
| 161 | Borland International | C-4 | 331 | Nirvonic | 41 |
| 212 | Burton Systems Software | 91 | * | NR:A Nroff-like Text Processor for MSdos | 151 |
| 235 | C Software Toolset | 62 | 342 | Oakland Group, Inc. | 87 |
| 181 | C Users Group | 90 | 254 | Oasys | 37 |
| 307 | Cauzin Systems | 50-51 | * | On Command | 67 |
| 378 | Cavalier Systems | 143 | 214 | Periscope Co. Inc. | 99 |
| 370 | Code Blue | 32-33 | 343 | Pharlap | 40 |
| 122 | Compu View | 144 | 283 | Polytron Corporation | 124 |
| 237 | CompuServe | 4 | 229 | Port - A - Soft | 91 |
| 382 | Conversational Computer Systems | 64 | 129 | Programmer's Connection | 75 |
| 348 | Creative Computer Software | 61 | 129 | Programmer's Connection | 76-77 |
| * | Creative Programming | 123 | 334 | Programmer's Paradise | 52 |
| 379 | Crescent Software | 65 | 133 | Programmer's Shop (The) | 46-47 |
| 268 | Custom Software Systems | 148 | 301-304 | Programmer's Shop (The) | 125 |
| 203 | Datalight | 9 | 144 | Quantum Computing | 62 |
| 258 | Desktop A.I. | 61 | 377 | Quelo | 91 |
| 127 | Digitalk | 83 | 206 | Raima Corporation | 103 |
| * | Dr Dobb's Toolbook Shelf | 119 | 145 | Rational Systems | 140 |
| * | Dr Dobb's Bound Volumes | 122 | 312 | Royal American Technologies | 149 |
| * | Dr Dobb's Subscriptions | 36 | 365 | RR Software Inc. | 81 |
| 89 | Ecosoft, Inc. | 97 | * | SAS Institute | 111 |
| 138 | Essential Software | 13 | 168 | Sapiens Software | 84 |
| 139 | Essential Software | 15 | 210 | Scientific Endeavors | 45 |
| 371 | Exim | 59 | 114 | Seidl Computer Engineering | 85 |
| 93 | Fair-Com | 133 | 85 | Semi-Disk Systems | 115 |
| 340 | Farbware | 74 | 78 | SLR Systems | 45 |
| * | Financial Freedom Publishers | 135 | 349 | SofCap Inc. | 72 |
| 362 | Galaticomm | 57 | 40 | Softcraft Inc. | 5 |
| 373 | Genesis Data Systems | 74 | 259 | Softfocus | 40 |
| * | Gimpel Software | 143 | 361 | Software Factory (The) | 118 |
| 291 | Gold Hill Computers, Inc. | 1 | 314 | Software Garden Inc. | 55 |
| 97 | Greenleaf Software | 31 | 347 | Software Masters | 88 |
| 351 | Guidelines Software | 67 | 170 | Software Security | 29 |
| 132 | Harvard Softworks | 92 | 372 | SoftWay | 59 |
| 280 | Hersey Micro Consulting | 89 | 142 | Solution Systems | 131 |
| 376 | Hi-Tech Software | 72 | 148 | Solution Systems | 127 |
| 327 | Integral Quality, Inc. | 25 | 152 | Solution Systems | 102 |
| 179 | Intel Corporation | 38-39 | 381 | Spencer Organization | 134 |
| 355 | Jou Laboratories | 94 | 228 | Spencer Organization | 79 |
| 294 | Kurtzberg Computer Systems | 86 | 363 | Summit Software Technology, Inc. | 107 |
| 101 | Lattice, Inc. | 113 | 374 | Sun Dog Software | 67 |
| 118 | Lifboat | 69 | 345 | T.O.C Business Solutions | 90 |
| 366 | Logicware | 114 | 204 | Team Austin, Inc. | 22 |
| 257 | Logitech, Inc. | C3 | * | TeleOperating Systems | 14 |
| 135 | Lugaru | 134 | 175 | Tom Rettig Association | 129 |
| * | M&T Catalog of Books & Software Tools | PB | 230 | The Software Family | 80 |
| 313 | Magma Systems | 56 | 207 | Turbo Power Software | 23 |
| 336 | Magus Inc. | 147 | 119 | Turbo Report | 49 |
| 108 | Manx Software Systems | 7 | 332 | Unify Corporation | 73 |
| 317 | Marshal Language Systems | 139 | 316 | Upland Software | 95 |
| 285 | MDS, Inc. | 129 | 157 | Vermont Creative Software | 21 |
| 375 | MEF Environmental | 44 | 112 | Wendin | 11 |
| 352 | Megamax | 65 | 116 | Wizard Systems Software, Inc. | 150 |
| 358 | MetaComCo | 62 | 244 | Workman & Associates | 137 |
| 95 | MetaWare Incorporated | 44 | 225 | Xenosoft | 90 |

*This advertiser prefers to be contacted directly: see ad for phone number.

ADVERTISING SALES OFFICES

Midwest

(317) 875-8093

Southeast

Gary George (404) 897-1923

Northeast

Cynthia Zuck (718) 499-9333

Northern California/Northwest

Lisa Boudreau (415) 366-3600

Southern California/AZ/NM/TX

Michael Wiener (415) 366-3600

Advertising Director

Robert Horton (415) 366-3600

Announcing Nr: An Nroff-like Text Formatter for MS-DOS

Nr is an expanded version of the text formatter described in *Dr. Dobb's* February through April 1987 issues. Nr is written in C and is compatible with the Unix Nroff. You'll find complete implementation of the -ms macro package, and an in-depth description of how -ms works.

Nr does hyphenation and simple proportional spacing. It supports automatic Table of Contents and Index generation, automatic footnotes and endnotes, italics, boldface, overstriking, understriking, and left and right margin adjustment.

Nr also contains:

- extensive macro & string capability
- number registers in various formats including roman numerals and arabic, spelled out and in outline form
- diversions and diversion traps
- input and output line traps

Nr comes configured for any Diablo-compatible printer, and Hewlett Packard's ThinkJet and LaserJet. It is easily configurable for most other printers and comes with full source code so that you can make it work with your system. For PC compatibles.

Item #165

\$29.95

TO ORDER: Return this order form with your payment to: M&T Books, 501 Galveston Dr., Redwood City, CA 94063. Or, call TOLL-FREE 800-533-4372 Mon-Fri 8AM-5PM (In CA call 800-356-2002)

YES! Please send me _____ copies

of Nr at \$ _____ each

Subtotal _____

CA residents add sales tax _____ %

Add \$2.25 per item for shipping _____

TOTAL _____

Name _____

Address _____

City _____

State _____ Zip _____

☐ Check enclosed. Make payable to M&T Publishing.
Please Charge my ☐ VISA ☐ M/C ☐ Amer. Exp.

Card No. _____

Exp. Date _____

Signature _____


3125E

SWAINE'S FLAMES

A computer system that encapsulates the knowledge of experts (including heuristic decision processes) for retrieval by the inexpert but naturally intelligent is called an expert system. There are many expert systems in existence throughout the world today. When a British health association recently recommended that each health district in Great Britain avail itself of a (presumably human) expert on AIDS, it discovered that there were fewer AIDS experts than health districts in Britain. Enter the AIDS expert system.

At Warwick University in Great Britain, a team of computer scientists under the direction of Dr. Roger Brittain is scanning more than 100 articles a month on AIDS, building a knowledge base that will help doctors counsel AIDS patients and serve as a research and diagnostic tool. The project builds on a prototype system for rabies patients and is expected to cost some £20,000 and result in a piece of software that can run on a mainframe or microcomputer.

Despite some recent press grumblings about expert systems technology not being the miracle the same press had made it out to be, expert systems are useful tools in just such situations as AIDS diagnosis—in fact, many of the fundamental expert systems techniques were developed in a medical diagnostic framework called MYCIN. (We have received and expect to publish next month a MYCIN-like expert system.) The Warwick project sounds practical and may actually make a contribution to putting the brakes on the AIDS epidemic. That's great, and because I try to maintain a positive mental attitude in this column, I won't suggest that the three major American television networks are making a counterbalancing contribution to the spread of the disease with their refusal to carry condom advertising.



I learned about the AIDS expert system in a news item in the Christmas 1986 issue of a British weekly called *New Scientist*. This periodical is worth the time of any scientifically curious and naturally intelligent person on either side of the Atlantic. Erstwhile *DDJ* resident intern Dave Cortesi and I have shared a deep fondness for *New Scientist* for years (something like our fondness for Jon Bentley's Programming Pearls column in *IEEE Software* and our respect for at least the intentions of the best science fiction, this last being what Dave is currently writing). *New Scientist's* snipes at the British government are often (to me) funny and its humor is largely (to me) incomprehensible, but everything else is gold. There is more to think about in six weeks of *New Scientist* than in twelve months of *Scientific American*.

A videophone system for the deaf that handles the bandwidth problem by abstracting essential expressive and gestural cues into an animated cartoon of the caller is something I've followed off and on for years; the latest word on this University of Essex project appeared in the October 23 issue of *New Scientist*. The November 27 issue talked about progress toward standardization on a Unix application interface, which could be the biggest boost for Unix since Bell Labs gave it to the universities. The December 18 issue had brief items on Texas Instruments' trenching technology for 3-D 4-megabit memory chips and on European research into sixth generation computers (see also

"Sixth Generation Computers" by Richard Grigonis in the May 1984 *DDJ*). It's a good magazine.

January brought one of the most enjoyable of the computer trade shows: Macworld Expo. The atmosphere this year was particularly charged, and there were products and announcements significant enough to support the electricity.

Steve Jasik showed off his debugger MacNosy Part Two: The Debugger. His slogan: Beyond Discipline and Into Bondage. The Interface Builder from Expertelligence looked interesting: it lets you put a Mac interface on LISP programs. The Developers' Toolkit panel, with moderator Scott Knaster (manager of the Developer Technical Support Group at Apple), MicroPhone author Dennis Brothers, Jim Friedlander of Apple, and David Intersimoni of Borland, talked encouragingly about MacApp and APDA, the Apple Programmer's and Developer's Association.

One East Coast writer out for the Expo was sometime *Rolling Stone* writer Steven Levy, who some think was the model for the John Travolta character in the less-than-perfect movie *Perfect*. Levy definitely was one of the founders of the Lunch Bunch, a group of technology writers who ate hamburgers together on two coasts. The Lunch Bunch has served up at least one book and has now spun off a dinner group gourmandizing in Silicon Valley under the label Nerd's Night Out. January's menu called for a discussion of Apple's new machines, but the most knowledgeable sources decided that they couldn't talk about that and canceled. How Apple has changed.


Michael Swaine

Michael Swaine
editor-in-chief

WHY LOGITECH MODULA-2 IS MORE POWERFUL THAN PASCAL OR C.

"A clear winner... The integrated editor is
a joy to use."
BYTE Magazine,
Jan. '87

APPRENTICE PACKAGE \$99



WIZARDS' PACKAGE \$199

- Separate Compilation
w/inter-module typechecking
- Native Code Generation
- Large Memory Model Support
- Most Powerful Runtime Debugger
- Comprehensive Module Library
- Maintainability
- Translator from Turbo and
ANSI Pascal

NEW!

APPRENTICE PACKAGE \$99

Everything you need to begin producing reliable maintainable Modula-2 code. Includes the Compiler with 8087 support, integrated Editor, Linker, and BCD Module. We're also including FREE our Turbo Pascal to Modula-2 Translator!

NEW!

WIZARDS' PACKAGE \$199

This package contains our Plus Compiler—for professional programmers or for those who just want the best. The Plus Compiler with Integrated Editor requires 512K and takes advantage of the larger memory to increase compilation speed by 50%. Our Turbo Pascal to Modula-2 Translator is also included at no extra charge.

NEW!

MAGIC TOOLKIT \$99

We've put our most powerful development tools into one amazing Toolkit for use with either the Apprentice or Wizards' packages. Highlighted by our Runtime Debugger, the finest debugging tool available anywhere, the Toolkit also includes our Post Mortem Debugger, Disassembler, Cross Reference utility and Version which keeps track of different versions of one program. Our MAKE Utility figures out module dependencies and automatically selects those affected by code changes to minimize recompilation and relinking. We also provide source code of our major library modules for you to customize—or just play with.

WINDOW PACKAGE \$49

Now you can build true windowing into your Modula-2 code. Features virtual screens, color support, overlapping windows and a variety of borders.

ROM PACKAGE AND CROSS RUN TIME DEBUGGER \$299

For those who want to produce rommable code. You can even debug code running in ROM from your PC.

Turbo Pascal is a registered trademark of Borland International.

Call for information about our
VAX/VMS version, Site License, University
Discounts, Dealer & Distributor pricing.

To place an order call
toll-free:

800-231-7717

In California:

800-552-8885

YES! I want the spellbinding power
of LOGITECH Modula-2!

- | | |
|---|--------------|
| <input type="checkbox"/> Apprentice Package | \$99 |
| <input type="checkbox"/> Wizards' Package | \$199 |
| <input type="checkbox"/> Magic Toolkit | \$99 |
| <input type="checkbox"/> Window Package | \$49 |
| <input type="checkbox"/> ROM Pkg/Cross RTD | \$299 |

Add \$6.50 for shipping and handling. Calif. residents
add applicable sales tax. Prices valid in U.S. only.

Total Enclosed \$ _____

☐ VISA ☐ MasterCard ☐ Check Enclosed

Card Number _____ Expiration Date _____

Signature _____

Name _____

Address _____

City _____ State _____

Zip _____ Phone _____



LOGITECH

LOGITECH, Inc.
805 Veterans Blvd. Redwood City, CA 94063
Tel: 415-365-9852

In Europe:

LOGITECH SA, Switzerland
Tel: 41-21-879656 • Telex 458 217 Tech Ch

In Italy:

Tel: 39-2-215-5622

WIN A FREE TRIP TO Switzerland



HOMELAND OF MODULA-2

Return your Modula-2 Registration Card or a reasonable facsimile* postmarked between March 1, 1987 and May 31, 1987 to be included in a once-only drawing!

Grand Prize: One week excursion for 2 in Zurich, Switzerland including a guided tour of ETH, the University where Modula-2 was created by Niklaus Wirth. European customers may substitute a trip to Silicon Valley, California.

Second and Third Prizes: LOGITECH C7 Mouse or LOGITECH Bus Mouse with Paint & Draw software—a \$219 value, absolutely free!

*Write to Logitech, Inc. for a registration card facsimile.



Turbo C®

Turbo C: The fastest, most efficient and easy-to-use C compiler at any price

Compilation speed is more than 7000 lines a minute, which makes anything less than Turbo C an exercise in slow motion. Expect what only Borland delivers: Quality, Speed, Power and Price.

Turbo C: The C compiler for amateurs and professionals

If you're just beginning and you've "kinda wanted to learn C," now's your chance to do it the easy way. Like Turbo Pascal, Turbo C's got everything to get you going.

If you're already programming in C, switching to Turbo C will considerably increase your productivity and help make your programs both smaller and faster. Actually, writing in Turbo C is a highly productive and effective method—and we speak from experience. Eureka: The Solver™ and our new generation of software have been developed using Turbo C.

Turbo C: a complete interactive development environment

Free MicroCalc spreadsheet with source code

Like Turbo Pascal® and Turbo Prolog,™ Turbo C comes

with an interactive editor that will show you syntax errors right in your source code. Developing, debugging, and running a Turbo C program is a snap.

Turbo C: The C compiler everybody's been waiting for. Everybody but the competition

Borland's "Quality, Speed, Power and Price" commitment isn't idle corporate chatter. The \$99.95 price tag on Turbo C isn't a "typo," it's real. So if you'd like to learn C in a hurry, pick up the phone. If you're already using C, switch to Turbo C and see the difference for yourself.

System requirements

IBM PC, XT, AT or true compatibles. PC-DOS (MS-DOS) 2.0 or later. One floppy drive. 320K.

*Introductory price—good through July 1, 1987

Technical Specifications

- ✓ **Compiler:** One-pass compiler generating linkable object modules and inline assembler. Included is Borland's high performance "Turbo Linker." The object module is compatible with the PC-DOS linker. Supports tiny, small, compact, medium, large, and huge memory model libraries. Can mix models with near and far pointers. Includes floating point emulator (utilizes 8087/80287 if installed).
- ✓ **Interactive Editor:** The system includes a powerful, interactive full-screen text editor. If the compiler detects an error, the editor automatically positions the cursor appropriately in the source code.
- ✓ **Development Environment:** A powerful "Make" is included so that managing Turbo C program development is highly efficient. Also includes pull-down menus and windows.
- ✓ **Links with relocatable object modules** created using Borland's Turbo Prolog into a single program.
- ✓ **ANSI C compatible.**
- ✓ **Start-up routine source code included.**
- ✓ **Both command line and integrated environment versions included.**

Turbo C and Turbo Pascal are registered trademarks and Turbo Prolog and Eureka: The Solver are trademarks of Borland International, Inc. Microsoft C and MS-DOS are registered trademarks of Microsoft Corp. IBM, XT, and AT are registered trademarks of International Business Machines Corp. Copyright 1987 Borland International BI-1104

Sieve benchmark (25 iterations)

| | Turbo C | Microsoft® C | Lattice C |
|-----------------------|---------|--------------|-----------|
| Compile time | 3.89 | 16.37 | 13.90 |
| Compile and link time | 9.94 | 29.06 | 27.79 |
| Execution time | 5.77 | 9.51 | 13.79 |
| Object code size | 274 | 297 | 301 |
| Price | \$99.95 | \$450.00 | \$500.00 |

Benchmark run on a 6 Mhz IBM AT using Turbo C version 1.0 and the Turbo Linker version 1.0; Microsoft C version 4.0 and the MS overlay linker version 3.51; Lattice C version 3.1 and the MS object linker version 3.05.



BORLAND
INTERNATIONAL

4585 SCOTTS VALLEY DRIVE
SCOTTS VALLEY, CA 95066
(408) 438-8400 TELEX: 172373

Vive la différence

For the dealer nearest you or to order by phone call

(800)255-8008

in CA (800) 742-1133 in Canada (800) 237-1136

Circle no. 161 on reader service card.

Only \$99.95!*

